PROBLEMS IN PLANE AND SOLID GEOMETRY
v.1 Plane Geometry

Viktor Prasolov
translated and edited by Dimitry Leites

Abstract. This book has no equal. The priceless treasures of elementary geometry are nowhere else exposed in so complete and at the same time transparent form. The short solutions take barely $1.5 - 2$ times more space than the formulations, while still remaining *complete*, with no gaps whatsoever, although many of the problems are quite difficult. Only this enabled the author to squeeze about 2000 problems on plane geometry in the book of volume of ca 600 pages thus embracing practically all the known problems and theorems of elementary geometry.

The book contains non-standard geometric problems of a level higher than that of the problems usually offered at high school. The collection consists of two parts. It is based on three Russian editions of Prasolov's books on plane geometry.

The text is considerably modified for the English edition. Many new problems are added and detailed structuring in accordance with the methods of solution is adopted.

The book is addressed to high school students, teachers of mathematics, mathematical clubs, and college students.

Contents

Editor's preface

The enormous number of problems and theorems of elementary geometry was considered too wide to grasp in full even in the last century. Even nowadays the stream of new problems is still wide. (The majority of these problems, however, are either well-forgotten old ones or those recently pirated from a neighbouring country.)

Any attempt to collect an encyclopedia of all the problems seems to be doomed to failure for many reasons.

First of all, this is an impossible task because of the huge number of the problems, an enormity too vast to grasp. Second, even if this might have been possible, the book would be terribly overloaded, and therefore of no interest to anybody.

However, in the book *Problems in plane geometry* followed by *Problems in solid geometry* this task is successfully perfomed.

In the process of writing the book the author used the books and magazines published in the last century as well as modern ones. The reader can judge the completeness of the book by, for instance, the fact that *American Mathematical Monthly* yearly[1] publishes, as "new", 1–2 problems already published in the Russian editions of this book.

The book turned out to be of interest to a vast audience: about 400 000 copies of the first edition of each of the Parts (Parts 1 and 2 — Plane and Part 3 — Solid) were sold; the second edition, published 5 years later, had an even larger circulation, the total over 1 000 000 copies. The 3rd edition of *Problems in Plane Geometry* was issued in 1996 and the latest one in 2001.

The readers' interest is partly occasioned by a well-thought classification system.

The collection consists of three parts.

Part 1 covers classical subjects of plane geometry. It contains nearly 1000 problems with complete solutions and over 100 problems to be solved on one's own. Still more will be added for the English version of the book.

Part 2 includes more recent topics, geometric transformations and problems more suitable for contests and for use in mathematical clubs. The problems cover cuttings, colorings, the pigeonhole (or Dirichlet's) principle, induction, and so on.

Part 3 is devoted to solid geometry.

A rather detailed table of contents serves as a guide in the sea of geometric problems. It helps the experts to easily find what they need while the uninitiated can quickly learn what exactly is that they are interested in in geometry. Splitting the book into small sections (5 to 10 problems in each) made the book of interest to the readers of various levels.

FOR THE ENGLISH VERSION of the book about 150 new problems are already added and several hundred more of elementary and intermideate level problems will be added to make the number of more elementary problems sufficient to use the book in the ordinary school: the Russian editions are best suited for coaching for a mathematical Olympiad than for a regular class work: the level of difficulty increases rather fast.

Problems in each section are ordered difficulty-wise. The first problems of the sections are simple; they are a match for many. Here are some examples:

[1]Here are a few samples: v. 96, n. 5, 1989, p. 429–431 (here the main idea of the solution is the right illustration — precisely the picture from the back cover of the 1st Russian edition of *Problems in Solid Geometry*, Fig. to Problem 13.22); v. 96, n. 6, p. 527, Probl. E3192 corresponds to Problems 5.31 and 18.20 of *Problems in Plane Geometry* — with their two absolutely different solutions, the one to Problem 5.31, unknown to AMM, is even more interesting.

Plane 1.1. The bases of a trapezoid are a and b. Find the length of the segment that the diagonals of the trapezoid intersept on the trapezoid's midline.

Plane 1.52. Let AA_1 and BB_1 be the altitudes of $\triangle ABC$. Prove that $\triangle A_1B_1C$ is similar to $\triangle ABC$. What is the similarity coefficient?

Plane 2.1. A line segment connects vertex A of an acute $\triangle ABC$ with the center O of the circumscribed circle. The altitude AH is dropped from A. Prove that $\angle BAH = \angle OAC$.

Plane 6.1. Prove that if the center of the circle inscribed in a quadrilateral coincides with the intersection point of the quadrilateral's diagonals, then the quadrilateral is a rhombus.

Solid 1. Arrange 6 match sticks to get 4 equilateral triangles with side length equal to the length of a stick.

Solid 1.1. Consider the cube $ABCDA_1B_1C_1D_1$ with side length a. Find the angle and the distance between the lines A_1B and AC_1.

Solid 6.1. Is it true that in every tetrahedron the heights meet at one point?

The above problems are not difficult. The last problems in the sections are a challenge for the specialists in geometry. It is important that the passage from simple problems to complicated ones is not too long; there are no boring and dull long sequences of simple similar problems. (In the Russian edition these sequences are, perhaps, too short, so more problems are added.)

The final problems of the sections are usually borrowed from scientific journals. Here are some examples:

Plane 10.20. Prove that $l_a + l_b + m_c \leq \sqrt{3}p$, where l_a, l_b are the lengths of the bisectors of the angles $\angle A$ and $\angle B$ of the triangle $\triangle ABC$, m_c is the length of the median of the side AB, and p is the semiperimeter.

Plane 19.55. Let O be the center of the circle inscribed in $\triangle ABC$, K the Lemoine's point, P and Q Brocard's points. Prove that P and Q belong to the circle with diameter KO and that $OP = OQ$.

Plane 22.29. The numbers $\alpha_1, \dots, \alpha_n$, whose sum is equal to $(n-2)\pi$, satisfy inequalities $0 < \alpha_i < 2\pi$. Prove that there exists an n-gon $A_1 \dots A_n$ with the angles $\alpha_1, \dots, \alpha_n$ at the vertices $A_1, \dots, A_n$, respectively.

Plane 24.12. Prove that for any n there exists a circle on which there lie precisely n points with integer coordinates.

Solid 4.48. Consider several arcs of great circles on a sphere with the sum of their angle measures $< \pi$. Prove that there exists a plane that passes through the center of the sphere but does not intersect any of these arcs.

Solid 14.22. Prove that if the centers of the escribed spheres of a tetrahedron belong to the circumscribed sphere, then the tetrahedron's faces are equal.

Solid 15.34. In space, consider 4 points not in one plane. How many various parallelipipeds with vertices in these points are there?

From the Author's preface

The book underwent extensive revision. The solutions to many of the problems were rewritten and about 600 new problems were added, particularly those concerning the geometry of the triangle. I was greatly influenced in the process by the second edition of the book by I. F. Sharygin *Problems on Geometry. Plane geometry*, Nauka, Moscow,1986 and a wonderful and undeservedly forgotten book by D. Efremov *New Geometry of the Triangle*, Matezis, Odessa, 1902.

The present book can be used not only as a source of optional problems for students but also as a self-guide for those who wish (or have no other choice but) to study geometry independently. Detailed headings are provided for the reader's convenience. Problems in the two parts of Plane are spread over 29 Chapters, each Chapter comprising 6 to 14 sections. The classification is based on the methods used to solve geometric problems. The purpose of the division is basically to help the reader find his/her bearings in this large array of problems. Otherwise the huge number of problems might be somewhat depressingly overwhelming.

Advice and comments given by Academician A. V. Pogorelov, and Professors A. M. Abramov, A. Yu. Vaintrob, N. B. Vasiliev, N. P. Dolbilin, and S. Yu. Orevkov were a great help to me in preparing the first Soviet edition. I wish to express my sincere gratitude to all of them.

To save space, sections with background only contain the material directly pertinent to the respective chapter. It is collected just to remind the reader of notations. Therefore, the basic elements of a triangle are only defined in chapter 5, while in chapter 1 we assume that their definition is known. For the reader's convenience, cross references in this translation are facilitated by a very detailed index.

Chapter 1. SIMILAR TRIANGLES

Background

1) Triangle ABC is said to be *similar* to triangle $A_1B_1C_1$ (we write $\triangle ABC \sim \triangle A_1B_1C_1$) if and only if one of the following equivalent conditions is satisfied:

a) $AB : BC : CA = A_1B_1 : B_1C_1 : C_1A_1$;

b) $AB : BC = A_1B_1 : B_1C_1$ and $\angle ABC = \angle A_1B_1C_1$;

c) $\angle ABC = \angle A_1B_1C_1$ and $\angle BAC = \angle B_1A_1C_1$.

2) *Triangles AB_1C_1 and AB_2C_2 cut off from an angle with vertex A by parallel lines are similar and $AB_1 : AB_2 = AC_1 : AC_2$* (here points B_1 and B_2 lie on one leg of the angle and C_1 and C_2 on the other leg).

3) A *midline* of a triangle is the line connecting the midpoints of two of the triangle's sides. *The midline is parallel to the third side and its length is equal to a half length of the third side.*

The *midline of a trapezoid* is the line connecting the midpoints of the trapezoid's sides. *This line is parallel to the bases of the trapezoid and its length is equal to the halfsum of their lengths.*

4) *The ratio of the areas of similar triangles is equal to the square of the similarity coefficient*, i.e., to the squared ratio of the lengths of respective sides. This follows, for example, from the formula $S_{ABC} = \frac{1}{2} AB \cdot AC \sin \angle A$.

5) Polygons $A_1A_2 \dots A_n$ and $B_1B_2 \dots B_n$ are called *similar* if $A_1A_2 : A_2A_3 : \dots : A_nA_1 = B_1B_2 : B_2B_3 : \dots : B_nB_1$ and the angles at the vertices $A_1, \dots, A_n$ are equal to the angles at the vertices $B_1, \dots, B_n$, respectively.

The ratio of the respective diagonals of similar polygons is equal to the similarity coefficient. For the circumscribed similar polygons, the ratio of the radii of the inscribed circles is also equal to the similarity coefficient.

Introductory problems

1. Consider heights AA_1 and BB_1 in acute triangle ABC. Prove that $A_1C \cdot BC = B_1C \cdot AC$.

2. Consider height CH in right triangle ABC with right angle $\angle C$. Prove that $AC^2 = AB \cdot AH$ and $CH^2 = AH \cdot BH$.

3. Prove that the medians of a triangle meet at one point and this point divides each median in the ratio of $2 : 1$ counting from the vertex.

4. On side BC of $\triangle ABC$ point A_1 is taken so that $BA_1 : A_1C = 2 : 1$. What is the ratio in which median CC_1 divides segment AA_1?

5. Square $PQRS$ is inscribed into $\triangle ABC$ so that vertices P and Q lie on sides AB and AC and vertices R and S lie on BC. Express the length of the square's side through a and h_a.

§1. Line segments intercepted by parallel lines

1.1. Let the lengths of bases AD and BC of trapezoid $ABCD$ be a and b ($a > b$).

a) Find the length of the segment that the diagonals intercept on the midline.

b) Find the length of segment MN whose endpoints divide AB and CD in the ratio of $AM : MB = DN : NC = p : q$.

1.2. Prove that the midpoints of the sides of an arbitrary quadrilateral are vertices of a parallelogram. For what quadrilaterals this parallelogram is a rectangle, a rhombus, a square?

1.3. Points A_1 and B_1 divide sides BC and AC of $\triangle ABC$ in the ratios $BA_1 : A_1C = 1 : p$ and $AB_1 : B_1C = 1 : q$, respectively. In what ratio is AA_1 divided by BB_1?

1.4. Straight lines AA_1 and BB_1 pass through point P of median CC_1 in $\triangle ABC$ (A_1 and B_1 lie on sides BC and CA, respectively). Prove that $A_1B_1 \parallel AB$.

1.5. The straight line which connects the intersection point P of the diagonals in quadrilateral $ABCD$ with the intersection point Q of the lines AB and CD bisects side AD. Prove that it also bisects BC.

1.6. A point P is taken on side AD of parallelogram $ABCD$ so that $AP : AD = 1 : n$; let Q be the intersection point of AC and BP. Prove that $AQ : AC = 1 : (n + 1)$.

1.7. The vertices of parallelogram $A_1B_1C_1D_1$ lie on the sides of parallelogram $ABCD$ (point A_1 lies on AB, B_1 on BC, etc.). Prove that the centers of the two parallelograms coincide.

1.8. Point K lies on diagonal BD of parallelogram $ABCD$. Straight line AK intersects lines BC and CD at points L and M, respectively. Prove that $AK^2 = LK \cdot KM$.

1.9. One of the diagonals of a quadrilateral inscribed in a circle is a diameter of the circle. Prove that (the lengths of) the projections of the opposite sides of the quadrilateral on the other diagonal are equal.

1.10. Point E on base AD of trapezoid $ABCD$ is such that $AE = BC$. Segments CA and CE intersect diagonal BD at O and P, respectively. Prove that if $BO = PD$, then $AD^2 = BC^2 + AD \cdot BC$.

1.11. On a circle centered at O, points A and B single out an arc of 60°. Point M belongs to this arc. Prove that the straight line passing through the midpoints of MA and OB is perpendicular to that passing through the midpoints of MB and OA.

1.12. a) Points A, B, and C lie on one straight line; points A_1, B_1, and C_1 lie on another straight line. Prove that if $AB_1 \parallel BA_1$ and $AC_1 \parallel CA_1$, then $BC_1 \parallel CB_1$.

b) Points A, B, and C lie on one straight line and A_1, B_1, and C_1 are such that $AB_1 \parallel BA_1$, $AC_1 \parallel CA_1$, and $BC_1 \parallel CB_1$. Prove that A_1, B_1 and C_1 lie on one line.

1.13. In $\triangle ABC$ bisectors AA_1 and BB_1 are drawn. Prove that the distance from any point M of A_1B_1 to line AB is equal to the sum of distances from M to AC and BC.

1.14. Let M and N be the midpoints of sides AD and BC in rectangle $ABCD$. Point P lies on the extension of DC beyond D; point Q is the intersection point of PM and AC. Prove that $\angle QNM = \angle MNP$.

1.15. Points K and L are taken on the extensions of the bases AD and BC of trapezoid $ABCD$ beyond A and C, respectively. Line segment KL intersects sides AB and CD at M and N, respectively; KL intersects diagonals AC and BD at O and P, respectively. Prove that if $KM = NL$, then $KO = PL$.

1.16. Points P, Q, R, and S on sides AB, BC, CD and DA, respectively, of convex quadrilateral $ABCD$ are such that $BP : AB = CR : CD = \alpha$ and $AS : AD = BQ : BC = \beta$. Prove that PR and QS are divided by their intersection point in the ratios $\beta : (1 - \beta)$ and $\alpha : (1 - \alpha)$, respectively.

§2. The ratio of sides of similar triangles

1.17. a) In $\triangle ABC$ bisector BD of the external or internal angle $\angle B$ is drawn. Prove that $AD : DC = AB : BC$.

b) Prove that the center O of the circle inscribed in $\triangle ABC$ divides the bisector AA_1 in the ratio of $AO : OA_1 = (b + c) : a$, where a, b and c are the lengths of the triangle's sides.

1.18. The lengths of two sides of a triangle are equal to a while the length of the third side is equal to b. Calculate the radius of the circumscribed circle.

1.19. A straight line passing through vertex A of square $ABCD$ intersects side CD at E and line BC at F. Prove that $\frac{1}{AE^2} + \frac{1}{AF^2} = \frac{1}{AB^2}$.

1.20. Given points B_2 and C_2 on heights BB_1 and CC_1 of $\triangle ABC$ such that $AB_2C = AC_2B = 90^\circ$, prove that $AB_2 = AC_2$.

1.21. A circle is inscribed in trapezoid $ABCD$ ($BC \parallel AD$). The circle is tangent to sides AB and CD at K and L, respectively, and to bases AD and BC at M and N, respectively.

a) Let Q be the intersection point of BM and AN. Prove that $KQ \parallel AD$.

b) Prove that $AK \cdot KB = CL \cdot LD$.

1.22. Perpendiculars AM and AN are dropped to sides BC and CD of parallelogram $ABCD$ (or to their extensions). Prove that $\triangle MAN \sim \triangle ABC$.

1.23. Straight line l intersects sides AB and AD of parallelogram $ABCD$ at E and F, respectively. Let G be the intersection point of l with diagonal AC. Prove that $\frac{AB}{AE} + \frac{AD}{AF} = \frac{AC}{AG}$.

1.24. Let AC be the longer of the diagonals in parallelogram $ABCD$. Perpendiculars CE and CF are dropped from C to the extensions of sides AB and AD, respectively. Prove that $AB \cdot AE + AD \cdot AF = AC^2$.

1.25. Angles α and β of $\triangle ABC$ are related as $3\alpha + 2\beta = 180^\circ$. Prove that $a^2 + bc = c^2$.

1.26. The endpoints of segments AB and CD are gliding along the sides of a given angle, so that straight lines AB and CD are moving parallelly (i.e., each line moves parallelly to itself) and segments AB and CD intersect at a point, M. Prove that the value of $\frac{AM \cdot BM}{CM \cdot DM}$ is a constant.

1.27. Through an arbitrary point P on side AC of $\triangle ABC$ straight lines are drawn parallelly to the triangle's medians AK and CL. The lines intersect BC and AB at E and F, respectively. Prove that AK and CL divide EF into three equal parts.

1.28. Point P lies on the bisector of an angle with vertex C. A line passing through P intercepts segments of lengths a and b on the angle's legs. Prove that the value of $\frac{1}{a} + \frac{1}{b}$ does not depend on the choice of the line.

1.29. A semicircle is constructed outwards on side BC of an equilateral triangle ABC as on the diameter. Given points K and L that divide the semicircle into three equal arcs, prove that lines AK and AL divide BC into three equal parts.

1.30. Point O is the center of the circle inscribed in $\triangle ABC$. On sides AC and BC points M and K, respectively, are selected so that $BK \cdot AB = BO^2$ and $AM \cdot AB = AO^2$. Prove that M, O and K lie on one straight line.

1.31. Equally oriented similar triangles AMN, NBM and MNC are constructed on segment MN (Fig. 1).

Prove that $\triangle ABC$ is similar to all these triangles and the center of its curcumscribed circle is equidistant from M and N.

1.32. Line segment BE divides $\triangle ABC$ into two similar triangles, their similarity ratio being equal to $\sqrt{3}$.

Find the angles of $\triangle ABC$.



Figure 1 (1.31)

§3. The ratio of the areas of similar triangles

1.33. A point E is taken on side AC of $\triangle ABC$. Through E pass straight lines DE and EF parallel to sides BC and AB, respectively; D and E are points on AB and BC, respectively. Prove that $S_{BDEF} = 2\sqrt{S_{ADE} \cdot S_{EFG}}$.

1.34. Points M and N are taken on sides AB and CD, respectively, of trapezoid $ABCD$ so that segment MN is parallel to the bases and divides the area of the trapezoid in halves. Find the length of MN if $BC = a$ and $AD = b$.

1.35. Let Q be a point inside $\triangle ABC$. Three straight lines are pass through Q parallelly to the sides of the triangle. The lines divide the triangle into six parts, three of which are triangles of areas S_1, S_2 and S_3. Prove that the area of $\triangle ABC$ is equal to $\left(\sqrt{S_1} + \sqrt{S_2} + \sqrt{S_3}\right)^2$.

1.36. Prove that the area of a triangle whose sides are equal to the medians of a triangle of area S is equal to $\frac{3}{4}S$.

1.37. a) Prove that the area of the quadrilateral formed by the midpoints of the sides of convex quadrilateral $ABCD$ is half that of $ABCD$.

b) Prove that if the diagonals of a convex quadrilateral are equal, then its area is the product of the lengths of the segments which connect the midpoints of its opposite sides.

1.38. Point O lying inside a convex quadrilateral of area S is reflected symmetrically through the midpoints of its sides. Find the area of the quadrilateral with its vertices in the images of O under the reflections.

§4. Auxiliary equal triangles

1.39. In right triangle ABC with right angle $\angle C$, points D and E divide leg BC of into three equal parts. Prove that if $BC = 3AC$, then $\angle AEC + \angle ADC + \angle ABC = 90°$.

1.40. Let K be the midpoint of side AB of square $ABCD$ and let point L divide diagonal AC in the ratio of $AL : LC = 3 : 1$. Prove that $\angle KLD$ is a right angle.

1.41. In square $ABCD$ straight lines l_1 and l_2 pass through vertex A. The lines intersect the square's sides. Perpendiculars BB_1, BB_2, DD_1, and DD_2 are dropped to these lines. Prove that segments B_1B_2 and D_1D_2 are equal and perpendicular to each other.

1.42. Consider an isosceles right triangle ABC with $CD = CE$ and points D and E on sides CA and CB, respectively. Extensions of perpendiculars dropped from D and C to AE intersect the hypotenuse AB at K and L. Prove that $KL = LB$.

1.43. Consider an inscribed quadrilateral $ABCD$. The lengths of sides AB, BC, CD, and DA are a, b, c, and d, respectively. Rectangles are constructed outwards on the sides of the quadrilateral; the sizes of the rectangles are $a \times c$, $b \times d$, $c \times a$ and $d \times b$, respectively. Prove that the centers of the rectangles are vertices of a rectangle.

1.44. Hexagon $ABCDEF$ is inscribed in a circle of radius R centered at O; let $AB = CD = EF = R$. Prove that the intersection points, other than O, of the pairs of circles circumscribed about $\triangle BOC$, $\triangle DOE$ and $\triangle FOA$ are the vertices of an equilateral triangle with side R.

* * *

1.45. Equilateral triangles BCK and DCL are constructed outwards on sides BC and CD of parallelogram $ABCD$. Prove that AKL is an equilateral triangle.

1.46. Squares are constructed outwards on the sides of a parallelogram. Prove that their centers form a square.

1.47. Isosceles triangles with angles 2α, 2β and 2γ at vertices A', B' and C' are constructed outwards on the sides of triangle ABC; let $\alpha + \beta + \gamma = 180^\circ$. Prove that the angles of $\triangle A'B'C'$ are equal to α, β and γ.

1.48. On the sides of $\triangle ABC$ as on bases, isosceles similar triangles AB_1C and AC_1B are constructed outwards and an isosceles triangle BA_1C is constructed inwards. Prove that $AB_1A_1C_1$ is a parallelogram.

1.49. a) On sides AB and AC of $\triangle ABC$ equilateral triangles ABC_1 and AB_1C are constructed outwards; let $\angle C_1 = \angle B_1 = 90^\circ$, $\angle ABC_1 = \angle ACB_1 = \varphi$; let M be the midpoint of BC. Prove that $MB_1 = MC_1$ and $\angle B_1MC_1 = 2\varphi$.

b) Equilateral triangles are constructed outwards on the sides of $\triangle ABC$. Prove that the centers of the triangles constructed form an equilateral triangle whose center coincides with the intersection point of the medians of $\triangle ABC$.

1.50. Isosceles triangles AC_1B and AB_1C with an angle φ at the vertex are constructed outwards on the unequal sides AB and AC of a scalene triangle $\triangle ABC$.

a) Let M be a point on median AA_1 (or on its extension), let M be equidistant from B_1 and C_1. Prove that $\angle B_1MC_1 = \varphi$.

b) Let O be a point of the midperpendicular to segment BC, let O be equidistant from B_1 and C_1. Prove that $\angle B_1OC = 180^\circ - \varphi$.

1.51. Similar rhombuses are constructed outwards on the sides of a convex rectangle $ABCD$, so that their acute angles (equal to α) are adjacent to vertices A and C. Prove that the segments which connect the centers of opposite rhombuses are equal and the angle between them is equal to α.

§5. The triangle determined by the bases of the heights

1.52. Let AA_1 and BB_1 be heights of $\triangle ABC$. Prove that $\triangle A_1B_1C \sim \triangle ABC$. What is the similarity coefficient?

1.53. Height CH is dropped from vertex C of acute triangle ABC and perpendiculars HM and HN are dropped to sides BC and AC, respectively. Prove that $\triangle MNC \sim \triangle ABC$.

1.54. In $\triangle ABC$ heights BB_1 and CC_1 are drawn.

a) Prove that the tangent at A to the circumscribed circle is parallel to B_1C_1.

b) Prove that $B_1C_1 \perp OA$, where O is the center of the circumscribed circle.

1.55. Points A_1, B_1 and C_1 are taken on the sides of an acute triangle ABC so that segments AA_1, BB_1 and CC_1 meet at H. Prove that $AH \cdot A_1H = BH \cdot B_1H = CH \cdot C_1H$ if and only if H is the intersection point of the heights of $\triangle ABC$.

1.56. a) Prove that heights AA_1, BB_1 and CC_1 of acute triangle ABC bisect the angles of $\triangle A_1B_1C_1$.

b) Points C_1, A_1 and B_1 are taken on sides AB, BC and CA, respectively, of acute triangle ABC. Prove that if $\angle B_1A_1C = \angle BA_1C_1$, $\angle A_1B_1C = \angle AB_1C_1$ and $\angle A_1C_1B = \angle AC_1B_1$, then points A_1, B_1 and C_1 are the bases of the heights of $\triangle ABC$.

1.57. Heights AA_1, BB_1 and CC_1 are drawn in acute triangle ABC. Prove that the point symmetric to A_1 through AC lies on B_1C_1.

1.58. In acute triangle ABC, heights AA_1, BB_1 and CC_1 are drawn. Prove that if $A_1B_1 \parallel AB$ and $B_1C_1 \parallel BC$, then $A_1C_1 \parallel AC$.

1.59. Let p be the semiperimeter of acute triangle ABC and q the semiperimeter of the triangle formed by the bases of the heights of $\triangle ABC$. Prove that $p : q = R : r$, where R and r are the radii of the circumscribed and the inscribed circles, respectively, of $\triangle ABC$.

§6. Similar figures

1.60. A circle of radius r is inscribed in a triangle. The straight lines tangent to the circle and parallel to the sides of the triangle are drawn; the lines cut three small triangles off the triangle. Let r_1, r_2 and r_3 be the radii of the circles inscribed in the small triangles. Prove that $r_1 + r_2 + r_3 = r$.

1.61. Given $\triangle ABC$, draw two straight lines x and y such that the sum of lengths of the segments MX_M and MY_M drawn parallel to x and y from a point M on AC to their intersections with sides AB and BC is equal to 1 for any M.

1.62. In an isosceles triangle ABC perpendicular HE is dropped from the midpoint of base BC to side AC. Let O be the midpoint of HE. Prove that lines AO and BE are perpendicular to each other.

1.63. Prove that projections of the base of a triangle's height to the sides between which it lies and on the other two heights lie on the same straight line.

1.64. Point B lies on segment AC; semicircles S_1, S_2, and S_3 are constructed on one side of AC, as on diameter. Let D be a point on S_3 such that $BD \perp AC$. A common tangent line to S_1 and S_2 touches these semicircles at F and E, respectively.

a) Prove that EF is parallel to the tangent to S_3 passing through D.

b) Prove that $BFDE$ is a rectangle.

1.65. Perpendiculars MQ and MP are dropped from an arbitrary point M of the circle circumscribed about rectangle $ABCD$ to the rectangle's two opposite sides; the perpendiculars MR and MT are dropped to the extensions of the other two sides. Prove that lines $PR \perp QT$ and the intersection point of PR and QT belongs to a diagonal of $ABCD$.

1.66. Two circles enclose non-intersecting areas. Common tangent lines to the two circles, one external and one internal, are drawn. Consider two straight lines each of which passes through the tangent points on one of the circles. Prove that the intersection point of the lines lies on the straight line that connects the centers of the circles.

Problems for independent study

1.67. The (length of the) base of an isosceles triangle is a quarter of its perimeter. From an arbitrary point on the base straight lines are drawn parallel to the sides of the triangle. How many times is the perimeter of the triangle greater than that of the parallelogram?

1.68. The diagonals of a trapezoid are mutually perpendicular. The intersection point divides the diagonals into segments. Prove that the product of the lengths of the trapezoid's bases is equal to the sum of the products of the lengths of the segments of one diagonal and those of another diagonal.

1.69. A straight line is drawn through the center of a unit square. Calculate the sum of the squared distances between the four vertices of the square and the line.

1.70. Points A_1, B_1 and C_1 are symmetric to the center of the circumscribed circle of $\triangle ABC$ through the triangle's sides. Prove that $\triangle ABC = \triangle A_1B_1C_1$.

1.71. Prove that if $\angle BAC = 2\angle ABC$, then $BC^2 = (AC + AB)AC$.

1.72. Consider points A, B, C and D on a line l. Through A, B and through C, D parallel straight lines are drawn. Prove that the diagonals of the parallelograms thus formed (or their extensions) intersect l at two points that do not depend on parallel lines but depend on points A, B, C, D only.

1.73. In $\triangle ABC$ bisector AD and midline A_1C_1 are drawn. They intersect at K. Prove that $2A_1K = |b - c|$.

1.74. Points M and N are taken on sides AD and CD of parallelogram $ABCD$ such that $MN \parallel AC$. Prove that $S_{ABM} = S_{CBN}$.

1.75. On diagonal AC of parallelogram $ABCD$ points P and Q are taken so that $AP = CQ$. Let M be such that $PM \parallel AD$ and $QM \parallel AB$. Prove that M lies on diagonal BD.

1.76. Consider a trapezoid with bases AD and BC. Extensions of the sides of $ABCD$ meet at point O. Segment EF is parallel to the bases and passes through the intersection point of the diagonals. The endpoints of EF lie on AB and CD. Prove that $AE : CF = AO : CO$.

1.77. Three straight lines parallel to the sides of the given triangle cut three triangles off it leaving an equilateral hexagon. Find the length of the side of the hexagon if the lengths of the triangle's sides are a, b and c.

1.78. Three straight lines parallel to the sides of a triangle meet at one point, the sides of the triangle cutting off the line segments of length x each. Find x if the lengths of the triangle's sides are a, b and c.

1.79. Point P lies inside $\triangle ABC$ and $\angle ABP = \angle ACP$. On straight lines AB and AC, points C_1 and B_1 are taken so that $BC_1 : CB_1 = CP : BP$. Prove that one of the diagonals of the parallelogram whose two sides lie on lines BP and CP and two other sides (or their extensions) pass through B_1 and C_1 is parallel to BC.

Solutions

1.1. a) Let P and Q be the midpoints of AB and CD; let K and L be the intersection points of PQ with the diagonals AC and BD, respectively. Then $PL = \frac{a}{2}$ and $PK = \frac{1}{2}b$ and so $KL = PL - PK = \frac{1}{2}(a - b)$.

b) Take point F on AD such that $BF \parallel CD$. Let E be the intersection point of MN with BF. Then

$$MN = ME + EN = \frac{q \cdot AF}{p+q} + b = \frac{q(a-b) + (p+q)b}{p+q} = \frac{qa + pb}{p+q}.$$

1.2. Consider quadrilateral $ABCD$. Let K, L, M and N be the midpoints of sides AB, BC, CD and DA, respectively. Then $KL = MN = \frac{1}{2}AC$ and $KL \parallel MN$, that is $KLMN$ is a parallelogram. It becomes clear now that $KLMN$ is a *rectangle* if the diagonals AC and BD are perpendicular, a *rhombus* if $AC = BD$, and a *square* if AC and BD are of equal length and perpendicular to each other.

1.3. Denote the intersection point of AA_1 with BB_1 by O. In $\triangle B_1BC$ draw segment A_1A_2 so that $A_1A_2 \parallel BB_1$. Then $\frac{B_1C}{B_1A_2} = 1 + p$ and so $AO : OA_1 = AB_1 : B_1A_2 = B_1C : qB_1A_2 = (1 + p) : q$.

1.4. Let A_2 be the midpoint of A_1B. Then $CA_1 : A_1A_2 = CP : PC_1$ and $A_1A_2 : A_1B = 1 : 2$. So $CA_1 : A_1B = CP : 2PC_1$. Similarly, $CB_1 : B_1A = CP : 2PC_1 = CA_1 : A_1B$.

1.5. Point P lies on the median QM of $\triangle AQD$ (or on its extension). It is easy to verify that the solution of Problem 1.4 remains correct also for the case when P lies on the extension of the median. Consequently, $BC \parallel AD$.

1.6. We have $AQ : QC = AP : BC = 1 : n$ because $\triangle AQP \sim \triangle CQB$. So $AC = AQ + QC = (n+1)AQ$.

1.7. The center of $A_1B_1C_1D_1$ being the midpoint of B_1D_1 belongs to the line segment which connects the midpoints of AB and CD. Similarly, it belongs to the segment which connects the midpoints of BC and AD. The intersection point of the segments is the center of $ABCD$.

1.8. Clearly, $AK : KM = BK : KD = LK : AK$, that is $AK^2 = LK \cdot KM$.

1.9. Let AC be the diameter of the circle circumscribed about $ABCD$. Drop perpendiculars AA_1 and CC_1 to BD (Fig. 2).



Figure 2 (Sol. 1.9)

We must prove that $BA_1 = DC_1$. Drop perpendicular OP from the center O of the circumscribed circle to BD. Clearly, P is the midpoint of BD. Lines AA_1, OP and CC_1 are parallel to each other and $AO = OC$. So $A_1P = PC_1$ and, since P is the midpoint of BD, it follows that $BA_1 = DC_1$.

1.10. We see that $BO : OD = DP : PB = k$, because $BO = PD$. Let $BC = 1$. Then $AD = k$ and $ED = \frac{1}{k}$. So $k = AD = AE + ED = 1 + \frac{1}{k}$, that is $k^2 = 1 + k$. Finally, observe that $k^2 = AD^2$ and $1 + k = BC^2 + BC \cdot AD$.

1.11. Let C, D, E and F be the midpoints of sides AO, OB, BM and MA, respectively, of quadrilateral $AOMB$. Since $AB = MO = R$, where R is the radius of the given circle, $CDEF$ is a rhombus by Problem 1.2. Hence, $CE \perp DF$.

1.12. a) If the lines containing the given points are parallel, then the assertion of the problem is obviously true. We assume that the lines meet at O. Then $OA : OB = OB_1 : OA_1$ and $OC : OA = OA_1 : OC_1$. Hence, $OC : OB = OB_1 : OC_1$ and so $BC_1 \parallel CB_1$ (the ratios of the segment should be assumed to be *oriented*).

b) Let AB_1 and CA_1 meet at D, let CB_1 and AC_1 meet at E. Then $CA_1 : A_1D = CB : BA = EC_1 : C_1A$. Since $\triangle CB_1D \sim \triangle EB_1A$, points A_1, B_1 and C_1 lie on the same line.

1.13. A point that lies on the bisector of an angle is equidistant from the angle's legs. Let a be the distance from point A_1 to lines AC and AB, let b be the distance from point B_1 to lines AB and BC. Further, let $A_1M : B_1M = p : q$, where $p + q = 1$. Then the distances from point M to lines AC and BC are equal to qa and pb, respectively. On the other hand, by Problem 1.1 b) the distance from point M to line AB is equal to $qa + pb$.

1.14. Let the line that passes through the center O of the given rectangle parallel to BC intersect line segment QN at point K (Fig. 3).



Figure 3 (Sol. 1.14)

Since $MO \parallel PC$, it follows that $QM : MP = QO : OC$ and, since $KO \parallel BC$, it follows that $QO : OC = QK : KN$. Therefore, $QM : MP = QK : KN$, i.e., $KM \parallel NP$. Hence, $\angle MNP = \angle KMO = \angle QNM$.

1.15. Let us draw through point M line EF so that $EF \parallel CD$ (points E and F lie on lines BC and AD). Then $PL : PK = BL : KD$ and $OK : OL = KA : CL = KA : KF = BL : EL$. Since $KD = EL$, we have $PL : PK = OK : OL$ and, therefore, $PL = OK$.

1.16. Consider parallelogram $ABCD_1$. We may assume that points D and D_1 do not coincide (otherwise the statement of the problem is obvious). On sides AD_1 and CD_1 take points S_1 and R_1, respectively, so that $SS_1 \parallel DD_1$ and $RR_1 \parallel DD_1$. Let segments PR_1 and QS_1 meet at N; let N_1 and N_2 be the intersection points of the line that passes through N parallel to DD_1 with segments PR and QS, respectively.

Then $\overrightarrow{N_1N} = \beta\overrightarrow{RR_1} = \alpha\beta\overrightarrow{DD_1}$ and $\overrightarrow{N_2N} = \alpha\overrightarrow{SS_1} = \alpha\beta\overrightarrow{DD_1}$. Hence, segments PR and QS meet at $N_1 = N_2$. Clearly, $PN_1 : PR = PN : PR_1 = \beta$ and $QN_2 : QS = \alpha$.

Remark. If $\alpha = \beta$, there is a simpler solution. Since $BP : BA = BQ : BC = \alpha$, it follows that $PQ \parallel AC$ and $PQ : AC = \alpha$. Similarly, $RS \parallel AC$ and $RS : AC = 1 - \alpha$. Therefore, segments PR and QS are divided by their intersection point in the ratio of $\alpha : (1 - \alpha)$.

1.17. a) From vertices A and C drop perpendiculars AK and CL to line BD. Since $\angle CBL = \angle ABK$ and $\angle CDL = \angle KDA$, we see that $\triangle BLC \sim \triangle BKA$ and $\triangle CLD \sim \triangle AKD$. Therefore, $AD : DC = AK : CL = AB : BC$.

b) Taking into account that $BA_1 : A_1C = BA : AC$ and $BA_1 + A_1C = BC$ we get $BA_1 = \frac{ac}{b+c}$. Since BO is the bisector of triangle ABA_1, it follows that $AO : OA_1 = AB : BA_1 = (b + c) : a$.

1.18. Let O be the center of the circumscribed circle of isosceles triangle ABC, let B_1 be the midpoint of base AC and A_1 the midpoint of the lateral side BC. Since $\triangle BOA_1 \sim \triangle BCB_1$, it follows that $BO : BA_1 = BC : BB_1$ and, therefore, $R = BO = \frac{a^2}{\sqrt{4a^2-b^2}}$.

1.19. If $\angle EAD = \varphi$, then $AE = \frac{AD}{\cos\varphi} = \frac{AB}{\cos\varphi}$ and $AF = \frac{AB}{\sin\varphi}$. Therefore,

$$\frac{1}{AE^2} + \frac{1}{AF^2} = \frac{\cos^2\varphi + \sin^2\varphi}{AB^2} = \frac{1}{AB^2}.$$

1.20. It is easy to verify that $AB_2^2 = AB_1 \cdot AC = AC_1 \cdot AB = AC_2^2$.

1.21. a) Since $BQ : QM = BN : AM = BK : AK$, we have: $KQ \parallel AM$.

b) Let O be the center of the inscribed circle. Since $\angle CBA + \angle BAD = 180^\circ$, it follows that $\angle ABO + \angle BAO = 90^\circ$. Therefore, $\triangle AKO \sim \triangle OKB$, i.e., $AK : KO = OK : KB$. Consequently, $AK \cdot KB = KO^2 = R^2$, where R is the radius of the inscribed circle. Similarly, $CL \cdot LD = R^2$.

1.22. If angle $\angle ABC$ is obtuse (resp. acute), then angle $\angle MAN$ is also obtuse (resp. acute). Moreover, the legs of these angles are mutually perpendicular. Therefore, $\angle ABC = \angle MAN$. Right triangles ABM and ADN have equal angles $\angle ABM = \angle ADN$, therefore, $AM : AN = AB : AD = AB : CB$, i.e., $\triangle ABC \sim \triangle MAN$.

1.23. On diagonal AC, take points D' and B' such that $BB' \parallel l$ and $DD' \parallel l$. Then $AB : AE = AB' : AG$ and $AD : AF = AD' : AG$. Since the sides of triangles ABB' and CDD' are pairwise parallel and $AB = CD$, these triangles are equal and $AB' = CD'$. Therefore,

$$\frac{AB}{AE} + \frac{AD}{AF} = \frac{AB'}{AG} + \frac{AD'}{AG} = \frac{CD' + AD'}{AG} = \frac{AC}{AG}.$$

1.24. Let us drop from vertex B perpendicular BG to AC (Fig. 4).



Figure 4 (Sol. 1.24)

Since triangles ABG and ACE are similar, $AC \cdot AG = AE \cdot AB$. Lines AF and CB are parallel, consequently, $\angle GCB = \angle CAF$. We also infer that right triangles CBG and ACF are similar and, therefore, $AC \cdot CG = AF \cdot BC$. Summing the equalities obtained we get

$$AC \cdot (AG + CG) = AE \cdot AB + AF \cdot BC.$$

Since $AG + CG = AC$, we get the equality desired.

1.25. Since $\alpha + \beta = 90^\circ - \frac{1}{2}\alpha$, it follows that $\gamma = 180^\circ - \alpha - \beta = 90^\circ + \frac{1}{2}\alpha$. Therefore, it is possible to find point D on side AB so that $\angle ACD = 90^\circ - \frac{1}{2}\alpha$, i.e., $AC = AD$. Then $\triangle ABC \sim \triangle CBD$ and, therefore, $BC : BD = AB : CB$, i.e., $a^2 = c(c - b)$.

1.26. As segments AB and CD move, triangle AMC is being replaced by another triangle similar to the initial one. Therefore, the quantity $\frac{AM}{CM}$ remains a constant. Analogously, $\frac{BM}{DM}$ remains a constant.

1.27. Let medians meet at O; denote the intersection points of median AK with lines FP and FE by Q and M, respectively; denote the intersection points of median CL with lines EP and FE by R and N, respectively (Fig. 5).

Clearly, $FM : FE = FQ : FP = LO : LC = 1 : 3$, i.e., $FM = \frac{1}{3}FE$. Similarly, $EN = \frac{1}{3}FE$.



Figure 5 (Sol. 1.27)

1.28. Let A and B be the intersection points of the given line with the angle's legs. On segments AC and BC, take points K and L, respectively, so that $PK \parallel BC$ and $PL \parallel AC$. Since $\triangle AKP \sim \triangle PLB$, it follows that $AK : KP = PL : LB$ and, therefore, $(a-p)(b-p) = p^2$, where $p = PK = PL$. Hence, $\frac{1}{a} + \frac{1}{b} = \frac{1}{p}$.

1.29. Denote the midpoint of side BC by O and the intersection points of AK and AL with side BC by P and Q, respectively. We may assume that $BP < BQ$. Triangle LCO is an equilateral one and $LC \parallel AB$. Therefore, $\triangle ABQ \sim \triangle LCQ$, i.e., $BQ : QC = AB : LC = 2 : 1$. Hence, $BC = BQ + QC = 3QC$. Similarly, $BC = 3BP$.

1.30. Since $BK : BO = BO : AB$ and $\angle KBO = \angle ABO$, it follows that $\triangle KOB \sim \triangle OAB$. Hence, $\angle KOB = \angle OAB$. Similarly, $\angle AOM = \angle ABO$. Therefore,

$$\angle KOM = \angle KOB + \angle BOA + \angle AOM = \angle OAB + \angle BOA + \angle ABO = 180°,$$

i.e., points K, O and M lie on one line.

1.31. Since $\angle AMN = \angle MNC$ and $\angle BMN = \angle MNA$, we see that $\angle AMB = \angle ANC$. Moreover, $AM : AN = NB : NM = BM : CN$. Hence, $\triangle AMB \sim \triangle ANC$ and, therefore, $\angle MAB = \angle NAC$. Consequently, $\angle BAC = \angle MAN$. For the other angles the proof is similar.

Let points B_1 and C_1 be symmetric to B and C, respectively, through the midperpendicular to segment MN. Since $AM : NB = MN : BM = MC : NC$, it follows that $MA \cdot MC_1 = AM \cdot NC = NB \cdot MC = MB_1 \cdot MC$. Therefore, point A lies on the circle circumscribed about trapezoid BB_1CC_1.

1.32. Since $\angle AEB + \angle BEC = 180°$, angles $\angle AEB$ and $\angle BEC$ cannot be different angles of similar triangles ABE and BEC, i.e., the angles are equal and BE is a perpendicular.

Two cases are possible: either $\angle ABE = \angle CBE$ or $\angle ABE = \angle BCE$. The first case should be discarded because in this case $\triangle ABE = \triangle CBE$.

In the second case we have $\angle ABC = \angle ABE + \angle CBE = \angle ABE + \angle BAE = 90°$. In right triangle ABC the ratio of the legs' lengths is equal to $1 : \sqrt{3}$; hence, the angles of triangle ABC are equal to $90°$, $60°$, $30°$.

1.33. We have $\frac{S_{BDEF}}{2S_{ADE}} = \frac{S_{BDE}}{S_{ADE}} = \frac{DB}{AD} = \frac{EF}{AD} = \sqrt{\frac{S_{EFC}}{S_{ADE}}}$. Hence,

$$S_{BDEF} = 2\sqrt{S_{ADE} \cdot S_{EFC}}.$$

1.34. Let $MN = x$; let E be the intersection point of lines AB and CD. Triangles EBC, EMN and EAD are similar, hence, $S_{EBC} : S_{EMN} : S_{EAD} = a^2 : x^2 : b^2$. Since $S_{EMN} - S_{EBC} = S_{MBCN} = S_{MADN} = S_{EAD} - S_{EMN}$, it follows that $x^2 - a^2 = b^2 - x^2$, i.e., $x^2 = \frac{1}{2}(a^2 + b^2)$.

1.35. Through point Q inside triangle ABC draw lines DE, FG and HI parallel to BC, CA and AB, respectively, so that points F and H would lie on side BC, points E and I on side AC, points D and G on side AB (Fig. 6).



Figure 6 (Sol. 1.35)

Set $S = S_{ABC}$, $S_1 = S_{GDQ}$, $S_2 = S_{IEQ}$, $S_3 = S_{HFQ}$. Then

$$\sqrt{\frac{S_1}{S}} + \sqrt{\frac{S_2}{S}} + \sqrt{\frac{S_3}{S}} = \frac{GQ}{AC} + \frac{IE}{AC} + \frac{FQ}{AC} = \frac{AI + IE + EC}{AC} = 1,$$

i.e., $S = (\sqrt{S_1} + \sqrt{S_2} + \sqrt{S_3})^2$.

1.36. Let M be the intersection point of the medians of triangle ABC; let point A_1 be symmetric to M through the midpoint of segment BC. The ratio of the lengths of sides of triangle CMA_1 to the lengths of the corresponding medians of triangle ABC is to $2:3$. Therefore, the area to be found is equal to $\frac{9}{4}S_{CMA_1}$. Clearly, $S_{CMA_1} = \frac{1}{3}S$ (cf. the solution of Problem 4.1).

1.37. Let E, F, G and H be the midpoints of sides AB, BC, CD and DA, respectively.

a) Clearly, $S_{AEH} + S_{CFG} = \frac{1}{4}S_{ABD} + \frac{1}{4}S_{CBD} = \frac{1}{4}S_{ABCD}$. Analogously, $S_{BEF} + S_{DGH} = \frac{1}{4}S_{ABCD}$; hence, $S_{EFGH} = S_{ABCD} - \frac{1}{4}S_{ABCD} - \frac{1}{4}S_{ABCD} = \frac{1}{2}S_{ABCD}$.

b) Since $AC = BD$, it follows that $EFGH$ is a rhombus (Problem 1.2). By heading a) we have $S_{ABCD} = 2S_{EFGH} = EG \cdot FH$.

1.38. Let E, F, G and H be the midpoints of sides of quadrilateral $ABCD$; let points E_1, F_1, G_1 and H_1 be symmetric to point O through these points, respectively. Since EF is the midline of triangle E_1OF_1, we see that $S_{E_1OF_1} = 4S_{EOF}$. Similarly, $S_{F_1OG_1} = 4S_{FOG}$, $S_{G_1OH_1} = 4S_{GOH}$, $S_{H_1OE_1} = 4S_{HOE}$. Hence, $S_{E_1F_1G_1H_1} = 4S_{EFGH}$. By Problem 1.37 a) $S_{ABCD} = 2S_{EFGH}$. Hence, $S_{E_1F_1G_1H_1} = 2S_{ABCD} = 2S$.

1.39. First solution. Let us consider square $BCMN$ and divide its side MN by points P and Q into three equal parts (Fig. 7).

Then $\triangle ABC = \triangle PDQ$ and $\triangle ACD = \triangle PMA$. Hence, triangle $\triangle PAD$ is an isosceles right triangle and $\angle ABC + \angle ADC = \angle PDQ + \angle ADC = 45°$.

Second solution. Since $DE = 1$, $EA = \sqrt{2}$, $EB = 2$, $AD = \sqrt{5}$ and $BA = \sqrt{10}$, it follows that $DE : AE = EA : EB = AD : BA$ and $\triangle DEA \sim \triangle AEB$. Therefore, $\angle ABC = \angle EAD$. Moreover, $\angle AEC = \angle CAE = 45°$. Hence,

$$\angle ABC + \angle ADC + \angle AEC = (\angle EAD + \angle CAE) + \angle ADC$$
$$= \angle CAD + \angle ADC = 90°.$$



Figure 7 (Sol. 1.39)

1.40. From point L drop perpendiculars LM and LN on AB and AD, respectively. Then $KM = MB = ND$ and $KL = LB = DL$ and, therefore, right triangles KML and DNL are equal. Hence, $\angle DLK = \angle NLM = 90^\circ$.

1.41. Since $D_1A = B_1B, AD_2 = BB_2$ and $\angle D_1AD_2 = \angle B_1BB_2$, it follows that $\triangle D_1AD_2 = \triangle B_1BB_2$. Sides AD_1 and BB_1 (and also AD_2 and BB_2) of these triangles are perpendicular and, therefore, $B_1B_2 \perp D_1D_2$.

1.42. On the extension of segment AC beyond point C take point M so that $CM = CE$ (Fig. 8).



Figure 8 (Sol. 1.42)

Then under the rotation with center C through an angle of 90° triangle ACE turns into triangle BCM. Therefore, line MB is perpendicular to line AE; hence, it is parallel to line CL. Since $MC = CE = DC$ and lines DK, CL and MB are parallel, $KL = LB$.

1.43. Let rectangles ABC_1D_1 and A_2BCD_2 be constructed on sides AB and BC; let P, Q, R and S be the centers of rectangles constructed on sides AB, BC, CD and DA, respectively. Since $\angle ABC + \angle ADC = 180^\circ$, it follows that $\triangle ADC = \triangle A_2BC_1$ and, therefore, $\triangle RDS = \triangle PBQ$ and $RS = PQ$. Similarly, $QR = PS$. Therefore, $PQRS$ is a parallelogram such that one of triangles RDS and PBQ is constructed on its sides outwards and on the other side inwards; a similar statement holds for triangles QCR and SAP as well. Therefore, $\angle PQR + \angle RSP = \angle BQC + \angle DSA = 180^\circ$ because $\angle PQB = \angle RSD$ and $\angle RQC = \angle PSA$. It follows that $PQRS$ is a rectangle.

1.44. Let K, L and M be the intersection points of the circumscribed circles of triangles FOA and BOC, BOC and DOE, DOE and FOA, respectively; 2α, 2β and 2γ the angles at the vertices of isosceles triangles BOC, DOE and FOA, respectively (Fig. 9).



Figure 9 (Sol. 1.44)

Point K lies on arc $\smile OB$ of the circumscribed circle of the isosceles triangle BOC and, therefore, $\angle OKB = 90^\circ + \alpha$. Similarly, $\angle OKA = 90^\circ + \gamma$. Since $\alpha + \beta + \gamma = 90^\circ$, it follows that $\angle AKB = 90^\circ + \beta$. Inside equilateral triangle AOB there exists a unique point K that serves as the vertex of the angles that subtend its sides and are equal to the given angles.

Similar arguments for a point L inside triangle COD show that $\triangle OKB = \triangle CLO$.

Now, let us prove that $\triangle KOL = \triangle OKB$. Indeed, $\angle COL = \angle KBO$; hence, $\angle KOB + \angle COL = 180^\circ - \angle OKB = 90^\circ - \alpha$ and, therefore, $\angle KOL = 2\alpha + (90^\circ - \alpha) = 90^\circ + \alpha = \angle OKB$. It follows that $KL = OB = R$. Similarly, $LM = MK = R$.

1.45. Let $\angle A = \alpha$. It is easy to verify that both angles $\angle KCL$ and $\angle ADL$ are equal to $240^\circ - \alpha$ (or $120^\circ + \alpha$). Since $KC = BC = AD$ and $CL = DL$, it follows that $\triangle KCL = \triangle ADL$ and, therefore, $KL = AL$. Similarly, $KL = AK$.

1.46. Let P, Q and R be the centers of the squares constructed on sides DA, AB and BC, respectively, in parallelogram $ABCD$ with an acute angle of α at vertex A. It is easy to verify that $\angle PAQ = 90^\circ + \alpha = \angle RBQ$; hence, $\triangle PAQ = \triangle RBQ$. Sides AQ and BQ of these triangles are perpendicular, hence, $PQ \perp QR$.

1.47. First, observe that the sum of the angles at vertices A, B and C of hexagon $AB'CA'BC'$ is equal to 360° because by the hypothesis the sum of its angles at the other vertices is equal to 360°. On side AC', construct outwards triangle $\triangle AC'P$ equal to triangle $\triangle BC'A'$ (Fig. 10).



Figure 10 (Sol. 1.47)

Then $\triangle AB'P = \triangle CB'A'$ because $AB' = CB'$, $AP = CA'$ and

$$\angle PAB' = 360^\circ - \angle PAC' - \angle C'AB' = 360^\circ - \angle A'BC' - \angle C'AB' = \angle A'CB'.$$

Hence, $\triangle C'B'A' = \triangle C'B'P$ and, therefore, $2\angle A'B'C' = \angle PB'A' = \angle AB'C$ because $\angle PB'A = \angle A'B'C$.

1.48. Since $BA : BC = BC_1 : BA_1$ and $\angle ABC = \angle C_1BA_1$, it follows that $\triangle ABC \sim \triangle C_1BA_1$. Similarly, $\triangle ABC \sim \triangle B_1A_1C$. Since $BA_1 = A_1C$, it follows that $\triangle C_1BA_1 = \triangle B_1A_1C$. Therefore, $AC_1 = C_1B = B_1A_1$ and $AB_1 = B_1C = C_1A_1$. It is also clear that quadrilateral $AB_1A_1C_1$ is a convex one.

1.49. a) Let P and Q be the midpoints of sides AB and AC. Then $MP = \frac{1}{2}AC = QB_1$, $MQ = \frac{1}{2}AB = PC_1$ and $\angle C_1PM = \angle C_1PB + \angle BPM = \angle B_1QC + \angle CQM = \angle B_1QM$. Hence, $\triangle MQB_1 = \triangle C_1PM$ and, therefore, $MC_1 = MB_1$. Moreover,

$$\angle PMC_1 + \angle QMB_1 = \angle QB_1M + \angle QMB_1 = 180^\circ - \angle MQB_1$$

and

$$\angle MQB_1 = \angle A + \angle CQB_1 = \angle A + (180^\circ - 2\varphi).$$

Therefore, $\angle B_1MC_1 = \angle PMQ + 2\varphi - \angle A = 2\varphi$. (The case when $\angle C_1PB + \angle BPM > 180^\circ$ is analogously treated.)

b) On sides AB and AC, take points B' and C', respectively, such that $AB' : AB = AC' : AC = 2 : 3$. The midpoint M of segment $B'C'$ coincides with the intersection point of the medians of triangle ABC. On sides AB' and AC', construct outwards right triangles $AB'C_1$ and AB_1C' with angle $\varphi = 60^\circ$ as in heading a). Then B_1 and C_1 are the centers of right triangles constructed on sides AB and AC; on the other hand, by heading a), $MB_1 = MC_1$ and $\angle B_1MC_1 = 120^\circ$.

Remark. Statements of headings a) and b) remain true for triangles constructed inwards, as well.

1.50. a) Let B' be the intersection point of line AC and the perpendicular to line AB_1 erected from point B_1; define point C' similarly. Since $AB' : AC' = AC_1 : AB_1 = AB : AC$, it follows that $B'C' \parallel BC$. If N is the midpoint of segment $B'C'$, then, as follows from Problem 1.49, $NC_1 = NB_1$ (i.e., $N = M$) and $\angle B_1NC_1 = 2\angle AB'B_1 = 180^\circ - 2\angle CAB_1 = \varphi$.

b) On side BC construct outwards isosceles triangle BA_1C with angle $360^\circ - 2\varphi$ at vertex A_1 (if $\varphi < 90^\circ$ construct inwards a triangle with angle 2φ). Since the sum of the angles at the vertices of the three constructed isosceles triangles is equal to 360°, it follows that the angles of triangle $A_1B_1C_1$ are equal to $180^\circ - \varphi$, $\frac{1}{2}\varphi$ and $\frac{1}{2}\varphi$ (cf. Problem 1.47). In particular, this triangle is an isosceles one, hence, $A_1 = O$.

1.51. Let O_1, O_2, O_3 and O_4 be the centers of rhombuses constructed on sides AB, BC, CA and DA, respectively; let M be the midpoint of diagonal AC. Then $MO_1 = MO_2$ and $\angle O_1MO_2 = \alpha$ (cf. Problem 1.49). Similarly, $MO_3 = MO_4$ and $\angle O_3MO_4 = \alpha$. Therefore, under the rotation through an angle of α about point M triangle $\triangle O_1MO_3$ turns into $\triangle O_2MO_4$.

1.52. Since $A_1C = AC|\cos C|$, $B_1C = BC|\cos C|$ and angle $\angle C$ is the common angle of triangles ABC and A_1B_1C, these triangles are similar; the similarity coefficient is equal to $|\cos C|$.

1.53. Since points M and N lie on the circle with diameter CH, it follows that $\angle CMN = \angle CHN$ and since $AC \perp HN$, we see that $\angle CHN = \angle A$. Similarly, $\angle CNM = \angle B$.

1.54. a) Let l be the tangent to the circumscribed circle at point A. Then $\angle(l, AB) = \angle(AC, CB) = \angle(C_1B_1, AC_1)$ and, therefore, $l \parallel B_1C_1$.

b) Since $OA \perp l$ and $l \parallel B_1C_1$, it follows that $OA \perp B_1C_1$.

1.55. If AA_1, BB_1 and CC_1 are heights, then right triangles AA_1C and BB_1C have equal angles at vertex C and, therefore, are similar. It follows that $\triangle A_1BH \sim \triangle B_1AH$, consequently, $AH \cdot A_1H = BH \cdot B_1H$. Similarly, $BH \cdot B_1H = CH \cdot C_1H$.

If $AH \cdot A_1H = BH \cdot B_1H = CH \cdot C_1H$, then $\triangle A_1BH \sim \triangle B_1AH$; hence, $\angle BA_1H = \angle AB_1H = \varphi$. Thus, $\angle CA_1H = \angle CB_1H = 180^\circ - \varphi$.

Similarly, $\angle AC_1H = \angle CA_1H = 180^\circ - \varphi$ and $\angle AC_1H = \angle AB_1H = \varphi$. Hence, $\varphi = 90^\circ$, i.e., AA_1, BB_1 and CC_1 are heights.

1.56. a) By Problem 1.52 $\angle C_1A_1B = \angle CA_1B_1 = \angle A$. Since $AA_1 \perp BC$, it follows that $\angle C_1A_1A = \angle B_1A_1A$. The proof of the fact that rays B_1B and C_1C are the bisectors of angles $A_1B_1C_1$ and $A_1C_1B_1$ is similar.

b) Lines AB, BC and CA are the bisectors of the outer angles of triangle $A_1B_1C_1$, hence, A_1A is the bisector of angle $\angle B_1A_1C_1$ and, therefore, $AA_1 \perp BC$. For lines BB_1 and CC_1 the proof is similar.

1.57. From the result of Problem 1.56 a) it follows that the symmetry through line AC sends line B_1A_1 into line B_1C_1.

1.58. By Problem 1.52 $\angle B_1A_1C = \angle BAC$. Since $A_1B_1 \parallel AB$, it follows that $\angle B_1A_1C = \angle ABC$. Hence, $\angle BAC = \angle ABC$. Similarly, since $B_1C_1 \parallel BC$, it follows that $\angle ABC = \angle BCA$. Therefore, triangle ABC is an equilateral one and $A_1C_1 \parallel AC$.

1.59. Let O be the center of the circumscribed circle of triangle ABC. Since $OA \perp B_1C_1$ (cf. Problem 1.54 b), it follows that $S_{AOC_1} + S_{AOB_1} = \frac{1}{2}(R \cdot B_1C_1)$. Similar arguments for vertices B and C show that $S_{ABC} = qR$. On the other hand, $S_{ABC} = pr$.

1.60. The perimeter of the triangle cut off by the line parallel to side BC is equal to the sum of distances from point A to the tangent points of the inscribed circle with sides AB and AC; therefore, the sum of perimeters of small triangles is equal to the perimeter of triangle ABC, i.e., $P_1 + P_2 + P_3 = P$. The similarity of triangles implies that $\frac{r_i}{r} = \frac{P_i}{P}$. Summing these equalities for all the i we get the statement desired.

1.61. Let $M = A$. Then $X_A = A$; hence, $AY_A = 1$. Similarly, $CX_C = 1$. Let us prove that $y = AY_A$ and $x = CX_C$ are the desired lines. On side BC, take point D so that $AB \parallel MD$, see Fig. 11. Let E be the intersection point of lines CX_C and MD. Then, $X_MM + Y_MM = X_CE + Y_MM$. Since $\triangle ABC \sim \triangle MDC$, it follows that $CE = Y_MM$. Therefore, $CE = Y_MM$. Hence, $X_MM + Y_MM = X_CE + CE = X_CC = 1$.



Figure 11 (Sol. 1.61)

1.62. Let D be the midpoint of segment BH. Since $\triangle BHA \sim \triangle HEA$, it follows that $AD : AO = AB : AH$ and $\angle DAH = \angle OAE$. Hence, $\angle DAO = \angle BAH$ and, therefore, $\triangle DAO \sim \triangle BAH$ and $\angle DOA = \angle BAH = 90^\circ$.

1.63. Let AA_1, BB_1 and CC_1 be heights of triangle ABC. Let us drop from point B_1 perpendiculars B_1K and B_1N to sides AB and BC, respectively, and perpendiculars B_1L and B_1M to heights AA_1 and CC_1, respectively. Since $KB_1 : C_1C = AB_1 : AC = LB_1 : A_1C$, it follows that $\triangle KLB_1 \sim \triangle C_1A_1C$ and, therefore, $KL \parallel C_1A_1$. Similarly, $MN \parallel C_1A_1$. Moreover, $KN \parallel C_1A_1$ (cf. Problem 1.53). It follows that points K, L, M and N lie on one line.

1.64. a) Let O be the midpoint of AC, let O_1 be the midpoint of AB and O_2 the midpoint of BC. Assume that $AB \leq BC$. Through point O_1 draw line O_1K parallel to EF (point K lies on segment EO_2). Let us prove that right triangles DBO and O_1KO_2 are equal. Indeed,

$O_1O_2 = DO = \frac{1}{2}AC$ and $BO = KO_2 = \frac{1}{2}(BC - AB)$. Since triangles DBO and O_1KO_2 are equal, we see that $\angle BOD = \angle O_1O_2E$, i.e., line DO is parallel to EO_2 and the tangent drawn through point D is parallel to line EF.

b) Since the angles between the diameter AC and the tangents to the circles at points F, D, E are equal, it follows that $\angle FAB = \angle DAC = \angle EBC$ and $\angle FBA + \angle DCA = \angle ECB$, i.e., F lies on line segment AD and E lies on line segment DC. Moreover, $\angle AFB = \angle BEC = \angle ADC = 90°$ and, therefore, $FDEB$ is a rectangle.

1.65. Let MQ and MP be perpendiculars dropped on sides AD and BC, let MR and MT be perpendiculars dropped on the extensions of sides AB and CD (Fig. 12). Denote by M_1 and P_1 the other intersection points of lines RT and QP with the circle.



Figure 12 (Sol. 1.65)

Since $TM_1 = RM = AQ$ and $TM_1 \parallel AQ$, it follows that $AM_1 \parallel TQ$. Similarly, $AP_1 \parallel RP$. Since $\angle M_1AP_1 = 90°$, it follows that $RP \perp TQ$.

Denote the intersection points of lines TQ and RP, M_1A and RP, P_1A and TQ by E, F, G, respectively. To prove that point E lies on line AC, it suffices to prove that rectangles $AFEG$ and AM_1CP_1 are similar. Since $\angle ARF = \angle AM_1R = \angle M_1TG = \angle M_1CT$, we may denote the values of these angles by the same letter α. We have: $AF = RA\sin\alpha = M_1A\sin^2\alpha$ and $AG = M_1T\sin\alpha = M_1C\sin^2\alpha$. Therefore, rectangles $AFEG$ and AM_1CP_1 are similar.

1.66. Denote the centers of the circles by O_1 and O_2. The outer tangent is tangent to the first circle at point K and to the other circle at point L; the inner tangent is tangent to the first circle at point M and to the other circle at point N (Fig. 13).



Figure 13 (Sol. 1.66)

Let lines KM and LN intersect line O_1O_2 at points P_1 and P_2, respectively. We have to prove that $P_1 = P_2$. Let us consider points A, D_1, D_2 — the intersection points of KL with MN, KM with O_1A, and LN with O_2A, respectively. Since $\angle O_1AM + \angle NAO_2 = 90°$, right triangles O_1MA and ANO_2 are similar; we also see that $AO_2 \parallel KM$ and $AO_1 \parallel LN$. Since these lines are parallel, $AD_1 : D_1O_1 = O_2P_1 : P_1O_1$ and $D_2O_2 : AD_2 = O_2P_2 : P_2O_1$. The similarity of quadrilaterals AKO_1M and O_2NAL yields $AD_1 : D_1O_1 = D_2O_2 : AD_2$. Therefore, $O_2P_1 : P_1O_1 = O_2P_2 : P_2O_1$, i.e., $P_1 = P_2$.

CHAPTER 2. INSCRIBED ANGLES

Background

1. Angle $\angle ABC$ whose vertex lies on a circle and legs intersect this circle is called *inscribed* in the circle. Let O be the center of the circle. Then

$$\angle ABC = \begin{cases} \frac{1}{2}\angle AOC & \text{if points } B \text{ and } O \text{ lie on one side of } AC \\ 180^\circ - \frac{1}{2}\angle AOC & \text{otherwise.} \end{cases}$$

The most important and most often used corollary of this fact is that *equal chords subtend angles that either are equal or the sum of the angles is equal to* 180°.

2. The value of the angle between chord AB and the tangent to the circle that passes through point A is equal to half the angle value of arc $\smile AB$.

3. The angle values of arcs confined between parallel chords are equal.

4. As we have already said, if two angles subtend the same chord, either they are equal or the sum of their values is 180°. In order not to consider various variants of the positions of points on the circle let us introduce the notion of an *oriented angle* between lines. The *value of the oriented angle between lines* AB and CD (notation: $\angle(AB, CD)$) is the value of the angle by which we have to rotate line AB counterclockwise in order for it to become parallel to line CD. The angles that differ by $n \cdot 180^\circ$ are considered equal.

Notice that, generally, the oriented angle between lines CD and AB is not equal to the oriented angle between lines AB and CD (the sum of $\angle(AB, CD)$ and $\angle(CD, AB)$ is equal to 180° which, according to our convention, is the same as 0°).

It is easy to verify the following properties of the oriented angles:

a) $\angle(AB, BC) = -\angle(BC, AB)$;

b) $\angle(AB, CD) + \angle(CD, EF) = \angle(AB, EF)$;

c) *points A, B, C, D not on one line lie on one circle if and only if* $\angle(AB, BC) = \angle(AD, DC)$. (To prove this property we have to consider two cases: points B and D lie on one side of AC; points B and D lie on different sides of AC.)

Introductory problems

1. a) From point A lying outside a circle rays AB and AC come out and intersect the circle. Prove that the value of angle $\angle BAC$ is equal to half the difference of the angle measures of the arcs of the circle confined inside this angle.

b) The vertex of angle $\angle BAC$ lies inside a circle. Prove that the value of angle $\angle BAC$ is equal to half the sum of angle measures of the arcs of the circle confined inside angle $\angle BAC$ and inside the angle symmetric to it through vertex A.

2. From point P inside acute angle $\angle BAC$ perpendiculars PC_1 and PB_1 are dropped on lines AB and AC. Prove that $\angle C_1AP = \angle C_1B_1P$.

3. Prove that all the angles formed by the sides and diagonals of a regular n-gon are integer multiples of $\frac{180^\circ}{n}$.

4. The center of an inscribed circle of triangle ABC is symmetric through side AB to the center of the circumscribed circle. Find the angles of triangle ABC.

5. The bisector of the exterior angle at vertex C of triangle ABC intersects the circumscribed circle at point D. Prove that $AD = BD$.

§1. Angles that subtend equal arcs

2.1. Vertex A of an acute triangle ABC is connected by a segment with the center O of the circumscribed circle. From vertex A height AH is drawn. Prove that $\angle BAH = \angle OAC$.

2.2. Two circles intersect at points M and K. Lines AB and CD are drawn through M and K, respectively; they intersect the first circle at points A and C, the second circle at points B and D, respectively. Prove that $AC \parallel BD$.

2.3. From an arbitrary point M inside a given angle with vertex A perpendiculars MP and MQ are dropped to the sides of the angle. From point A perpendicular AK is dropped on segment PQ. Prove that $\angle PAK = \angle MAQ$.

2.4. a) The continuation of the bisector of angle $\angle B$ of triangle ABC intersects the circumscribed circle at point M; O is the center of the inscribed circle, O_b is the center of the escribed circle tangent to AC. Prove that points A, C, O and O_b lie on a circle centered at M.

b) Point O inside triangle ABC is such that lines AO, BO and CO pass through the centers of the circumscribed circles of triangles BCO, ACO and ABO, respectively. Prove that O is the center of the inscribed circle of triangle ABC.

2.5. Vertices A and B of right triangle ABC with right angle $\angle C$ slide along the sides of a right angle with vertex P. Prove that in doing so point C moves along a line segment.

2.6. Diagonal AC of square $ABCD$ coincides with the hypothenuse of right triangle ACK, so that points B and K lie on one side of line AC. Prove that

$$BK = \frac{|AK - CK|}{\sqrt{2}} \quad \text{and} \quad DK = \frac{AK + CK}{\sqrt{2}}.$$

2.7. In triangle ABC medians AA_1 and BB_1 are drawn. Prove that if $\angle CAA_1 = \angle CBB_1$, then $AC = BC$.

2.8. Each angle of triangle ABC is smaller than 120°. Prove that inside $\triangle ABC$ there exists a point that serves as the vertex for three angles each of value 120° and subtending the side of the triangle different from the sides subtended by the other angles.

2.9. A circle is divided into equal arcs by n diameters. Prove that the bases of the perpendiculars dropped from an arbitrary point M inside the circle to these diameters are vertices of a regular n-gon.

2.10. Points A, B, M and N on a circle are given. From point M chords MA_1 and MB_1 perpendicular to lines NB and NA, respectively, are drawn. Prove that $AA_1 \parallel BB_1$.

2.11. Polygon $ABCDEF$ is an inscribed one; $AB \parallel DE$ and $BC \parallel EF$. Prove that $CD \parallel AF$.

2.12. Polygon $A_1A_2 \dots A_{2n}$ as an inscribed one. We know that all the pairs of its opposite sides except one are parallel. Prove that for any odd n the remaining pair of sides is also parallel and for any even n the lengths of the exceptional sides are equal.

2.13. Consider triangle ABC. Prove that there exist two families of equilateral triangles whose sides (or extensions of the sides) pass through points A, B and C. Prove also that the centers of triangles from these families lie on two concentric circles.

§2. The value of an angle between two chords

The following fact helps to solve problems from this section. Let A, B, C, D be points on a circle situated in the order indicated. Then

$$\angle(AC, BD) = \frac{\smile AB + \smile CD}{2} \quad \text{and} \quad \angle(AB, CD) = \frac{|\smile AD - \smile CB|}{2}.$$

To prove this, we have to draw a chord parallel to another chord through the endpoint of one of the chords.

2.14. Points A, B, C, D in the indicated order are given on a circle. Let M be the midpoint of arc $\smile AB$. Denote the intersection points of chords MC and MD with chord AB by E and K. Prove that $KECD$ is an inscribed quadrilateral.

2.15. Concider an equilateral triangle. A circle with the radius equal to the triangle's height rolls along a side of the triangle. Prove that the angle measure of the arc cut off the circle by the sides of the triangle is always equal to $60°$.

2.16. The diagonals of an isosceles trapezoid $ABCD$ with lateral side AB intersect at point P. Prove that the center O of the inscribed circle lies on the inscribed circle of triangle APB.

2.17. Points A, B, C, D in the indicated order are given on a circle; points A_1, B_1, C_1 and D_1 are the midpoints of arcs $\smile AB$, $\smile BC$, $\smile CD$ and $\smile DA$, respectively. Prove that $A_1C_1 \perp B_1D_1$.

2.18. Point P inside triangle ABC is taken so that $\angle BPC = \angle A + 60°$, $\angle APC = \angle B + 60°$ and $\angle APB = \angle C + 60°$. Lines AP, BP and CP intersect the circumscribed circle of triangle ABC at points A', B' and C', respectively. Prove that triangle $A'B'C'$ is an equilateral one.

2.19. Points A, C_1, B, A_1, C, B_1 in the indicated order are taken on a circle.

a) Prove that if lines AA_1, BB_1 and CC_1 are the bisectors of the angles of triangle ABC, then they are the heights of triangle $A_1B_1C_1$.

b) Prove that if lines AA_1, BB_1 and CC_1 are the heights of triangle ABC, then they are the bisectors of the angles of triangle $A_1B_1C_1$.

2.20. Triangles T_1 and T_2 are inscribed in a circle so that the vertices of triangle T_2 are the midpoints of the arcs into which the circle is divided by the vertices of triangle T_1. Prove that in the hexagon which is the intersection of triangles T_1 and T_2 the diagonals that connect the opposite vertices are parallel to the sides of triangle T_1 and meet at one point.

§3. The angle between a tangent and a chord

2.21. Two circles intersect in points P and Q. Through point A on the first circle lines AP and AQ are drawn. The lines intersect the second circle in points B and C. Prove that the tangent at A to the first circle is parallel to line BC.

2.22. Circles S_1 and S_2 intersect at points A and P. Tangent AB to circle S_1 is drawn through point A, and line CD parallel to AB is drawn through point P (points B and C lie on S_2, point D on S_1). Prove that $ABCD$ is a parallelogram.

2.23. The tangent at point A to the inscribed circle of triangle ABC intersects line BC at point E; let AD be the bisector of triangle ABC. Prove that $AE = ED$.

2.24. Circles S_1 and S_2 intersect at point A. Through point A a line that intersects S_1 at point B and S_2 at point C is drawn. Through points C and B tangents to the circles are drawn; the tangents intersect at point D. Prove that angle $\angle BDC$ does not depend on the choice of the line that passes through A.

2.25. Two circles intersect at points A and B. Through point A tangents AM and AN, where M and N are points of the respective circles, are drawn. Prove that:

a) $\angle ABN + \angle MAN = 180^\circ$;

b) $\frac{BM}{BN} = \left(\frac{AM}{AN}\right)^2$.

2.26. Inside square $ABCD$ a point P is taken so that triangle ABP is an equilateral one. Prove that $\angle PCD = 15^\circ$.

2.27. Two circles are internally tangent at point M. Let AB be the chord of the greater circle which is tangent to the smaller circle at point T. Prove that MT is the bisector of angle AMB.

2.28. Through point M inside circle S chord AB is drawn; perpendiculars MP and MQ are dropped from point M to the tangents that pass through points A and B respectively. Prove that the value of $\frac{1}{PM} + \frac{1}{QM}$ does not depend on the choice of the chord that passes through point M.

2.29. Circle S_1 is tangent to sides of angle ABC at points A and C. Circle S_2 is tangent to line AC at point C and passes through point B, circle S_2 intersects circle S_1 at point M. Prove that line AM divides segment BC in halves.

2.30. Circle S is tangent to circles S_1 and S_2 at points A_1 and A_2; let B be a point of circle S, let K_1 and K_2 be the other intersection points of lines A_1B and A_2B with circles S_1 and S_2, respectively. Prove that if line K_1K_2 is tangent to circle S_1, then it is also tangent to circle S_2.

§4. Relations between the values of an angle and the lengths of the arc and chord associated with the angle

2.31. Isosceles trapezoids $ABCD$ and $A_1B_1C_1D_1$ with parallel respective sides are inscribed in a circle. Prove that $AC = A_1C_1$.

2.32. From point M that moves along a circle perpendiculars MP and MQ are dropped on diameters AB and CD, respectively. Prove that the length of segment PQ does not depend on the position of point M.

2.33. In triangle ABC, angle $\angle B$ is equal to 60°; bisectors AD and CE intersect at point O. Prove that $OD = OE$.

2.34. In triangle ABC the angles at vertices B and C are equal to 40°; let BD be the bisector of angle B. Prove that $BD + DA = BC$.

2.35. On chord AB of circle S centered at O a point C is taken. The circumscribed circle of triangle AOC intersects circle S at point D. Prove that $BC = CD$.

2.36. Vertices A and B of an equilateral triangle ABC lie on circle S, vertex C lies inside this circle. Point D lies on circle S and $BD = AB$. Line CD intersects S at point E. Prove that the length of segment EC is equal to the radius of circle S.

2.37. Along a fixed circle another circle whose radius is half that of the fixed one rolls on the inside without gliding. What is the trajectory of a fixed point K of the rolling circle?

§5. Four points on one circle

2.38. From an arbitrary point M on leg BC of right triangle ABC perpendicular MN is dropped on hypothenuse AP. Prove that $\angle MAN = \angle MCN$.

2.39. The diagonals of trapezoid $ABCD$ with bases AD and BC intersect at point O; points B' and C' are symmetric through the bisector of angle $\angle BOC$ to vertices B and C, respectively. Prove that $\angle C'AC = \angle B'DB$.

2.40. The extensions of sides AB and CD of the inscribed quadrilateral $ABCD$ meet at point P; the extensions of sides BC and AD meet at point Q. Prove that the intersection points of the bisectors of angles $\angle AQB$ and $\angle BPC$ with the sides of the quadrilateral are vertices of a rhombus.

2.41. The inscribed circle of triangle ABC is tangent to sides AB and AC at points M and N, respectively. Let P be the intersection point of line MN with the bisector (or its extension) of angle $\angle B$. Prove that:

a) $\angle BPC = 90^\circ$;

b) $S_{ABP} : S_{ABC} = 1 : 2$.

2.42. Inside quadrilateral $ABCD$ a point M is taken so that $ABMD$ is a parallelogram. Prove that if $\angle CBM = \angle CDM$, then $\angle ACD = \angle BCM$.

2.43. Lines AP, BP and CP intersect the circumscribed circle of triangle ABC at points A_1, B_1 and C_1, respectively. On lines BC, CA and AB points A_2, B_2 and C_2, respectively, are taken so that $\angle(PA_2, BC) = \angle(PB_2, CA) = \angle(PC_2, AB)$. Prove that $\triangle A_2B_2C_2 \sim \triangle A_1B_1C_1$.

2.44. About an equilateral triangle APQ a rectangular $ABCD$ is circumscribed so that points P and Q lie on sides BC and CD, respectively; P' and Q' are the midpoints of sides AP and AQ, respectively. Prove that triangles $BQ'C$ and $CP'D$ are equilateral ones.

2.45. Prove that if for inscribed quadrilateral $ABCD$ the equality $CD = AD + BC$ holds, then the intersection point of the bisectors of angles $\angle A$ and $\angle B$ lies on side CD.

2.46. Diagonals AC and CE of a regular hexagon $ABCDEF$ are divided by points M and N, respectively, so that $AM : AC = CN : CE = \lambda$. Find λ if it is known that points B, M and N lie on a line.

2.47. The corresponding sides of triangles ABC and $A_1B_1C_1$ are parallel and sides AB and A_1B_1 lie on one line. Prove that the line that connects the intersection points of the circumscribed circles of triangles A_1BC and AB_1C contains point C_1.

2.48. In triangle ABC heights AA_1, BB_1 and CC_1 are drawn. Line KL is parallel to CC_1; points K and L lie on lines BC and B_1C_1, respectively. Prove that the center of the circumscribed circle of triangle A_1KL lies on line AC.

2.49. Through the intersection point O of the bisectors of triangle ABC line MN is drawn perpendicularly to CO so that M and N lie on sides AC and BC, respectively. Lines AO and BO intersect the circumscribed circle of triangle ABC at points A' and B', respectively. Prove that the intersection point of lines $A'N$ and $B'M$ lies on the circumscribed circle.

§6. The inscribed angle and similar triangles

2.50. Points A, B, C and D on a circle are given. Lines AB and CD intersect at point M. Prove that
$$\frac{AC \cdot AD}{AM} = \frac{BC \cdot BD}{BM}.$$

2.51. Points A, B and C on a circle are given; the distance BC is greater than the distance from point B to line l tangent to the circle at point A. Line AC intersects the line drawn through point B parallelly to l at point D. Prove that $AB^2 = AC \cdot AD$.

2.52. Line l is tangent to the circle of diameter AB at point C; points M and N are the projections of points A and B on line l, respectively, and D is the projection of point C on AB. Prove that $CD^2 = AM \cdot BN$.

2.53. In triangle ABC, height AH is drawn and from vertices B and C perpendiculars BB_1 and CC_1 are dropped on the line that passes through point A. Prove that $\triangle ABC \sim \triangle HB_1C_1$.

2.54. On arc $\smile BC$ of the circle circumscribed about equilateral triangle ABC, point P is taken. Segments AP and BC intersect at point Q. Prove that
$$\frac{1}{PQ} = \frac{1}{PB} + \frac{1}{PC}.$$

2.55. On sides BC and CD of square $ABCD$ points E and F are taken so that $\angle EAF = 45^\circ$. Segments AE and AF intersect diagonal BD at points P and Q, respectively. Prove that $\frac{S_{AEF}}{S_{APQ}} = 2$.

2.56. A line that passes through vertex C of equilateral triangle ABC intersects base AB at point M and the circumscribed circle at point N. Prove that

$$CM \cdot CN = AC^2 \quad \text{and} \quad \frac{CM}{CN} = \frac{AM \cdot BM}{AN \cdot BN}.$$

2.57. Consider parallelogram $ABCD$ with an acute angle at vertex A. On rays AB and CB points H and K, respectively, are marked so that $CH = BC$ and $AK = AB$. Prove that:

a) $DH = DK$;

b) $\triangle DKH \sim \triangle ABK$.

2.58. a) The legs of an angle with vertex C are tangent to a circle at points A and B. From point P on the circle perpendiculars PA_1, PB_1 and PC_1 are dropped on lines BC, CA and AB, respectively. Prove that $PC_1^2 = PA_1 \cdot PB_1$.

b) From point O of the inscribed circle of triangle ABC perpendiculars OA', OB', OC' are dropped on the sides of triangle ABC opposite to vertices A, B and C, respectively, and perpendiculars OA'', OB'', OC'' are dropped to the sides of the triangle with vertices at the tangent points. Prove that

$$OA' \cdot OB' \cdot OC' = OA'' \cdot OB'' \cdot OC''.$$

2.59. Pentagon $ABCDE$ is inscribed in a circle. Distances from point E to lines AB, BC and CD are equal to a, b and c, respectively. Find the distance from point E to line AD.

2.60. In triangle ABC, heights AA_1, BB_1 and CC_1 are drawn; B_2 and C_2 are the midpoints of heights BB_1 and CC_1, respectively. Prove that $\triangle A_1B_2C_2 \sim \triangle ABC$.

2.61. On heights of triangle ABC points A_1, B_1 and C_1 that divide them in the ratio $2:1$ counting from the vertex are taken. Prove that $\triangle A_1B_1C_1 \sim \triangle ABC$.

2.62. Circle S_1 with diameter AB intersects circle S_2 centered at A at points C and D. Through point B a line is drawn; it intersects S_2 at point M that lies inside S_1 and it intersects S_1 at point N. Prove that $MN^2 = CN \cdot ND$.

2.63. Through the midpoint C of an arbitrary chord AB on a circle chords KL and MN are drawn so that points K and M lie on one side of AB. Segments KN and ML intersect AB at points Q and P, respectively. Prove that $PC = QC$.

2.64. a) A circle that passes through point C intersects sides BC and AC of triangle ABC at points A_1 and B_1, respectively, and it intersects the circumscribed circle of triangle ABC at point M. Prove that $\triangle AB_1M \sim \triangle BA_1M$.

b) On rays AC and BC segments AA_1 and BB_1 equal to the semiperimeter of triangle ABC are drawn. Let M be a point on the circumscribed circle such that $CM \parallel A_1B_1$. Prove that $\angle CMO = 90^\circ$, where O is the center of the inscribed circle.

§7. The bisector divides an arc in halves

2.65. In triangle ABC, sides AC and BC are not equal. Prove that the bisector of angle $\angle C$ divides the angle between the median and the height drawn from this vertex in halves if and only if $\angle C = 90^\circ$.

2.66. It is known that in a triangle the median, the bisector and the height drawn from vertex C divide the angle $\angle C$ into four equal parts. Find the angles of this triangle.

2.67. Prove that in triangle ABC bisector AE lies between median AM and height AH.

2.68. Given triangle ABC; on its side AB point P is chosen; lines PM and PN parallel to AC and BC, respectively, are drawn through P so that points M and N lie on sides BC and AC, respectively; let Q be the intersection point of the circumscribed circles of triangles APN and BPM. Prove that all lines PQ pass through a fixed point.

2.69. The continuation of bisector AD of acute triangle ABC inersects the circumscribed circle at point E. Perpendiculars DP and DQ are dropped on sides AB and AC from point D. Prove that $S_{ABC} = S_{APEQ}$.

§8. An inscribed quadrilateral with perpendicular diagonals

In this section $ABCD$ is an inscribed quadrilateral whose diagonals intersect at a right angle. We will also adopt the following notations: O is the center of the circumscribed circle of quadrilateral $ABCD$ and P is the intersection point of its diagonals.

2.70. Prove that the broken line AOC divides $ABCD$ into two parts whose areas are equal.

2.71. The radius of the circumscribed circle of quadrilateral $ABCD$ is equal to R.

a) Find $AP^2 + BP^2 + CP^2 + DP^2$.

b) Find the sum of squared lengths of the sides of $ABCD$.

2.72. Find the sum of squared lengths of the diagonals of $ABCD$ if the length of segment OP and the radius of the circumscribed circle R are known.

2.73. From vertices A and B perpendiculars to CD that intersect lines BD and AC at points K and L, respectively, are drawn. Prove that $AKLB$ is a rhombus.

2.74. Prove that the area of quadrilateral $ABCD$ is equal to $\frac{1}{2}(AB \cdot CD + BC \cdot AD)$.

2.75. Prove that the distance from point O to side AB is equal to half the length of side CD.

2.76. Prove that the line drawn through point P perpendicularly to BC divides side AD in halves.

2.77. Prove that the midpoints of the sides of quadrilateral $ABCD$ and the projections of point P on the sides lie on one circle.

2.78. a) Through vertices A, B, C and D tangents to the circumscribed circle are drawn. Prove that the quadrilateral formed by them is an inscribed one.

b) Quadrilateral $KLMN$ is simultaneously inscribed and circumscribed; A and B are the tangent points of the inscribed circle with sides KL and LM, respectively. Prove that $AK \cdot BM = r^2$, where r is the radius of the inscribed circle.

§9. Three circumscribed circles intersect at one point

2.79. On sides of triangle ABC triangles ABC', $AB'C$ and $A'BC$ are constructed outwards so that the sum of the angles at vertices A', B' and C' is a multiple of 180°. Prove that the circumscribed circles of the constructed triangles intersect at one point.

2.80. a) On sides (or their extensions) BC, CA and AB of triangle ABC points A_1, B_1 and C_1 distinct from the vertices of the triangle are taken (one point on one side). Prove that the circumscribed circles of triangles AB_1C_1, A_1BC_1 and A_1B_1C intersect at one point.

b) Points A_1, B_1 and C_1 move along lines BC, CA and AB, respectively, so that all triangles $A_1B_1C_1$ are similar and equally oriented. Prove that the intersection point of the circumscribed circles of triangles AB_1C_1, A_1BC_1 and A_1B_1C remains fixed in the process.

2.81. On sides BC, CA and AB of triangle ABC points A_1, B_1 and C_1 are taken. Prove that if triangles $A_1B_1C_1$ and ABC are similar and have opposite orientations, then circumscribed circles of triangles AB_1C_1, ABC_1 and A_1B_1C pass through the center of the circumscribed circle of triangle ABC.

2.82. Points A', B' and C' are symmetric to a point P relative sides BC, CA and AB, respectively, of triangle ABC.

a) The circumscribed circles of triangles $AB'C'$, $A'BC'$, $A'B'C$ and ABC have a common point;

b) the circumscribed circles of triangles $A'BC$, $AB'C$, ABC' and $A'B'C'$ have a common point Q;

c) Let I, J, K and O be the centers of the circumscribed circles of triangles $A'BC$, $AB'C$, ABC' and $A'B'C'$, respectively. Prove that $QI : OI = QJ : OJ = QK : OK$.

§10. Michel's point

2.83. Four lines form four triangles. Prove that

a) The circumscribed circles of these triangles have a common point. (*Michel's point.*)

b) The centers of the circumscribed circles of these triangles lie on one circle that passes through Michel's point.

2.84. A line intersects sides (or their extensions) AB, BC and CA of triangle ABC at points C_1, B_1 and A_1, respectively; let O, O_a, O_b and O_c be the centers of the circumscribed circles of triangles ABC, AB_1C_1, A_1BC_1 and A_1B_1C, respectively; let H, H_a, H_b and H_c be the respective orthocenters of these triangles. Prove that

a) $\triangle O_aO_bO_c \sim \triangle ABC$.

b) the midperpendiculars to segments OH, O_aH_a, O_bH_b and O_cH_c meet at one point.

2.85. Quadrilateral $ABCD$ is an inscribed one. Prove that Michel's point of lines that contain its sides lies on the segment that connects the intersection points of the extensions of the sides.

2.86. Points A, B, C and D lie on a circle centered at O. Lines AB and CD intersect at point E and the circumscribed circles of triangles AEC and BED ilntersect at points E and P. Prove that

a) points A, D, P and O lie on one circle;

b) $\angle EPO = 90^\circ$.

2.87. Given four lines prove that the projections of Michel's point to these lines lie on one line.

See also Problem 19.45.

§11. Miscellaneous problems

2.88. In triangle ABC height AH is drawn; let O be the center of the circumscribed circle. Prove that $\angle OAH = |\angle B - \angle C|$.

2.89. Let H be the intersection point of the heights of triangle ABC; let AA' be a diameter of its circumscribed circle. Prove that segment $A'H$ divides side BC in halves.

2.90. Through vertices A and B of triangle ABC two parallel lines are drawn and lines m and n are symmetric to them through the bisectors of the corresponding angles. Prove that the intersection point of lines m and n lies on the circumscribed circle of triangle ABC.

2.91. a) Lines tangent to circle S at points B and C are drawn from point A. Prove that the center of the inscribed circle of triangle ABC and the center of its escribed circle tangent to side BC lie on circle S.

b) Prove that the circle that passes through vertices B and C of any triangle ABC and the center O of its inscribed circle intercepts on lines AB and AC chords of equal length.

2.92. On sides AC and BC of triangle ABC squares ACA_1A_2 and BCB_1B_2 are constructed outwards. Prove that lines A_1B, A_2B_2 and AB_1 meet at one point.

2.93. Circles S_1 and S_2 intersect at points A and B so that the tangents to S_1 at these points are radii of S_2. On the inner arc of S_1 a point C is taken; straight lines connect it with points A and B. Prove that the second intersection points of these lines with S_2 are the endpoints of a diameter.

2.94. From the center O of a circle the perpendicular OA is dropped to line l. On l, points B and C are taken so that $AB = AC$. Through points B and C two sections are drawn one of which intersects the circle at points P and Q and the other one at points M and N. Lines PM and QN intersect line l at points R and S, respectively. Prove that $AR = AS$.

Problems for independent study

2.95. In triangle ABC heights AA_1 and BB_1 are drawn; let M be the midpoint of side AB. Prove that $MA_1 = MB_1$.

2.96. In convex quadrilateral $ABCD$ angles $\angle A$ and $\angle C$ are right ones. Prove that $AC = BD \sin ABC$.

2.97. Diagonals AD, BE and CF of an inscribed hexagon $ABCDEF$ meet at one point. Prove that $AB \cdot CD \cdot EF = BC \cdot DE \cdot AF$.

2.98. In a convex quadrilateral $AB = BC = CD$, let M be the intersection point of diagonals, K is the intersection point of bisectors of angles $\angle A$ and $\angle D$. Prove that points A, M, K and D lie on one circle.

2.99. Circles centered at O_1 and O_2 intersect at points A and B. Line O_1A intersects the circle centered at O_2 at point N. Prove that points O_1, O_2, B and N lie on one circle.

2.100. Circles S_1 and S_2 intersect at points A and B. Line MN is tangent to circle S_1 at point M and to S_2 at point N. Let A be the intersection point of the circles, which is more distant from line MN. Prove that $\angle O_1AO_2 = 2\angle MAN$.

2.101. Given quadrilateral $ABCD$ inscribed in a circle and such that $AB = BC$, prove that $S_{ABCD} = \frac{1}{2}(DA+CD)\cdot h_b$, where h_b is the height of triangle ABD dropped from vertex B.

2.102. Quadrilateral $ABCD$ is an inscribed one and AC is the bisector of angle $\angle DAB$. Prove that $AC \cdot BD = AD \cdot DC + AB \cdot BC$.

2.103. In right triangle ABC, bisector CM and height CH are drawn from the vertex of the right angle $\angle C$. Let HD and HE be bisectors of triangles AHC and CHB. Prove that points C, D, H, E and M lie on one circle.

2.104. Two circles pass through the vertex of an angle and a point on its bisector. Prove that the segments cut by them on the sides of the angle are equal.

2.105. Triangle BHC, where H is the orthocenter of triangle ABC is complemented to the parallelogram $BHCD$. Prove that $\angle BAD = \angle CAH$.

2.106. Outside equilateral triangle ABC but inside angle $\angle BAC$, point M is taken so that $\angle CMA = 30^\circ$ and $\angle BMA = \alpha$. What is the value of angle $\angle ABM$?

2.107. Prove that if the inscribed quadrilateral with perpendicular diagonals is also a circumscribed one, then it is symmetric with respect to one of its diagonals.

Solutions

2.1. Let us draw diameter AD. Then $\angle CDA = \angle CBA$; hence, $\angle BAH = \angle DAC$ because $\angle BHA = \angle ACD = 90^\circ$.

2.2. Let us make use of the properties of oriented angles:

$$\angle(AC, CK) = \angle(AM, MK) = \angle(BM, MK) = \angle(BD, DK) = \angle(BD, CK),$$

i.e., $AC \parallel BD$.

2.3. Points P and Q lie on the circle with diameter AM. Therefore, $\angle QMA = \angle QPA$ as angles that intersect the same arc. Triangles PAK and MAQ are right ones, therefore, $\angle PAK = \angle MAQ$.

2.4. a) Since

$$\angle AOM = \angle BAO + \angle ABO = \frac{\angle A + \angle B}{2}$$

and

$$\angle OAM = \angle OAC + \angle CAM = \frac{\angle A}{2} + \angle CBM = \frac{\angle A + \angle B}{2},$$

we have $MA = MO$. Similarly, $MC = MO$.

Since triangle OAO_b is a right one and $\angle AOM = \angle MAO = \varphi$, it follows that $\angle MAO_b = \angle MO_bA = 90^\circ - \varphi$ and, therefore, $MA = MO_b$. Similarly, $MC = MO_b$.

b) Let P be the center of the circumscribed circle of triangle ACO. Then

$$\angle COP = \frac{180^\circ - \angle CPO}{2} = 90^\circ - \angle OAC.$$

Hence, $\angle BOC = 90^\circ + \angle OAC$. Similarly, $\angle BOC = 90^\circ + \angle OAB$ and, therefore, $\angle OAB = \angle OAC$. We similarly establish that point O lies on the bisectors of angles $\angle B$ and $\angle C$.

2.5. Points P and C lie on the circle with diameter AB, and, therefore, $\angle APC = \angle ABC$, i.e., the value of angle $\angle APC$ is a constant.

Remark. A similar statement is true for any triangle ABC whose vertices are moving along the legs of angle $\angle MPN$ equal to $180^\circ - \angle C$.

2.6. Points B, D and K lie on the circle with diameter AC. Let, for definiteness sake, $\angle KCA = \varphi \leq 45^\circ$. Then

$$BK = AC \sin(45^\circ - \varphi) = \frac{AC(\cos\varphi - \sin\varphi)}{\sqrt{2}}$$

and

$$DK = AC \sin(45^\circ + \varphi) = \frac{AC(\cos\varphi + \sin\varphi)}{\sqrt{2}}.$$

Clearly, $AC\cos\varphi = CK$ and $AC\sin\varphi = AK$.

2.7. Since $\angle B_1AA_1 = \angle A_1BB_1$, it follows that points A, B, A_1 and B_1 lie on one circle. Parallel lines AB and A_1B_1 intercept on it equal chords AB_1 and BA_1. Hence, $AC = BC$.

2.8. On side BC of triangle ABC construct outwards an equilateral triangle A_1BC. Let P be the intersection point of line AA_1 with the circumscribed circle of triangle A_1BC. Then point P lies inside triangle ABC and

$$\angle APC = 180^\circ - \angle A_1PC = 180^\circ - \angle A_1BC = 120^\circ.$$

Similarly, $\angle APB = 120^\circ$.

2.9. The bases of perpendiculars dropped from point M on the diameters lie on the circle S with diameter OM (where O is the center of the initial circle). The intersection points of the given diameters with circle S distinct from O divide the circle into n arcs. Since the angles $\frac{180^\circ}{n}$ intersect all the circles that do not contain point O, the angle measure of each of these arcs is equal to $\frac{360^\circ}{n}$. Therefore, the angle measure of the arc on which point O lies is equal to $360^\circ - (n-1)\cdot\frac{360^\circ}{n} = \frac{360^\circ}{n}$. Thus, the bases of the perpendiculars divide the circle S into n equal arcs.

2.10. Clearly,

$$\angle(AA_1, BB_1) = \angle(AA_1, AB_1) + \angle(AB_1, BB_1) = \angle(MA_1, MB_1) + \angle(AN, BN).$$

Since $MA_1 \perp BN$ and $MB_1 \perp AN$, it follows that

$$\angle(MA_1, MB_1) = \angle(BN, AN) = -\angle(AN, BN).$$

Therefore, $\angle(AA_1, BB_1) = 0°$, i.e., $AA_1 \parallel BB_1$.

2.11. Since $AB \parallel DE$, it follows that $\angle ACE = \angle BFD$ and since $BC \parallel EF$, it follows that $\angle CAE = \angle BDF$. Triangles ACE and BDF have two pairs of equal angles and, therefore, their third angles are also equal. The equality of these angles implies the equality of arcs $\smile AC$ and $\smile DF$, i.e., chords CD and AF are parallel.

2.12. Let us carry out the proof by induction on n. For the quadrilateral the statement is obvious; for the hexagon it had been proved in the preceding problem. Assume that the statement is proved for the $2(n-1)$-gon; let us prove the statement for the $2n$-gon. Let $A_1 \dots A_{2n}$ be a $2n$-gon in which $A_1A_2 \parallel A_{n+1}A_{n+2}, \dots, A_{n-1}A_n \parallel A_{2n-1}A_{2n}$. Let us consider $2(n-1)$-gon $A_1A_2 \dots A_{n-1}A_{n+1} \dots A_{2n-1}$. By the inductive hypothesis for n odd we have $A_{n-1}A_{n+1} = A_{2n-1}A_1$, and for n even we have $A_{n-1}A_{n+1} \parallel A_{2n-1}A_1$.

Let us consider triangles $A_{n-1}A_nA_{n+1}$ and $A_{2n-1}A_{2n}A_1$. Let n be even. Then vectors $\{A_{n-1}A_n\}$ and $\{A_{2n-1}A_{2n}\}$, as well as $\{A_{n-1}A_{n+1}\}$ and $\{A_{2n-1}A_1\}$ are parallel and directed towards each other; hence, $\angle A_nA_{n-1}A_{n+1} = \angle A_1A_{2n-1}A_{2n}$ and $A_nA_{n+1} = A_{2n}A_1$ as chords that cut equal arcs, as required.

Let n be odd. Then $A_{n-1}A_{n+1} = A_{2n-1}A_1$, i.e., $A_1A_{n-1} \parallel A_{n+1}A_{2n-1}$. In hexagon $A_{n-1}A_nA_{n+1}A_{2n-1}A_{2n}A_1$ we have $A_1A_{n-1} \parallel A_{n+1}A_{2n-1}$ and $A_{n-1}A_n \parallel A_{2n-1}A_{2n}$; hence, thanks to the preceding problem $A_nA_{n+1} \parallel A_{2n}A_1$, as required.

2.13. Let lines FG, GE and EF pass through points A, B and C, respectively, so that triangle EFG is an equilateral one, i.e.,

$$\angle(GE, EF) = \angle(EF, FG) = \angle FG, GE) = \pm 60°.$$

Then

$$\angle(BE, EC) = \angle(CF, FA) = \angle(AG, GB) = \pm 60°.$$

Selecting one of the signs we get three circles S_E, S_F and S_G on which points E, F and G should lie. Any point E of circle S_E uniquely determines triangle EFG.

Let O be the center of triangle EFG; let P, R and Q be the intersection points of lines OE, OF and OG with the corresponding circles S_E, S_F and S_G. Let us prove that P, Q and R are the centers of equilateral triangles constructed on sides of triangle ABC (outwards for one family and inwards for the other one), and point O lies on the circumscribed circle of triangle PQR.

Clearly,

$$\angle(CB, BP) = \angle(CE, EP) = \angle(EF, EO) = \mp 30°$$

and

$$\angle(BP, CP) = \angle(BE, EC) = \angle(GE, EF) = \pm 60°.$$

Hence,

$$\angle(CB, CP) = \angle(CB, BP) + \angle(BP, CP) = \pm 30°.$$

Therefore, P is the center of an equilateral triangle with side AB.

For points Q and R the proof is similar. Triangle PQR is an equilateral one and its center coincides with the intersection point of medians of triangle ABC (cf. Problem 1.49 b)). As is not difficult to verify,

$$\angle(PR, RQ) = \mp 60° = \angle(OE, OG) = \angle(OP, OQ),$$

i.e., point O lies on the circumscribed circle of triangle PQR.

2.14. Clearly,

$$2(\angle KEC + \angle KDC) = (\smile MB + \smile AC) + (\smile MB + \smile BC) = 360^\circ,$$

since $\smile MB = \smile AM$.

2.15. Denote the angle measure of the arc intercepted on the circle by the sides of triangle ABC by α. Denote the angle measure of the arc intercepted by the extensions of the sides of the triangle on the circle by α'. Then $\frac{1}{2}(\alpha + \alpha') = \angle BAC = 60^\circ$. But $\alpha = \alpha'$ because these arcs are symmetric through the line that passes through the center of the circle parallel to side BC. Hence, $\alpha = \alpha' = 60^\circ$.

2.16. Since $\angle APB = \frac{1}{2}(\smile AB + \smile CD) = \angle AOB$, point O lies on the circumscribed circle of triangle APB.

2.17. Let O be the point where lines A_1C_1 and B_1D_1 meet; let α, β, γ and δ be angle measures of arcs AB, BC, CD and DA. Then

$$\angle A_1OB_1 = \frac{\smile A_1B + \smile BB_1 + \smile C_1D + \smile DD_1}{2} = \frac{\alpha + \beta + \gamma + \delta}{4} = 90^\circ.$$

2.18. By summing up the equalities we get

$$\smile C'A + \smile CA' = 2(180^\circ - \angle APC) = 240^\circ - 2\angle B \quad \text{and} \quad \smile AB' + \smile BA' = 240^\circ - 2\angle C.$$

Then by subtracting from their sum the equality $\smile BA' + \smile CA' = 2\angle A$ we get

$$\smile C'B' = \smile C'A + \smile AB' = 480^\circ - 2(\angle A + \angle B + \angle C) = 120^\circ.$$

Similarly, $\smile B'A' = \smile C'A' = 120^\circ$.

2.19. a) Let us prove, for example, that $AA_1 \perp C_1B_1$. Let M be the intersection point of these segments. Then

$$\angle AMB_1 = \frac{\smile AB_1 + \smile A_1B + \smile BC_1}{2} = \angle ABB_1 + \angle A_1AB + \angle BCC_1 = \frac{\angle B + \angle A + \angle C}{2} = 90^\circ.$$

b) Let M_1 and M_2 be the intersection points of segments AA_1 with BC and BB_1 with AC. Right triangles AM_1C and BM_2C have a common angle $\angle C$; hence, $\angle B_1BC = \angle A_1AC$. Consequently, $\smile B_1C = \smile A_1C$ and $\angle B_1C_1C = \angle A_1C_1C$, i.e., CC_1 is the bisector of angle $\angle A_1C_1B_1$.

2.20. Denote the vertices of triangle T_1 by A, B and C; denote the midpoints of arcs $\smile BC$, $\smile CA$, $\smile AB$ by A_1, B_1, C_1, respectively. Then $T_2 = A_1B_1C_1$. Lines AA_1, BB_1, CC_1 are the bisectors of triangle T_1; hence, they meet at one point, O. Let lines AB and C_1B_1 intersect at point K. It suffices to verify that $KO \parallel AC$. In triangle AB_1O, line B_1C_1 is a bisector and height, hence, this triangle is an isosceles one. Therefore, triangle AKO is also an isosceles one. Lines KO and AC are parallel, since $\angle KOA = \angle KAO = \angle OAC$.

2.21. Let l be tangent to the first circle at point A. Then $\angle(l, AP) = \angle(AQ, PQ) = \angle(BC, PB)$, hence, $l \parallel BC$.

2.22. Since

$$\angle(AB, AD) = \angle(AP, PD) = \angle(AB, BC),$$

we have $BC \parallel AD$.

2.23. Let, for definiteness, point E lie on ray BC. Then $\angle ABC = \angle EAC$ and

$$\angle ADE = \angle ABC + \angle BAD = \angle EAC + \angle CAD = \angle DAE.$$

2.24. Let P be the other intersection point of the circles. Then $\angle(AB, DB) = \angle(PA, PB)$ and $\angle(DC, AC) = \angle(PC, PA)$. By summing these equalities we get

$$\angle(DC, DB) = \angle(PC, PB) = \angle(PC, CA) + \angle(BA, PB).$$

The latter two angles subtend constant arcs.

2.25. a) Since $\angle MAB = \angle BNA$, the sum of angles $\angle ABN$ and $\angle MAN$ is equal to the sum of the angles of triangle ABN.

b) Since $\angle BAM = \angle BNA$ and $\angle BAN = \angle BMA$, it follows that $\triangle AMB \sim \triangle NAB$ and, therefore, $AM : NA = MB : AB$ and $AM : NA = AB : NB$. By multiplying these equalities we get the desired statement.

2.26. Point P lies on the circle of radius BC with center B and line DC is tangent to this circle at point C. Hence, $\angle PCD = \frac{1}{2}\angle PBC = 15^\circ$.

2.27. Let A_1 and B_1 be intersection points of lines MA and MB, respectively, with the smaller circle. Since M is the center of homothety of the circles, $A_1B_1 \parallel AB$. Hence, $\angle A_1MT = \angle A_1TA = \angle B_1A_1T = \angle B_1MT$.

2.28. Let φ be the angle between chord AB and the tangent that passes through one of the chord's endpoints. Then $AB = 2R\sin\varphi$, where R is the radius of circle S. Moreover, $PM = AM\sin\varphi$ and $QM = BM\sin\varphi$. Hence,

$$\frac{1}{PM} + \frac{1}{QM} = \left(\frac{AM + BM}{\sin\varphi}\right) AM \cdot BM = \frac{2R}{AM \cdot BM}.$$

The value $AM \cdot BM$ does not depend on the choice of chord AB.

2.29. Let line AM intersect circle S_2 at point D. Then $\angle MDC = \angle MCA = \angle MAB$; hence, $CD \parallel AB$. Further, $\angle CAM = \angle MCB = \angle MDB$; hence, $AC \parallel BD$. Therefore, $ABCD$ is a parallelogram and its diagonal AD divides diagonal BC in halves.

2.30. Let us draw line l_1 tangent to S_1 at point A_1. Line K_1K_2 is tangent to S_1 if and only if $\angle(K_1K_2, K_1A_1) = \angle(K_1A_1, l_1)$. It is also clear that

$$\angle(K_1A_1, l_1) = \angle(A_1B, l_1) = \angle(A_2B, A_1A_2).$$

Similarly, line K_1K_2 is tangent to S_2 if and only if $\angle(K_1K_2, K_2A_2) = \angle(A_1B, A_1A_2)$. It remains to observe that if $\angle(K_1K_2, K_1A_1) = \angle(A_2B, A_1A_2)$, then

$$\angle(K_1K_2, K_2A_2) = \angle(K_1K_2, A_2B) =$$
$$\angle(K_1K_2, A_1B) + \angle(A_1B, A_1A_2) + \angle(A_1A_2, A_2B) = \angle(A_1B, A_1A_2).$$

2.31. Equal angles ABC and $A_1B_1C_1$ intersect chords AC and A_1C_1, hence, $AC = A_1C_1$.

2.32. Let us denote the center of the circle by O. Points P and Q lie on the circle with diameter OM, i.e., points O, P, Q and M lie on a circle of radius $\frac{1}{2}R$. Moreover, either $\angle POQ = \angle AOD$ or $\angle POQ = \angle BOD = 180^\circ - \angle AOD$, i.e., the length of chord PQ is a constant.

2.33. Since $\angle AOC = 90^\circ + \frac{1}{2}\angle B$ (cf. Problem 5.3), it follows that

$$\angle EBD + \angle EOD = 90^\circ + \frac{3}{2}\angle B = 180^\circ$$

and, therefore, quadrilateral $BEOD$ is an inscribed one. Equal angles $\angle EBO$ and $\angle OBD$ subtend chords EO and OD, hence, $EO = OD$.

2.34. On the extension of segment BD beyond point D take a point Q such that $\angle ACQ = 40^\circ$. Let P be the intersection point of lines AB and QC. Then $\angle BPC = 60^\circ$ and D is the intersection point of the bisectors of angles of triangle BCP. By Problem 2.33 $AD = DQ$. Moreover, $\angle BQC = \angle BCQ = 80^\circ$. Therefore, $BC = BD + DQ = BD + DA$.

2.35. It suffices to verify that the exterior angle ACD of triangle BCD is twice greater than the angle at vertex B. Clearly, $\angle ACD = \angle AOD = 2\angle ABD$.

2.36. Let O be the center of circle S. Point B is the center of the circumscribed circle of triangle ACD, hence, $\angle CDA = \frac{1}{2}\angle ABC = 30^\circ$ and, therefore, $\angle EOA = 2\angle EDA = 60^\circ$, i.e., triangle EOA is an equilateral one. Moreover, $\angle AEC = \angle AED = \angle AOB = 2\angle AOC$; hence, point E is the center of the circumscribed circle of triangle AOC. Therefore, $EC = EO$.

2.37. Let us consider two positions of the moving circle: at the first moment, when point K just gets to the fixed circle (the tangent point of the circles at this moment will be denoted by K_1) and at some other (second) moment.

Let O be the center of the fixed circle, O_1 and O_2 be the positions of the center of the moving circle at the first and the second moments, respectively, K_2 be the position of point K at the second moment. Let A be the tangent point of the circles at the second moment. Since the moving circle rolls without gliding, the length of arc $\smile K_1A$ is equal to the length of arc $\smile K_2A$. Since the radius of the moving circle is one half of the radius of the fixed circle, $\angle K_2O_2A = 2\angle K_1OA$. Point O lies on the moving circle, hence, $\angle K_2OA = \frac{1}{2}\angle K_2O_2A = \angle K_1OA$, i.e., points K_2, K_1 and O lie on one line.

The trajectory of point K is the diameter of the fixed circle.

2.38. Points N and C lie on the circle with diameter AM. Angles $\angle MAN$ and $\angle MCN$ subtend the same arc and therefore, are equal.

2.39. The symmetry through the bisector of angle $\angle BOC$ sends lines AC and DB into each other and, therefore, we have to prove that $\angle C'AB' = \angle B'DC'$. Since $BO = B'O$, $CO = C'O$ and $AO : DO = CO : BO$, it follows that $AO \cdot B'O = DO \cdot C'O$, i.e., the quadrilateral $AC'B'D$ is an inscribed one and $\angle C'AB' = \angle B'DC'$.

2.40. Denote the intersection points and angles as indicated on Fig. 14.



Figure 14 (Sol. 2.40)

It suffices to verify that $x = 90^\circ$. The angles of quadrilateral $BMRN$ are equal to $180^\circ - \varphi$, $\alpha + \varphi$, $\beta + \varphi$ and x, hence, the equality $x = 90^\circ$ is equivalent to the equality $(2\alpha+\varphi)+(2\beta+\varphi) = 180^\circ$. It remains to notice that $2\alpha+\varphi = \angle BAD$ and $2\beta+\varphi = \angle BCD$.

2.41. a) It suffices to prove that if P_1 is the point on the bisector (or its extension) of angle $\angle B$ that serves as the vertex of an angle of 90° that subtends segment BC, then P_1 lies on line MN. Points P_1 and N lie on the circle with diameter CO, where O is the intersection point of bisectors, hence,

$$\angle(P_1N, NC) = \angle(P_1O, OC) = \frac{1}{2}(180^\circ - \angle A) = \angle(MN, NC).$$

b) Since $\angle BPC = 90°$, it follows that $BP = BC \cdot \cos\frac{\angle B}{2}$; hence,

$$S_{ABP} : S_{ABC} = \left(BP \cdot \sin\frac{\angle B}{2}\right) : (BC \sin B) = 1 : 2.$$

2.42. Take point N so that $BN \parallel MC$ and $NC \parallel BM$. Then $NA \parallel CD$, $\angle NCB = \angle CBM = \angle CDM = \angle NAB$, i.e., points A, B, N and C lie on one circle. Hence, $\angle ACD = \angle NAC = \angle NBC = \angle BCM$.

2.43. Points A_2, B_2, C and P lie on one circle, hence,

$$\angle(A_2B_2, B_2P) = \angle(A_2C, CP) = \angle(BC, CP).$$

Similarly, $\angle(B_2P, B_2C_2) = \angle(AP, AB)$. Therefore,

$$\begin{aligned}\angle(A_2B_2, B_2C_2) &= \angle(BC, CP) + \angle(AP, AB) = \angle(B_1B, B_1C_1) + \angle(A_1B_1, B_1B)\\ &= \angle(A_1B_1, B_1C_1).\end{aligned}$$

We similarly verify that all the other angles of triangles $A_1B_1C_1$ and $A_2B_2C_2$ are either equal or their sum is equal to $180°$; therefore, these triangles are similar (cf. Problem 5.42).

2.44. Points Q' and C lie on the circle with diameter PQ, hence, $\angle Q'CQ = \angle Q'PQ = 30°$. Therefore, $\angle BCQ' = 60°$. Similarly, $\angle CBQ' = 60°$ and, therefore, triangle $BQ'C$ is equilateral one. By similar reasons triangle $CP'D$ is an equilateral one.

2.45. Let $\angle BAD = 2\alpha$ and $\angle CBA = 2\beta$; for definiteness we will assume that $\alpha \geq \beta$. On side CD take point E so that $DE = DA$. Then $CE = CD - AD = CB$. The angle at vertex C of an isosceles triangle BCE is equal to $180° - 2\alpha$; hence, $\angle CBE = \alpha$. Similarly, $\angle DAE = \beta$. The bisector of angle B intersects CD at a point F. Since $\angle FBA = \beta = \angle AED$, quadrilateral $ABFE$ is an inscribed one and, therefore, $\angle FAE = \angle FBE = \alpha - \beta$. It follows that $\angle FAD = \beta + (\alpha - \beta) = \alpha$, i.e., AF is the bisector of angle $\angle A$.

2.46. Since $ED = CB$, $EN = CM$ and $\angle DEC = \angle BCA = 30°$ (Fig. 15), it follows that $\triangle EDN = \triangle CBM$. Let $\angle MBC = \angle NDE = \alpha$, $\angle BMC = \angle END = \beta$.



Figure 15 (Sol. 2.46)

It is clear that $\angle DNC = 180° - \beta$. Considering triangle BNC we get $\angle BNC = 90° - \alpha$. Since $\alpha + \beta = 180° - 30° = 150°$, it follows that

$$\angle DNB = \angle DNC + \angle CNB = (180° - \beta) + (90° - \alpha) = 270° - (\alpha + \beta) = 120°.$$

Therefore, points B, O, N and D, where O is the center of the hexagon, lie on one circle. Moreover, $CO = CB = CD$, i.e., C is the center of this circle, hence, $\lambda = CN : CE = CB : CA = 1 : \sqrt{3}$.

2.47. Let D be the other intersection point of the circumscribed circles of triangles A_1BC and AB_1C. Then $\angle(AC, CD) = \angle(AB_1, B_1D)$ and $\angle(DC, CB) = \angle(DA_1, A_1B)$.

Hence,

$$\begin{aligned}\angle(A_1C_1, C_1B_1) &= \angle(AC, CB) = \angle(AC, CD) + \angle(DC, CB) \\ &= \angle(AB_1, B_1D) + \angle(DA_1, A_1B) = \angle(A_1D, DB_1),\end{aligned}$$

i.e., points A_1, B_1, C_1 and D lie on one circle. Therefore, $\angle(A_1C_1, C_1B) = \angle(A_1B_1, B_1D) = \angle(AC, CD)$. Taking into account that $A_1C_1 \parallel AC$, we get the desired statement.

2.48. Let point M be symmetric to point A_1 through line AC. By Problem 1.57 point M lies on line B_1C_1. Therefore,

$$\angle(LM, MA_1) = \angle(C_1B_1) = \angle(C_1C, CB) = \angle(LK, KA_1),$$

i.e., point M lies on the circumscribed circle of triangle A_1KL. It follows that the center of this circle lies on line AC — the midperpendicular to segment A_1M.

2.49. Let PQ be the diameter perpendicular to AB and such that Q and C lie on one side of AB; let L be the intersection point of line QO with the circumscribed circle; let M' and N' be the intersection points of lines LB' and LA' with sides AC and BC, respectively. It suffices to verify that $M' = M$ and $N' = N$.

Since $\smile PA + \smile AB' + \smile B'Q = 180^\circ$, it follows that $\smile B'Q = \angle A$ and, therefore, $\angle B'LQ = \angle M'AO$. Hence, quadrilateral $AM'OL$ is an inscribed one and $\angle M'OA = \angle M'LA = \frac{1}{2}\angle B$. Therefore, $\angle CMO = \frac{1}{2}(\angle A + \angle B)$, i.e., $M' = M$. Similarly, $N' = N$.

2.50. Since $\triangle ADM \sim \triangle CBM$ and $\triangle ACM \sim \triangle DBM$, it follows that $AD : CB = DM : BM$ and $AC : DB = AM : DM$. It remains to multiply these equalities.

2.51. Let D_1 be the intersection point of line BD with the circle distinct from point B. Then $\smile AB = \smile AD_1$; hence, $\angle ACB = \angle AD_1B = \angle ABD_1$. Triangles ACB and ABD have a common angle, $\angle A$, and, moreover, $\angle ACB = \angle ABD$; hence, $\triangle ACB \sim \triangle ABD$. Therefore, $AB : AC = AD : AB$.

2.52. Let O be the center of the circle. Since $\angle MAC = \angle ACO = \angle CAO$, it follows that $\triangle AMC = \triangle ADC$. Similarly, $\triangle CDB = \triangle CNB$. Since $\triangle ACD \sim \triangle CDB$, it follows that $CD^2 = AD \cdot DB = AM \cdot NB$.

2.53. Points B_1 and H lie on the circle with diameter AB, hence,

$$\angle(AB, BC) = \angle(AB, BH) = \angle(AB_1, B_1H) = \angle(B_1C_1, B_1H).$$

Similarly, $\angle(AC, BC) = \angle(B_1C_1, C_1H)$.

2.54. On an extension of segment BP beyond point P take point D such that $PD = CP$. Then triangle CDP is an equilateral one and $CD \parallel QP$. Therefore, $BP : PQ = BD : DC = (BP + CP) : CP$, i.e., $\frac{1}{PQ} = \frac{1}{CP} + \frac{1}{BP}$.

2.55. Segment QE subtends angles of 45° with vertices at points A and B, hence, quadrilateral $ABEQ$ is an inscribed one. Since $\angle ABE = 90^\circ$, it follows that $\angle AQE = 90^\circ$. Therefore, triangle AQE is an isosceles right triangle and $\frac{AE}{AQ} = \sqrt{2}$. Similarly, $\frac{AF}{AP} = \sqrt{2}$.

2.56. Since $\angle ANC = \angle ABC = \angle CAB$, it follows that $\triangle CAM \sim \triangle CNA$ and, therefore, $CA : CM = CN : CA$, i.e., $CM \cdot CN = AC^2$ and $AM : NA = CM : CA$. Similarly, $BM : NB = CM : CB$. Therefore,

$$\frac{AM \cdot BM}{AN \cdot BN} = \frac{CM^2}{CA^2} = \frac{CM^2}{CM \cdot CN} = \frac{CM}{CN}.$$

2.57. Since $AK = AB = CD$, $AD = BC = CH$ and $\angle KAD = \angle DCH$, it follows that $\triangle ADK = \triangle CHD$ and $DK = DH$. Let us show that points A, K, H, C and D lie on one circle. Let us circumscribe the circle about triangle ADC. Draw chord CK_1 in this circle parallel to AD and chord AH_1 parallel to DC. Then $K_1A = DC$ and $H_1C = AD$. Hence, $K_1 = K$ and $H_1 = H$, i.e., the constructed circle passes through points K and H and angles

$\angle KAH$ and $\angle KDH$ are equal because they subtend the same arc. Moreover, as we have already proved, KDH is an isosceles triangle.

2.58. a) $\angle PBA_1 = \angle PAC_1$ and $\angle PBC_1 = \angle PAB_1$ and, therefore, right triangles PBA_1 and PAC_1, PAB_1 and PBC_1 are similar, i.e., $PA_1 : PB = PC_1 : PA$ and $PB_1 : PA = PC_1 : PB$. By multiplying these equalities we get $PA_1 \cdot PB_1 = PC_1^2$.

b) According to heading a)

$$OA'' = \sqrt{OB' \cdot OC'}, \quad OB'' = \sqrt{OA' \cdot OC'}, \quad OC'' = \sqrt{OA' \cdot OB'}.$$

By multiplying these equalities we get the desired statement.

2.59. Let K, L, M and N be the bases of perpendiculars dropped from point E to lines AB, BC, CD and DA, respectively. Points K and N lie on the circle with diameter AE, hence, $\angle(EK, KN) = \angle(EA, AN)$. Similarly, $\angle(EL, LM) = \angle(EC, CM) = \angle(EA, AN)$ and, therefore, $\angle(EK, KN) = \angle(EL, LM)$. Similarly, $\angle(EN, NK) = \angle(EM, ML)$ and $\angle(KE, EN) = \angle(LE, EM)$. It follows that $\triangle EKN \sim \triangle ELM$ and, therefore, $EK : EN = EL : EM$, i.e., $EN = \frac{EK \cdot EM}{EL} = \frac{ac}{b}$.

2.60. Let H be the intersection point of heights, M the midpoint of side BC. Points A_1, B_2 and C_2 lie on the circle with diameter MH, hence, $\angle(B_2A_1, A_1C_2) = \angle(B_2M, MC_2) = \angle(AC, AB)$. Moreover, $\angle(A_1B_2, B_2C_2) = \angle(A_1H, HC_2) = \angle(BC, AB)$ and $\angle(A_1C_2, C_2B_2) = \angle(BC, AC)$.

2.61. Let M be the intersection point of medians, H the intersection point of heights of triangle ABC. Points A_1, B_1 and C_1 are the projections of point M on the heights and, therefore, these points lie on the circle with diameter MH. Hence, $\angle(A_1B_1, B_1C_1) = \angle(AH, HC) = \angle(BC, AB)$. By writing similar equalities for the other angles we get the desired statement.

2.62. Let lines BM and DN meet S_2 at points L and C_1, respectively. Let us prove that lines DC_1 and CN are symmetric through line AN. Since $BN \perp NA$, it suffices to verify that $\angle CNB = \angle BND$. But arcs $\smile CB$ and $\smile BD$ are equal. Arcs $\smile C_1M$ and $\smile CL$ are symmetric through line AN, hence, they are equal and, therefore, $\angle MDC_1 = \angle CML$. Besides, $\angle CNM = \angle MND$. Thus, $\triangle MCN \sim \triangle DMN$, i.e., $CN : MN = MN : DN$.

2.63. Let us drop from point Q perpendiculars QK_1 and QN_1 to KL and NM, respectively, and from point P perpendiculars PM_1 and PL_1 to NM and KL, respectively. Clearly, $\frac{QC}{PC} = \frac{QK_1}{PL_1} = \frac{QN_1}{PM_1}$, i.e., $\frac{QC^2}{PC^2} = \frac{QK_1 \cdot QN_1}{PL_1 \cdot PM_1}$. Since $\angle KNC = \angle MLC$ and $\angle NKC = \angle LMC$, it follows that $QN_1 : PL_1 = QN : PL$ and $QK_1 : PM_1 = QK : PM$. Therefore,

$$\frac{QC^2}{PC^2} = \frac{QK \cdot QN}{PL \cdot PM} = \frac{AQ \cdot QB}{PB \cdot AP} = \frac{(AC - QC) \cdot (AC + QC)}{(AC - PC) \cdot (AC + PC)} = \frac{AC^2 - QC^2}{AC^2 - PC^2}.$$

This implies that $QC = PC$.

2.64. a) Since $\angle CAM = \angle CBM$ and $\angle CB_1M = \angle CA_1M$, it follows that $\angle B_1AM = \angle A_1BM$ and $\angle AB_1M = \angle BA_1M$.

b) Let M_1 be a point of the circle S with diameter CO such that $CM_1 \parallel A_1B_1$; let M_2 be an intersection point of circle S with the circumscribed circle of triangle ABC; let A_2 and B_2 be the tangent points of of the inscribed circle with sides BC and AC, respectively. It suffices to verify that $M_1 = M_2$. By Problem a) $\triangle AB_2M_2 \sim \triangle BA_2M_2$, hence, $B_2M_2 : A_2M_2 = AB_2 : BA_2$. Since $CA_1 = p - b - BA_2$ and $CB_1 = AB_2$, it follows that

$$\frac{B_2M_1}{A_2M_1} = \frac{\sin B_2CM_1}{\sin A_2CM_1} = \frac{\sin CA_1B_1}{\sin CB_1A_1} = \frac{CB_1}{CA_1} = \frac{AB_2}{BA_2}.$$

On arc $\smile A_2CB_2$ of circle S, there exists a unique point X for which $B_2X : A_2X = k$ (Problem 7.14), hence, $M_1 = M_2$.

2.65. Let O be the center of the circumscribed circle of the triangle, M the midpoint of side AB, H the base of height CH, D the midpoint of the arc on which point C does not lie and with endpoints A and B. Since $OD \parallel CH$, it follows that $\angle DCH = \angle MDC$. The bisector divides the angle between the median and the height in halves if and only if $\angle MCD = \angle DCH = \angle MDC = \angle ODC = \angle OCD$, i.e., $M = O$ and AB is the diameter of the circle.

2.66. Let $\alpha = \angle A < \angle B$. By the preceding problem $\angle C = 90^\circ$. Median CM divides triangle ABC into two isosceles triangles. Since $\angle ACM = \angle A = \alpha$, $\angle MCB = 3\alpha$, it follows that $\alpha + 3\alpha = 90^\circ$, i.e., $\alpha = 22.5^\circ$. Therefore, $\angle A = 22.5^\circ$, $\angle B = 67.5^\circ$, $\angle C = 90^\circ$.

2.67. Let D be a point at which line AE intersects the circumscribed circle. Point D is the midpoint of arc $\smile BC$. Therefore, $MD \parallel AH$, moreover, points A and D lie on different sides of line MH. It follows that point E lies on segment MH.

2.68. Clearly,

$$\angle(AQ, QP) = \angle(AN, NP) = \angle(PM, MB) = \angle(QP, QB).$$

Therefore, point Q lies on the circle such that segment AB subtends an angle of $2\angle(AC, CB)$ with vertex at Q and line QP divides arc $\smile AB$ of this circle in halves.

2.69. Points P and Q lie on the circle with diameter AD; this circle intersects side BC at point F. (Observe that F does not coincide with D if $AB \neq AC$.) Clearly,

$$\angle(FC, CE) = \angle(BA, AE) = \angle(DA, AQ) = \angle(DF, FQ), \text{ i.e., } EC \parallel FQ.$$

Similarly, $BE \parallel FP$. To complete the proof it suffices to notice that the areas of triangles adjacent to the lateral sides of the trapezoid are equal.

2.70. Let $\angle AOB = \alpha$ and $\angle COD = \beta$. Then $\frac{\alpha}{2} + \frac{\beta}{2} = \angle ADP + \angle PAD = 90^\circ$. Since $2S_{AOB} = R^2 \sin\alpha$ and $2S_{COD} = R^2 \sin\beta$, where R is the radius of the circumscribed circle, it follows that $S_{AOB} = S_{COD}$. Similarly, $S_{BOC} = S_{AOD}$.

2.71. Let $\angle AOB = 2\alpha$ and $\angle COD = 2\beta$. Then $\alpha + \beta = \angle ADP + \angle PAD = 90^\circ$. Hence,

$$(AP^2 + BP^2) + (CP^2 + DP^2) = AB^2 + CD^2 = 4R^2(\sin^2\alpha + \cos^2\alpha) = 4R^2.$$

Similarly, $BC^2 + AD^2 = 4R^2$.

2.72. Let M be the midpoint of AC, N the midpoint of BD. We have $AM^2 = AO^2 - OM^2$ and $BN^2 = BO^2 - ON^2$; hence,

$$AC^2 + BD^2 = 4(R^2 - OM^2) + 4(R^2 - ON^2) = 8R^2 - 4(OM^2 + ON^2) = 8R^2 - 4OP^2$$

since $OM^2 + ON^2 = OP^2$.

2.73. The correspondiong legs of acute angles $\angle BLP$ and $\angle BDC$ are perpendicular, hence, the angles are equal.

Therefore, $\angle BLP = \angle BDC = \angle BAP$. Moreover, $AK \parallel BL$ and $AL \perp BK$. It follows that $AKLB$ is a rhombus.

2.74. In the circumscribed circle take a point D' so that $DD' \parallel AC$. Since $DD' \perp BD$, it follows that BD' is a diameter and, therefore, $\angle D'AB = \angle D'CB = 90^\circ$. Hence,

$$S_{ABCD} = S_{ABCD} = \frac{1}{2}(AD' \cdot AB + BC \cdot CD') = \frac{1}{2}(AB \cdot CD + BC \cdot AD).$$

2.75. Let us draw diameter AE. Since $\angle BEA = \angle BCP$ and $\angle ABE = \angle BPC = 90^\circ$, it follows that $\angle EAB = \angle CBP$. The angles that intersect chords EB and CD are equal, hence, $EB = CD$. Since $\angle EBA = 90^\circ$, the distance from point O to AB is equal to $\frac{1}{2}EB$.

2.76. Let the perpendicular dropped from point P to BC intersect BC at point H and AD at point M (Fig. 16).



Figure 16 (Sol. 2.76)

Therefore, $\angle BDA = \angle BCA = \angle BPH = \angle MPD$. Since angles MDP and MPD are equal, MP is a median of right triangle APD. Indeed,

$$\angle APM = 90^\circ - \angle MPD = 90^\circ - \angle MDP = \angle PAM,$$

i.e., $AM = PM = MD$.

2.77. The midpoints of the sides of quadrilateral $ABCD$ are vertices of a rectangle (cf. Problem 1.2), hence, they lie on one circle. Let K and L be the midpoints of sides AB and CD, let M be the intersection point of lines KP and CD. By Problem 2.76 $PM \perp CD$; hence, M is the projection of point P on side CD and point M lies on the circle with diameter KL.

For the other projections the proof is similar.

2.78. a) It is worth to observe that since points A, B, C and D divide the circle into arcs smaller than 180° each, then the quadrilateral constructed contains this circle. The angle φ between the tangents drawn through points A and B is equal to $180^\circ - \angle AOB$ and the angle ψ between the tangents drawn through points C and D is equal to $180^\circ - \angle COD$. Since $\angle AOB + \angle COD = 180^\circ$, it follows that $\varphi + \psi = 180^\circ$.

Remark. Conversely, the equality $\varphi + \psi = 180^\circ$ implies that $\angle AOB + \angle COD = 180^\circ$, i.e., $AC \perp BD$.

b) Let O be the center of the inscribed circle. Since $\angle AKO + \angle BMO = 90^\circ$, it follows that $\angle AKO = \angle BOM$ and $\triangle AKO \sim \triangle BOM$. Therefore, $AK \cdot BM = BO \cdot AO = r^2$.

2.79. First, let us suppose that the circumscribed circles of triangles $A'BC$ and $AB'C$ are not tangent to each other and P is their common point distinct from C. Then

$$\begin{aligned}\angle(PA, PB) &= \angle(PA, PC) + \angle(PC, PB)\\ &= \angle(B'A, B'C) + \angle(A'C, A'B) = \angle(C'A, C'B),\end{aligned}$$

i.e., point P lies on the circumscribed circle of triangle ABC'.

If the the circumscribed circles of triangles $A'BC$ and $AB'C$ are tangent to each other, i.e., $P = C$, then our arguments require an insignificant modifications: instead of line PC we have to take the common tangent.

2.80. a) By applying the statement of Problem 2.79 to triangles AB_1C_1, A_1BC_1 and A_1B_1C constructed on the sides of triangle $A_1B_1C_1$ we get the desired statement.

b) Let P be the intersection point of the indicated circles. Let us prove that the value of the angle $\angle(AP, PC)$ is a constant. Since

$$\angle(AP, PC) = \angle(AP, AB) + \angle(AB, BC) + \angle(BC, PC)$$

and angle $\angle(AB, BC)$ is a constant, it remains to verify that the sum $\angle(AP, AB)+\angle(BC, PC)$ is a constant. Clearly,

$$\begin{array}{rcl} \angle(AP, AB) + \angle(BC, CP) & = & \angle(AP, AC_1) + \angle(CA_1, CP) = \\ \angle(B_1P, B_1C_1) + \angle(B_1A_1, B_1P) & = & \angle(B_1A_1, B_1C_1) \end{array}$$

and the value of the latter angle is constant by hypothesis.

We similarly prove that the values of angles $\angle(AP, PB)$ and $\angle(BP, PC)$ are constants. Hence, point P remains fixed.

2.81. As follows from Problem 2.80 b) it suffices to carry out the proof for one such triangle $A_1B_1C_1$ only; for instance, for the triangle with vertices in the midpoints of sides of triangle ABC. Let H be the intersection point of heights of triangle $A_1B_1C_1$, i.e., the center of the circumscribed circle of triangle ABC. Since $A_1H \perp B_1C_1$ and $B_1H \perp A_1C_1$, it follows that $\angle(A_1H, HB_1) = \angle(B_1C_1, A_1C_1) = \angle(A_1C, CB_1)$, i.e., point H lies on the circumscribed circle of triangle A_1B_1C.

A similar argument shows that point H lies on the circumscribed circles of triangles A_1BC_1 and AB_1C_1.

2.82. a) Let X be the intersection point of the circumscribed circles of triangles ABC and $AB'C'$. Then

$$\angle(XB', XC) = \angle(XB', XA) + \angle(XA, XC) = \angle(C'B', C'A) + \angle(BA, BC).$$

Since $AC' = AP = AB'$, triangle $C'AB'$ is an isosceles one and $\angle C'AB' = 2\angle A$; hence, $\angle(C'B', C'A) = \angle A - 90^\circ$. Therefore,

$$\angle(XB', XC) = \angle A - 90^\circ + \angle B = 90^\circ - \angle C = \angle(A'B', A'C),$$

i.e., point X lies on the circumscribed circle of triangle $A'B'C$. For the circumscribed circle of triangle $A'BC'$ the proof is similar.

b) Let X be the intersection point of the circumscribed circles of triangles $A'B'C'$ and $A'BC$. Let us prove that X lies on the circumscribed circle of triangle ABC'. Clearly,

$$\angle(XB, XC') = \angle(XB, XA') + \angle(XA', XC') = \angle(CB, CA') + \angle(B'A', B'C').$$

Let A_1, B_1 and C_1 be the midpoints of segments PA', PB' and PC'. Then

$$\angle(CB, CA') = \angle(CP, CA_1) = \angle(B_1P, B_1A_1), \angle(B'A', B'C') = \angle(B_1A_1, B_1C_1)$$

and

$$\angle(AB, AC') = \angle(AP, AC_1) = \angle(B_1P, B_1C_1).$$

It follows that $\angle(XB, XC') = \angle(AB, AC')$.

We similarly prove that point X lies on the circumscribed circle of triangle $AB'C$.

c) Since QA' is the common chord of circles centered at O and I, it follows that $QA' \perp OI$. Similarly, $QB' \perp OJ$ and $QC \perp IJ$. Therefore, sides of angles OJI and $B'QC$, as well as sides of angles OIJ and $A'QC$, are mutually perpendicular, hence, $\sin OJI = \sin B'QC$ and $\sin OIJ = \sin A'QC$. Therefore, $OI : OJ = \sin OJI : \sin OIJ = \sin B'QC : \sin A'QC$. It is also clear that

$$\frac{QI}{QJ} = \frac{\sin QJI}{\sin QIJ} = \frac{\sin(\frac{1}{2}QJC)}{\sin(\frac{1}{2}QIC)} = \frac{\sin QB'C}{\sin QA'C}.$$

Taking into account that $\sin B'QC : \sin QB'C = B'C : QC$ and $\sin A'QC : \sin QA'C = A'C : QC$ we get

$$\frac{OI}{OJ} : \frac{QI}{QJ} = \frac{B'C}{QC} : \frac{A'C}{QC} = 1.$$

2.83. a) The conditions of the problem imply that no three lines meet at one point. Let lines AB, AC and BC intersect the fourth line at points D, E, and F, respectively (Fig. 17).



Figure 17 (Sol. 2.83)

Denote by P the intersection point of circumscribed circles of triangles ABC and CEF distinct from point C. Let us prove that point P belongs to the circumscribed circle of triangle BDF. For this it suffices to verify that $\angle(BP, PF) = \angle(BD, DF)$. Clearly,

$$\begin{aligned}\angle(BP, PF) &= \angle(BP, PC) + \angle(PC, PF) = \angle(BA, AC) + \angle(EC, EF)\\ &= \angle(BD, AC) + \angle(AC, DF) = \angle(BD, DF).\end{aligned}$$

We similarly prove that point P belongs to the circumscribed circle of triangle ADE.

b) Let us make use of notations of Fig. 17. Thanks to heading a), the circumscribed circles of triangles ABC, ADE and BDF pass through point P and, therefore, we can consider them as the circumscribed circles of triangles ABP, ADP and BDP respectively. Therefore, their centers lie on a circle that passes through point P (cf. Problem 5.86).

We similarly prove that the centers of any of the three of given circles lie on a circle that passes through point P. It follows that all the four centers lie on a circle that passes through point P.

2.84. a) Let P be Michel's point for lines AB, BC, CA and A_1B_1. The angles between rays PA, PB, PC and the tangents to circles S_a, S_b, S_c are equal to $\angle(PB_1, B_1A) = \angle(PC_1, C_1A)$, $\angle(PC_1, C_1B) = \angle(PA_1, A_1B)$, $\angle(PA_1, A_1C) = \angle(PB_1, B_1C)$, respectively. Since $\angle(PC_1, C_1A) = \angle(PC_1, C_1B) = \angle(PA_1, A_1C) = \varphi$, it follows that after a rotation through an angle of φ about point P lines PA, PB and PC turn into the tangents to circles S_a, S_b and S_c, respectively, and, therefore, after a rotation through an angle of $90^\circ - \varphi$ these lines turn into lines PO_a, PO_b and PO_c respectively. Moreover,

$$\frac{PO_a}{PA} = \frac{PO_b}{PB} = \frac{PO_c}{PC} = \frac{1}{2}\sin\varphi.$$

Therefore, the composition of the rotation through an angle of $90^\circ - \varphi$ and the homothety (see ???) with center P and coefficient $\frac{1}{2}\sin\varphi$ sends triangle ABC to $O_aO_bO_c$.

b) The transformation considered in the solution of heading a) sends the center O of the circumscribed circle of triangle ABC into the center O' of the circumscribed circle of triangle $O_aO_bO_c$ and the orthocenter H of triangle ABC to orthocenter H' of triangle $O_aO_bO_c$. Let us complement triangle $OO'H'$ to parallelogram $OO'H'M$. Since $\frac{OH}{OM} = \frac{OH}{O'H'} = 2\sin\varphi$ and $\angle HOM = \angle(HO, O'H') = 90^\circ - \varphi$, it follows that $MH = MO$, i.e., point M lies on the midperpendicular of segment OH. It remains to notice that for the inscribed quadrilateral $OO_aO_bO_c$ point M is uniquely determined: taking instead of point O any of the points O_a, O_b or O_c we get the same point M (cf. Problem 13.33).

2.85. We may assume that rays AB and DC meet at point E and rays BC and AD meet at point F. Let P be the intersection point of circumscribed circles of triangles BCE

and CDF. Then $\angle CPE = \angle ABC$ and $\angle CPF = \angle ADC$. Hence, $\angle CPE + \angle CPF = 180^\circ$, i.e., point P lies on segment EF.

2.86. a) Since

$$\angle(AP, PD) = \angle(AP, PE) + \angle(PE, PD) = \angle(AC, CD) + \angle(AB, BD) + \angle(AO, OD),$$

points A, P, D and O lie on one circle.

b) Clearly,

$$\angle(EP, PO) = \angle(EP, PA) + \angle(PA, PO) = \angle(DC, CA) + \angle(DA, DO) = 90^\circ,$$

because the arcs intersected by these angles constitute a half of the circle.

2.87. Let us make use of notations of Fig. 17. The projections of point P on lines CA and CB coincide with its projection to CE and CF, respectively. Therefore, Simson's lines of point P relative triangles ABC and CEF coincide (cf. Problem 5.85 a).

2.88. Let point A' be symmetric to point A through the midperpendicular to segment BC. Then $\angle OAH = \frac{1}{2}\angle AOA' = \angle ABA' = |\angle B - \angle C|$.

2.89. Since AA' is a diameter, $A'C \perp AC$; hence, $BH \parallel A'C$. Similarly, $CH \parallel A'B$. Therefore, $BA'CH$ is a parallelogram.

2.90. Let l be a line parallel to the two given lines, D the intersection point of lines m and n. Then

$$\angle(AD, DB) = \angle(m, AB) + \angle(AB, n) = \angle(AC, l) + \angle(l, CB) = \angle(AC, CB)$$

and, therefore, point D lies on the circumscribed circle of triangle ABC.

2.91. a) Let O be the midpoint of the arc of circle S that lies inside triangle ABC. Then $\angle CBO = \angle BCO$ and due to a property of the angle between a tangent and a chord, $\angle BCO = \angle ABO$. Therefore, BO is the bisector of angle ABC, i.e., O is the center of the inscribed circle of triangle ABC. We similarly prove that the midpoint of the arc of circle S that lies outside triangle ABC is the center of its escribed circle.

b) We have to prove that the center of the considered circle S lies on the bisector of angle BAC. Let D be the intersection point of the bisector of the angle with the circumscribed circle of triangle ABC. Then $DB = DO = DC$ (cf. Problem 2.4 a), i.e., D is the center of circle S.

2.92. If angle $\angle C$ is a right one, then the solution of the problem is obvious: C is the intersection point of lines A_1B, A_2B_2, AB_1. If $\angle C \neq 90^\circ$, then the circumscribed circles of squares ACA_1A_2 and BCB_1B_2 have in addition to C one more common point, C_1. Then

$$\begin{aligned}\angle(AC_1, A_2C_1) &= \angle(A_2C_1, A_1C_1) = \angle(A_1C_1, C_1C) = \angle(C_1C, C_1B_1)\\ = \angle(C_1B_1, C_1B_2) &= \angle(C_1B_2, C_1B) = 45^\circ\end{aligned}$$

(or -45°; it is only important that all the angles are of the same sign). Hence, $\angle(AC, C_1B_1) = 4 \cdot 45^\circ = 180^\circ$, i.e., line AB_1 passes through point C_1.

Similarly, A_2B_2 and A_1B pass through point C_1.

2.93. Let P and O be the centers of circles S_1 and S_2, respectively; let $\alpha = \angle APC$, $\beta = \angle BPC$; lines AC and BC intersect S_2 at points K and L, respectively. Since $\angle OAP = \angle OBP = 90^\circ$, it follows that $\angle AOB = 180^\circ - \alpha - \beta$. Furthermore,

$$\angle LOB = 180^\circ - 2\angle LBO = 2\angle CBP = 180^\circ - \beta.$$

Similarly, $\angle KOA = 180^\circ - \alpha$. Therefore,

$$\angle LOK = \angle LOB + \angle KOA - \angle AOB = 180^\circ,$$

i.e., KL is a diameter.

2.94. Let us consider points M', P', Q' and R' symmetric to points M, P, Q and R, respectively, through line OA. Since point C is symmetric to point B through OA, it follows that line $P'Q'$ passes through point C. The following equalities are easy to verify:

$$\angle(CS, NS) = \angle(Q'Q, NQ) = \angle(Q'P, NP') = \angle(CP', NP');$$
$$\angle(CR', P'R') = \angle(MM', P'M') = \angle(MN, P'N) = \angle(CN, P'N).$$

From these equalities we deduce that points C, N, P', S and R' lie on one circle. But points S, R' and C lie on one line, therefore, $S = R'$.

CHAPTER 3. CIRCLES

Background

1. A line that has exactly one common point with a circle is called a line *tangent* to the circle. Through any point A outside the circle exactly two tangents to the circle can be drawn.

Let B and C be the tangent points and O the center of the circle. Then:

a) $AB = AC$;

b) $\angle BAO = \angle CAO$;

c) $OB \perp AB$.

(Sometimes the word "tangent" is applied not to the whole line AB but to the segment AB. Then property a), for example, is formulated as: *the tangents to one circle drawn from one point are equal.*)

2. Let lines l_1 and l_2 that pass through point A intersect a circle at points B_1, C_1 and B_2, C_2, respectively. Then $AB_1 \cdot AC_1 = AB_2 \cdot AC_2$. Indeed, $\triangle AB_1C_2 \sim \triangle AB_2C_1$ in three angles. (We advise the reader to prove this making use of the properties of the inscribed angles and considering two cases: A lies outside the circle and A lies inside the circle.)

If line l_2 is tangent to the circle, i.e., $B_2 = C_2$, then $AB_1 \cdot AC_1 = AB_2^2$. The proof runs along the same lines as in the preceding case except that now we have to make use of *the properties of the angle between a tangent and a chord*.

3. The line that connects the centers of tangent circles passes through their tangent point.

4. The *value of the angle between two intersecting circles* is the value of the angle between the tangents to these circles drawn through the intersection point. It does not matter which of the two of intersection points we choose: the corresponding angles are equal.

The angle between tangent circles is equal to $0°$.

5. In solutions of problems from §6 a property that has no direct relation to circles is used: *the heights of a triangle meet at one point*. The reader can find the proof of this fact in solutions of Problems 5.45 and 7.41 or can take it for granted for the time being.

6. It was already in the middle of the V century A.D. that **Hyppocratus** from island Chios (do not confuse him with the famous doctor Hyppocratus from island Kos who lived somewhat later) and Pythagoreans began to solve the *quadrature of the circle* problem. It is formulated as follows: *with the help of a ruler and compass construct a square of the same area as the given circle.*

In 1882 the German mathematician **Lindemann** proved that number π is transcendental, i.e., is not a root of a polynomial with integer coefficients. This implies, in particular, that the problem on the quadrature of the circle is impossible to solve as stated (using other tools one can certainly solve it).

It seems that it was the problem on *Hyppocratus' crescents* (Problem 3.38) that induced in many a person great expectations to the possibility of squaring the circle: *the area of the figure formed by arcs of circles is equal to the area of a triangle*. Prove this statement and try to understand why such expectations were not grounded in this case.

Introductory problems

1. Prove that from a point A outside a circle it is possible to draw exactly two tangents to the circle and the lengths of these tangents (more exactly, the lengths from A to the tangent points) are equal.

2. Two circles intersect at points A and B. Point X lies on line AB but not on segment AB. Prove that the lengths of all the tangents drawn from point X to the circles are equal.

3. Two circles whose radii are R and r are tangent from the outside (i.e., none of them lies inside the other one). Find the length of the common tangent to these circles.

4. Let a and b be the lengths of the legs of a right triangle, c the length of its hypothenuse. Prove that:

a) the radius of the inscribed circle of this triangle is equal to $\frac{1}{2}(a+b-c)$;

b) the radius of the circle tangent to the hypothenuse and the extensions of the legs is equal to $\frac{1}{2}(a+b+c)$.

§1. The tangents to circles

3.1. Lines PA and PB are tangent to a circle centered at O; let A and B be the tangent points. A third tangent to the circle is drawn; it intersects with segments PA and PB at points X and Y, respectively. Prove that the value of angle XOY does not depend on the choice of the third tangent.

3.2. The inscribed circle of triangle ABC is tangent to side BC at point K and an escribed circle is tangent at point L. Prove that $CK = BL = \frac{1}{2}(a+b-c)$, where a, b, c are the lengths of the triangle's sides.

3.3. On the base AB of an isosceles triangle ABC a point E is taken and circles tangent to segment CE at points M and N are inscribed into triangles ACE and ECB, respectively. Find the length of segment MN if the lengths of segments AE and BE are known.

3.4. Quadrilateral $ABCD$ is such that there exists a circle inscribed into angle $\angle BAD$ and tangent to the extensions of sides BC and CD. Prove that $AB + BC = AD + DC$.

3.5. The common inner tangent to circles whose radii are R and r intersects their common outer tangents at points A and B and is tangent to one of the circles at point C. Prove that $AC \cdot CB = Rr$.

3.6. Common outer tangents AB and CD are drawn to two circles of distinct radii. Prove that quadrilateral $ABCD$ is a circumscribed one if and only if the circles are tangent to each other.

3.7. Consider parallelogram $ABCD$ such that the escribed circle of triangle ABD is tangent to the extensions of sides AD and AB at points M and N, respectively. Prove that the intersection points of segment MN with BC and CD lie on the inscribed circle of triangle BCD.



Figure 18 (3.7)

3.8. On each side of quadrilateral $ABCD$ two points are taken; these points are connected as shown on Fig. 18. Prove that if all the five dashed quadrilaterals are circumscribed ones, then the quadrilateral $ABCD$ is also a circumscribed one.

§2. The product of the lengths of a chord's segments

3.9. Through a point P lying on the common chord AB of two intersecting circles chord KM of the first circle and chord LN of the second circle are drawn. Prove that quadrilateral $KLMN$ is an inscribed one.

3.10. Two circles intersect at points A and B; let MN be their common tangent. Prove that line AB divides MN in halves.

3.11. Line OA is tangent to a circle at point A and chord BC is parallel to OA. Lines OB and OC intersect the circle for the second time at points K and L, respectively. Prove that line KL divides segment OA in halves.

3.12. In parallelogram $ABCD$, diagonal AC is longer than diagonal BD; let M be a point on diagonal AC such that quadrilateral $BCDM$ is an inscribed one. Prove that line BD is a common tangent to the circumscribed circles of triangles ABM and ADM.

3.13. Given circle S and points A and B outside it. For each line l that passes through point A and intersects circle S at points M and N consider the circumscribed circle of triangle BMN. Prove that all these circles have a common point distinct from point B.

3.14. Given circle S, points A and B on it and point C on chord AB. For every circle S' tangent to chord AB at point C and intersecting circle S at points P and Q consider the intersection point M of lines AB and PQ. Prove that the position of point M does not depend on the choice of circle S'.

§3. Tangent circles

3.15. Two circles are tangent at point A. A common (outer) tangent line is drawn to them; it is tangent to the circles at points C and D, respectively. Prove that $\angle CAD = 90^\circ$.

3.16. Two circles S_1 and S_2 centered at O_1 and O_2 are tangent to each other at point A. A line that intersects S_1 at point A_1 and S_2 at point A_2 is drawn through point A. Prove that $O_1A_1 \parallel O_2A_2$.

3.17. Three circles S_1, S_2 and S_3 are pairwise tangent to each other at three distinct points. Prove that the lines that connect the tangent point of circles S_1 and S_2 with the other two tangent points intersect circle S_3 at points that are the endpoints of its diameter.

3.18. Two tangent circles centered at O_1 and O_2, respectively, are tangent from the inside to the circle of radius R centered at O. Find the perimeter of triangle OO_1O_2.

3.19. Circles S_1 and S_2 are tangent to circle S from the inside at points A and B so that one of the intersection points of circles S_1 and S_2 lies on segment AB. Prove that the sum of the radii of circles S_1 and S_2 is equal to the radius of circle S.

3.20. The radii of circles S_1 and S_2 tangent at point A are equal to R and r $(R > r)$. Find the length of the tangent drawn to circle S_2 from point B on circle S_1 if $AB = a$ (consider the cases of the inner and outer tangent).

3.21. A point C is taken on segment AB. A line that passes through point C intersects circles with diameters AC and BC at points K and L and the circle with diameter AB at points M and N, respectively. Prove that $KM = LN$.

3.22. Given four circles S_1, S_2, S_3 and S_4 such that S_i and S_{i+1} are tangent from the outside for $i = 1, 2, 3, 4$ $(S_5 = S_1)$. Prove that the tangent points are the vertices of an inscribed quadrilateral.

3.23. a) Three circles centered at A, B and C are tangent to each other and line l; they are placed as shown on Fig. 19. Let a, b and c be radii of circles centered at A, B and C, respectively. Prove that $\frac{1}{\sqrt{c}} = \frac{1}{\sqrt{a}} + \frac{1}{\sqrt{b}}$.



Figure 19 (3.23)

b) Four circles are pairwise tangent from the outside (at 6 distinct points). Let a, b, c and d be their radii; $\alpha = \frac{1}{a}$, $\beta = \frac{1}{b}$, $\gamma = \frac{1}{c}$ and $\delta = \frac{1}{d}$. Prove that

$$2(\alpha^2 + \beta^2 + \gamma^2 + \delta^2) = (\alpha + \beta + \gamma + \delta)^2.$$

§4. Three circles of the same radius

3.24. Three circles of radius R pass through point H; let A, B and C be points of their pairwise intersection distinct from H. Prove that

a) H is the intersection point of heights of triangle ABC;

b) the radius of the circumscribed circle of the triangle ABC is also equal to R.



Figure 20 (3.24)

3.25. Three equal circles intersect as shown on Fig. 20 a) or b). Prove that $\smile AB_1 + \smile BC_1 \pm \smile CA_1 = 180°$, where the minus sign is taken in case b) and plus in case a).



Figure 21 (3.26)

3.26. Three circles of the same radius pass through point P; let A, B and Q be points of their pairwise intersections. A fourth circle of the same radius passes through point Q

and intersects the other two circles at points C and D. The triangles ABQ and CDP thus obtained are acute ones and quadrilateral $ABCD$ is a convex one (Fig. 21). Prove that $ABCD$ is a parallelogram.

§5. Two tangents drawn from one point

3.27. Tangents AB and AC are drawn from point A to a circle centered at O. Prove that if segment AO subtends a right angle with vertex at point M, then segments OB and OC subtend equal angles with vertices at M.

3.28. Tangents AB and AC are drawn from point A to a circle centered at O. Through point X on segment BC line KL perpendicular to XO is drawn so that points K and L lie on lines AB and AC, respectively. Prove that $KX = XL$.

3.29. On the extension of chord KL of a circle centered at O a point A is taken and tangents AP and AQ to the circle are drawn from it; let M be the midpoint of segment PQ. Prove that $\angle MKO = \angle MLO$.

3.30. From point A tangents AB and AC to a circle and a line that intersects the circle at points D and E are drawn; let M be the midpoint of segment BC. Prove that $BM^2 = DM \cdot ME$ and either $\angle DME = 2\angle DBE$ or $\angle DME = 2\angle DCE$; moreover, $\angle BEM = \angle DEC$.

3.31. Quadrilateral $ABCD$ is inscribed in a circle so that tangents to this circle at points B and D intersect at a point K that lies on line AC.

a) Prove that $AB \cdot CD = BC \cdot AD$.

b) A line parallel to KB intersects lines BA, BD and BC at points P, Q and R, respectively. Prove that $PQ = QR$.

* * *

3.32. A circle S and a line l that has no common points with S are given. From point P that moves along line l tangents PA and PB to circle S are drawn. Prove that all chords AB have a common point.

Let point P lie outside circle S; let PA and PB be tangents to the circle. Then line AB is called the *polar line* of point P relative circle S.

3.33. Circles S_1 and S_2 intersect at points A and B so that the center O of circle S_1 lies on S_2. A line that passes through point O intersects segment AB at point P and circle S_2 at point C. Prove that point P lies on the polar line of point C relative circle S_1.

§6. Application of the theorem on triangle's heights

3.34. Points C and D lie on the circle with diameter AB. Lines AC and BD, AD and BC meet at points P and Q, respectively. Prove that $AB \perp PQ$.

3.35. Lines PC and PD are tangent to the circle with diameter AB so that C and D are tangent points. Prove that the line that connects P with the intersection point of lines AC and BD is perpendicular to AB.

3.36. Given diameter AB of a circle and point C outside AB. With the help of the ruler alone (no compasses) drop the perpendicular from C to AB if:

a) point C does not lie on the circle;

b) point C lies on the circle.

3.37. Let O_a, O_b and O_c be the centers of circumscribed circles of triangles PBC, PCA and PAB. Prove that if points O_a and O_b lie on lines PA and PB, then point O_c lies on line PC.

§7. Areas of curvilinear figures

3.38. On the hypothenuse and legs of a rectangular triangle semicircles are constructed as shown on Fig. 22. Prove that the sum of the areas of the crescents obtained (shaded) is equal to the area of the given triangle.



Figure 22 (3.38)

3.39. In a disc two perpendicular diameters, i.e., four radii, are constructed. Then there are constructed four disks whose diameters are these radii. Prove that the total area of the pairwise common parts of these four disks is equal to the area of the initial (larger) disk that lies outside the considered four disks (Fig. 23).



Figure 23 (3.39)

3.40. On three segments OA, OB and OC of the same length (point B lies outside angle AOC) circles are constructed as on diameters. Prove that the area of the curvilinear triangle bounded by the arcs of these circles and not containing point O is equal to a half area of the (common) triangle ABC.

3.41. On sides of an arbitrary acute triangle ABC as on diameters circles are constructed. They form three "outer" curvilinear triangles and one "inner" triangle (Fig. 24). Prove that if we subtract the area of the "inner" triangle from the sum of the areas of "outer" triangles we get the doubled area of triangle ABC.

§8. Circles inscribed in a disc segment

In this section a *segment* is always a disc segment.

3.42. Chord AB divides circle S into two arcs. Circle S_1 is tangent to chord AB at point M and one of the arcs at point N. Prove that:

a) line MN passes through the midpoint P of the second arc;

b) the length of tangent PQ to circle S_1 is equal to that of PA.

3.43. From point D of circle S the perpendicular DC is dropped to diameter AB. Circle S_1 is tangent to segment CA at point E and also to segment CD and to circle S. Prove that DE is a bisector of triangle ADC.



Figure 24 (3.41)

3.44. Two circles inscribed in segment AB of the given circle intersect at points M and N. Prove that line MN passes through the midpoint C of arc AB complementary for the given segment.

3.45. A circle tangent to sides AC and BC of triangle ABC at points M and N, respectively is also tangent to its circumscribed circle (from the inside). Prove that the midpoint of segment MN coincides with the center of the inscribed circle of triangle ABC.

3.46. Triangles ABC_1 and ABC_2 are inscribed in circle S so that chords AC_2 and BC_1 intersect. Circle S_1 is tangent to chord AC_2 at point M_2, to chord BC_1 at point N_1 and to circle S (???where?). Prove that the centers of the inscribed circles of triangles ABC_1 and ABC_2 lie on segment M_2N_1.

§9. Miscellaneous problems

3.47. The radii of two circles are equal to R_1 and R_2 and the distance between the centers of the circles is equal to d. Prove that these circles are orthogonal if and only if $d^2 = R_1^2 + R_2^2$.

3.48. Three circles are pairwise tangent from the outside at points A, B and C. Prove that the circumscribed circle of triangle ABC is perpendicular to all the three circles.

3.49. Two circles centered at O_1 and O_2 intersect at points A and B. A line is drawn through point A; the line intersects the first circle at point M_1 and the second circle at point M_2. Prove that $\angle BO_1M_1 = \angle BO_2M_2$.

§10. The radical axis

3.50. Circle S and point P are given on the plane. A line drawn through point P intersects the circle at points A and B. Prove that the product $PA \cdot PB$ does not depend on the choice of a line.

This product taken with the plus sign if point P is outside the circle and with minus sign if P is inside of the circle is called the *degree of point P with respect to circle S*.

3.51. Prove that for a point P outside circle S its degree with respect to S is equal to the square of the length of the tangent drawn to the circle from point P.

3.52. Prove that the degree of point P with respect to circle S is equal to $d^2 - R^2$, where R is the radius of S and d is the distance from P to the center of S.

3.53. Two nonconcentric circles S_1 and S_2 are given in plane. Prove that the locus of points whose degree with respect to S_1 is equal to the degree with respect to S_2 is a line.

This line is called *the radical axis* of circles S_1 and S_2.

3.54. Prove that the radical axis of two intersecting circles passes through the intersection points.

3.55. Given three circles in plane whose centers do not lie on one line. Let us draw radical axes for each pair of these circles. Prove that all the three radical axes meet at one point.

This point is called the *radical center* of the three circles.

3.56. Consider three pairwise intersecting circles in plane. Through the intersection points of any two of them a line is drawn. Prove that either these three lines meet at one point or are parallel.

3.57. Two nonconcentric circles S_1 and S_2 are given. Prove that the set of centers of circles that intersect both these circles at a right angle is their radical axis (without their common chord if the given circles intersect).

3.58. a) Prove that the midpoints of the four common tangents to two nonintersecting circles lie on one line.

b) Through two of the tangent points of common exterior tangents with two circles a line is drawn, see Fig. . Prove that the circles cut on this line equal chords.

3.59. On sides BC and AC of triangle ABC, points A_1 and B_1, respectively, are taken; let l be the line that passes through the common points of circles with diameters AA_1 and BB_1. Prove that:

a) Line l passes through the intersection point H of heights of triangle ABC;

b) line l passes through point C if and only if $AB_1 : AC = BA_1 : BC$.

3.60. The extensions of sides AB and CD of quadrilateral $ABCD$ meet at point F and the extensions of sides BC and AD meet at point E. Prove that the circles with diameters AC, BD and EF have a common radical axis and the orthocenters of triangles ABE, CDE, ADF and BCF lie on it.

3.6l. Three circles intersect pairwise at points A_1 and A_2, B_1 and B_2, C_1 and C_2. Prove that $A_1B_2 \cdot B_1C_2 \cdot C_1A_2 = A_2B_1 \cdot B_2C_1 \cdot C_2A_1$.

3.62. On side BC of triangle ABC point A' is taken. The midperpendicular to segment $A'B$ intersects side AB at point M and the midperpendicular to segment $A'C$ intersects side AC at point N. Prove that point symmetric to point A' through line MN lies on the circumscribed circle of triangle ABC.

3.63. Solve Problem 1.66 making use of the properties of the radical axis.

3.64. Inside a convex polygon several pairwise nonintersecting disks of distinct radii are placed. Prove that it is possible to cut the polygon into smaller polygons so that all these small polygons are convex and each of them contains exactly one of the given disks.

3.65. a) In triangle ABC, heights AA_1, BB_1 and CC_1 are drawn. Lines AB and A_1B_1, BC and B_1C_1, CA and C_1A_1 intersect at points C', A' and B', respectively. Prove that points A', B' and C' lie on the radical axis of the circle of nine points (cf. Problem 5.106) and on that of the circumscribed circle.

b) The bisectors of the outer angles of triangle ABC intersect the extensions of the opposite sides at points A', B' and C'. Prove that points A', B' and C' lie on one line and this line is perpendicular to the line that connects the centers of the inscribed and circumscribed circles of triangle ABC.

3.66. Prove that diagonals AD, BE and CF of the circumscribed hexagon $ABCDEF$ meet at one point. (*Brianchon's theorem.*)

3.67. Given four circles S_1, S_2, S_3 and S_4 such that the circles S_i and S_{i+1} are tangent from the outside for $i = 1, 2, 3, 4$, where $S_5 = S_1$. Prove that the radical axis of circles S_1 and S_3 passes through the intersection point of common outer tangents to S_2 and S_4.

3.68. a) Circles S_1 and S_2 intersect at points A and B. The degree of point P of circle S_1 with respect to circle S_2 is equal to p, the distance from point P to line AB is equal to h and the distance between the centers of circles is equal to d. Prove that $|p| = 2dh$.

b) The degrees of points A and B with respect to the circumscribed circles of triangles BCD and ACD are equal to p_a and p_b, respectively. Prove that $|p_a|S_{BCD} = |p_b|S_{ACD}$.

Problems for independent study

3.69. An easy chair of the form of a disc sector of radius R is swinging on a horizontal table. What is the trajectory of the vertex of the sector?

3.70. From a point A outside a circle of radius R two tangents AB and AC are drawn, B and C are tangent points. Let $BC = a$. Prove that $4R^2 = r^2 + r_a^2 + \frac{1}{2}a^2$, where r and r_a are the radii of the inscribed and escribed circles of triangle ABC.

3.71. Two circles have an inner tangent. The line that passes through the center of a smaller circle intersects the greater one at points A and D and the smaller one at points B and C. Find the ratio of the radii of the circles if $AB : BC : CD = 2 : 3 : 4$.

3.72. The centers of three circles each of radius R, where $1 < R < 2$, form an equilateral triangle with side 2. What is the distance between the intersection points of these circles that lie outside the triangle?

3.73. A point C is taken on segment AB and semicircles with diameters AB, AC and BC are constructed (on one side of line AB). Find the ratio of the area of the curvilinear triangle bounded by these semicircles to the area of the triangle formed by the midpoints of the arcs of these semicircles.

3.74. A circle intersects side BC of triangle ABC at points A_1 and A_2, side AC at points B_1 and B_2, side AB at points C_1 and C_2. Prove that

$$\frac{AC_1}{C_1B} \cdot \frac{BA_1}{A_1C} \cdot \frac{CB_1}{B_1A} = \left(\frac{AC_2}{C_2B} \cdot \frac{BA_2}{A_2C} \cdot \frac{CB_2}{B_2A}\right)^{-1}.$$

3.75. From point A tangents AB and AC to a circle are drawn (B and C are tangent points); PQ is a diameter of the circle; line l is tangent to the circle at point Q. Lines PA, PB and PC intersect line l at points A_1, B_1 and C_1. Prove that $A_1B_1 = A_1C_1$.

Solutions

3.1. Let line XY be tangent to the given circle at point Z. The corresponding sides of triangles XOA and XOZ are equal and, therefore, $\angle XOA = \angle XOZ$. Similarly, $\angle ZOY = \angle BOY$. Therefore,

$$\angle XOY = \angle XOZ + \angle ZOY = \frac{\angle AOZ + \angle ZOB}{2} = \frac{\angle AOB}{2}.$$

3.2. Let M and N be the tangent points of the inscribed circle with sides AB and BC. Then $BK + AN = BM + AM = AB$, hence, $CK + CN = a + b - c$.

Let P and Q be the tangent points of the escribed circle with the extensions of sides AB and BC. Then $AP = AB + BP = AB + BL$ and $AQ = AC + CQ = AC + CL$. Hence, $AP + AQ = a + b + c$. Therefore, $BL = BP = AP - AB = \frac{1}{2}(a + b - c)$.

3.3. By Problem 3.2 $CM = \frac{1}{2}(AC + CE - AE)$ and $CN = \frac{1}{2}(BC + CE - BE)$. Taking into account that $AC = BC$ we get $MN = |CM - CN| = \frac{1}{2}|AE - BE|$.

3.4. Let lines AB, BC, CD and DA be tangent to the circle at points P, Q, R and S, respectively. Then $CQ = CR = x$, hence, $BP = BC + CQ = BC + x$ and $DS = DC + CR = DC + x$. Therefore, $AP = AB + BP = AB + BC + x$ and $AS = AD + DS = AD + DC + x$. Taking into account that $AP = AS$, we get the statement desired.

3.5. Let line AB be tangent to the circles centered at O_1 and O_2 at points C and D, respectively. Since $\angle O_1AO_2 = 90^\circ$, the right triangles AO_1C and O_2AD are similar. Therefore, $O_1C : AC = AD : DO_2$. Moreover, $AD = CB$ (cf. Problem 3.2). Therefore, $AC \cdot CB = Rr$.

3.6. Let lines AB and CD intersect at point O. Let us assume for definiteness that points A and D lie on the first circle while points B and C lie on the second one. Suppose also that $OB < OA$ (Fig. 25).



Figure 25 (Sol. 3.6)

The intersection point M of bisectors of angles $\angle A$ and $\angle D$ of quadrilateral $ABCD$ is the midpoint of the arc of the first circle that lies inside triangle AOD and the intersection point N of bisectors of angles $\angle B$ and $\angle C$ is the midpoint of the arc of the second circle that lies outside triangle BOC, cf. Problem 2.91 a). Quadrilateral $ABCD$ is a circumscribed one if and only if points M and N coincide.

3.7. Let R be the tangent point of the escribed circle with side BD, let P and Q be the intersection points of segment MN with BC and CD, respectively (Fig. 26).



Figure 26 (Sol. 3.7)

Since $\angle DMQ = \angle BPN$, $\angle DQM = \angle BNP$ and $\angle DMQ = \angle BNP$, it follows that triangles MDQ, PBN and PCQ are isosceles ones. Therefore, $CP = CQ$, $DQ = DM = DR$ and $BP = BN = BR$. Therefore, P, Q and R are the tangent points of the inscribed circle of triangle BCD with its sides (cf. Problem 5.1).

3.8. Denote some of the tangent points as shown on Fig. 27. The sum of the lengths of one pair of the opposite sides of the inner quadrilateral is equal to the sum of the lengths of the pair of its other sides. Let us extend the sides of this quadrilateral to tangent points with inscribed circles of the other quadrilaterals (ST is one of the obtained segments).



Figure 27 (Sol. 3.8)

Then both sums of lengths of pairs of opposite segments increase by the same number. Each of the obtained segments is the common tangent to a pair of "corner" circles; each segment can be replaced with another common outer tangent of equal length (i.e., replace ST with QR). To prove the equality $AB + CD = BC + AD$, it remains to make use of equalities of the form $AP = AQ$.

3.9. Let P be the intersection point of diagonals of convex quadrilateral $ABCD$. Quadrilateral $ABCD$ is an inscribed one if and only if $\triangle APB \sim \triangle DPC$, i.e., $PA \cdot PC = PB \cdot PD$. Since quadrilaterals $ALBN$ and $AMBK$ are inscribed ones, $PL \cdot PN = PA \cdot PB = PM \cdot PK$. Hence, quadrilateral $KLMN$ is an inscribed one.

3.10. Let O be the intersection point of line AB and segment MN. Then $OM^2 = OA \cdot OB = ON^2$, i.e., $OM = ON$.

3.11. Let, for definiteness, rays OA and BC be codirected, M the intersection point of lines KL and OA. Then $\angle LOM = \angle LCB = \angle OKM$ and, therefore, $\triangle KOM \sim \triangle OLM$. Hence, $OM : KM = LM : OM$, i.e., $OM^2 = KM \cdot LM$. Moreover, $MA^2 = MK \cdot ML$. Therefore, $MA = OM$.

3.12. Let O be the intersection point of diagonals AC and BD. Then $MO \cdot OC = BO \cdot OD$. Since $OC = OA$ and $BO = OD$, we have $MO \cdot OA = BO^2$ and $MO \cdot OA = DO^2$. These equalities mean that OB is tangent to the circumscribed circle of triangle ABM and OD is tangent to the circumscribed circle of triangle ADM.

3.13. Let C be the intersection point of line AB with the circumscribed circle of triangle BMN distinct from point B; let AP be the tangent to circle S. Then $AB \cdot AC = AM \cdot AN = AP^2$ and, therefore, $AC = \frac{AP^2}{AB}$, i.e., point C is the same for all lines l.

Remark. We have to exclude the case when the length of the tangent drawn to S from A is equal to AB.

3.14. Clearly, $MC^2 = MP \cdot MQ = MA \cdot MB$ and point M lies on ray AB if $AC > BC$ and on ray BA if $AC < BC$. Let, for definiteness sake, point M lie on ray AB. Then $(MB + BC)^2 = (MB + BA) \cdot MB$. Therefore, $MB = \frac{BC^2}{AB - 2BC}$ and we deduce that the position of point M does not depend on the choice of circle S'.

3.15. Let M be the intersection point of line CD and the tangent to circles at point A. Then $MC = MA = MD$. Therefore, point A lies on the circle with diameter CD.

3.16. Points O_1, A and O_2 lie on one line, hence, $\angle A_2AO_2 = \angle A_1AO_1$. Triangles AO_2A_2 and AO_1A_1 are isosceles ones, hence, $\angle A_2AO_2 = \angle AA_2O_2$ and $\angle A_1AO_1 = \angle AA_1O_1$. Therefore, $\angle AA_2O_2 = \angle AA_1O_1$, i.e., $O_1A_1 \parallel O_2A_2$.

3.17. Let O_1, O_2 and O_3 be the centers of circles S_1, S_2 and S_3; let A, B, C be the tangent points of circles S_2 and S_3, S_3 and S_1, S_1 and S_2, respectively; A_1 and B_1 the intersection points of lines CA and CB, respectively, with circle S_3. By the previous problem $B_1O_3 \parallel CO_1$ and $A_1O_3 \parallel CO_2$. Points O_1, C and O_2 lie on one line and, therefore, points A_1, O_3 and B_1 also lie on one line, i.e., A_1B_1 is a diameter of cicle S_3.

3.18. Let A_1, A_2 and B be the tangent points of the circles centered at O and O_1, O and O_2, O_1 and O_2, respectively. Then $O_1O_2 = O_1B + BO_2 = O_1A_1 + O_2A_2$. Therefore,

$$OO_1 + OO_2 + O_1O_2 = (OO_1 + O_1A_1) + (OO_2 + O_2A_2) = OA_1 + OA_2 = 2R.$$

3.19. Let O, O_1 and O_2 be centers of circles S, S_1 and S_2; let C be the common point of circles S_1 and S_2 that lies on segment AB. Triangles AOB, AO_1C and CO_2B are isosceles ones; consequently, OO_1CO_2 is a parallelogram and $OO_1 = O_2C = O_2B$; hence, $AO = AO_1 + O_1O = AO_1 + O_2B$.

3.20. Let O_1 and O_2 be the centers of circles S_1 and S_2; let X be the other intersection point of line AB with circle S_2. The square of the length of the tangent in question is equal to $BA \cdot BX$. Since $AB : BX = O_1A : O_1O_2$, it follows that $AB \cdot BX = \frac{AB^2 \cdot O_1O_2}{R} = \frac{a^2(R \pm r)}{R}$, where the minus sign is taken for the inner tangent and the plus sign for the outer tangent.

3.21. Let O, O_1 and O_2 be the centers of the circles with diameters AB, AC and BC, respectively. It suffices to verify that $KO = OL$. Let us prove that $\triangle O_1KO = \triangle O_2OL$. Indeed, $O_1K = \frac{1}{2}AC = O_2O$, $O_1O = \frac{1}{2}BC = O_2L$ and $\angle KO_1O = \angle OO_2L = 180^\circ - 2\alpha$, where α is the value of the angle between lines KL and AB.

3.22. Let O_i be the center of circle S_i and A_i the tangent point of circles S_i and S_{i+1}. Quadrilateral $O_1O_2O_3O_4$ is a convex one; let α_1, α_2, α_3 and α_4 be the values of its angles. It is easy to verify that $\angle A_{i-1}A_iA_{i+1} = \frac{1}{2}(\alpha_i + \alpha_{i+1})$ and, therefore,

$$\angle A_1 + \angle A_3 = \frac{1}{2}(\alpha_1 + \alpha_2 + \alpha_3 + \alpha_4) = \angle A_2 + \angle A_4.$$

3.23. a) Let A_1, B_1 and C_1 be the projections of points A, B and C, respectively, to line l; let C_2 be the projection of point C to line AA_1. By Pythagorus theorem $CC_2^2 = AC^2 - AC_2^2$, i.e., $A_1C_1^2 = (a+c)^2 - (a-c)^2 = 4ac$. Similarly, $B_1C_1^2 = 4bc$ and $A_1B_1^2 = 4ab$. Since $A_1C_1 + C_1B_1 = A_1B_1$, it follows that $\sqrt{ac} + \sqrt{bc} = \sqrt{ab}$, i.e., $\frac{1}{\sqrt{b}} + \frac{1}{\sqrt{a}} = \frac{1}{\sqrt{c}}$.



Figure 28 (Sol. 3.23 b))

b) Let A, B, C be the centers of "outer" circles, D the center of the "inner" circle (Fig. 28). The semiperimeter of triangle BDC is equal to $b+c+d$, and, therefore,

$$\cos^2\left(\frac{\angle BDC}{2}\right) = \frac{d(b+c+d)}{(b+d)(c+d)},\quad \sin^2\left(\frac{\angle BDC}{2}\right) = \frac{bc}{(b+d)(c+d)}$$

(cf. Problem 12.13). As is easy to see the law of cosines is equivalent to the statement:

$$\alpha' + \beta' + \gamma' = 180^\circ \Longrightarrow \sin^2\alpha' - \sin^2\beta' - \sin^2\gamma' + 2\sin\beta'\sin\gamma'\cos\alpha' = 0. \qquad (*)$$

Substituting the values $\alpha' = \frac{1}{2}\angle BDC$, $\beta' = \frac{1}{2}\angle ADC$ and $\gamma' = \frac{1}{2}\angle ADB$ into formula $(*)$, we get

$$\frac{bc}{(b+d)(c+d)} - \frac{ac}{(a+d)(c+d)} - \frac{ab}{(a+d)(b+d)} + 2\frac{a\sqrt{bcd(b+c+d)}}{(a+d)(b+d)(c+d)} = 0,$$

i.e.,

$$\frac{a+d}{a} - \frac{b+d}{b} - \frac{c+d}{c} + 2\sqrt{\frac{d(b+c+d)}{bc}} = 0.$$

Dividing this by d we get

$$\alpha - \beta - \gamma - \delta + 2\sqrt{\beta\gamma + \gamma\delta + \delta\beta} = 0.$$

Therefore,

$$\begin{gathered}(\alpha+\beta+\gamma+\delta)^2 = (\alpha-\beta-\gamma-\delta)^2 + 4(\alpha\beta+\alpha\gamma+\alpha\delta)+\\ 4(\beta\gamma+\gamma\delta+\delta\beta) + 4(\alpha\beta+\alpha\gamma+\alpha\delta) =\\ 2(\alpha+\beta+\gamma+\delta)^2 - 2(\alpha^2+\beta^2+\gamma^2+\delta^2),\end{gathered}$$

i.e.,

$$2(\alpha^2+\beta^2+\gamma^2+\delta^2) = (\alpha+\beta+\gamma+\delta)^2.$$

3.24. Let A_1, B_1 and C_1 be the centers of the given circles (Fig. 29). Then A_1BC_1H is a rhombus and, therefore, $BA_1 \parallel HC_1$. Similarly, $B_1A \parallel HC_1$; hence, $B_1A \parallel BA_1$ and B_1ABA_1 is a parallelogram.



Figure 29 (Sol. 3.24)

a) Since $A_1B_1 \perp CH$ and $A_1B_1 \parallel AB$, it follows that $AB \perp CH$. We similarly prove that $BC \perp AH$ and $CA \perp BH$.

b) In the same way as we have proved that $B_1A \parallel BA_1$, we can prove that $B_1C \parallel BC_1$ and $A_1C \parallel AC_1$; moreover, the lengths of all these six segments are equal to R. Let us complement the triangle BA_1C to a rhombus BA_1CO. Then AB_1CO is also a rhombus. Therefore, $AO = BO = CO = R$, i.e., O is the center of the circumscribed circle of triangle ABC and its radius is equal to R.

3.25. It is easy to verify that

$$\begin{array}{rcl} \smile AB_1 \pm \smile B_1A_1 &=& \smile AC_1 + \smile C_1A_1, \\ \smile BC_1 + \smile C_1B_1 &=& \smile BA_1 \pm \smile B_1A_1 \\ \smile C_1A_1 \pm \smile CA_1 &=& \smile C_1B_1 \pm \smile B_1C, \end{array}$$

where the minus sign is only taken in case b). Adding up these equalities we get

$$\smile AB_1 + \smile BC_1 \pm \smile CA_1 = \smile AC_1 + \smile BA \pm \smile CB_1.$$

On the other hand, the doubled values of the angles of triangle ABC are equal to $\smile BA_1 \pm \smile CA_1$, $\smile AB_1 \pm \smile CB_1$ and $\smile BC_1 + \smile AC_1$, and their sum is equal to 360°.

3.26. Since $\smile AP + \smile BP + \smile PQ = 180^\circ$ (cf. Problem 3.25), it follows that $\smile AB = 180^\circ - \smile PQ$. Similarly, $\smile CD = 180^\circ - \smile PQ$, i.e., $\smile AB = \smile CD$ and, therefore, $AB = CD$. Moreover, $PQ \perp AB$ and $PQ \perp CD$ (cf. Problem 3.24) and, therefore, $AB \parallel CD$.

3.27. Points M, B and C lie on the circle with diameter AO. Moreover, chords OB and OC of the circle are equal.

3.28. Points B and X lie on the circle with diameter KO, and, therefore, $\angle XKO = \angle XBO$. Similarly, $\angle XLO = \angle XCO$. Since $\angle XBO = \angle XCO$, triangle KOL is an isosceles one and OX is its height.

3.29. It suffices to verify that $AK \cdot AL = AM \cdot AO$. Indeed, if such is the case, then points K, L, M and O lie on one circle and, therefore, $\angle MKO = \angle MLO$. Since $\triangle AOP \sim \triangle APM$, it follows that $AM \cdot AO = AP^2$; it is also clear that $AK \cdot AL = AP^2$.

3.30. Let O be the center of the circle; let points D' and E' be symmetric to points D and E through line AO. By Problem 28.7 the lines ED' and $E'D$ meet at point M. Hence, $\angle BDM = \angle EBM$ and $\angle BEM = \angle DBM$ and, therefore, $\triangle BDM \sim \triangle EBM$. It follows that $BM : DM = EM : BM$. Moreover, if line ED separates points B and M, then $\angle DME = \smile DE = 2\angle DCE$.

The equality $\angle BEM = \angle DBM$ implies that $\angle BEM = \angle DBC = \angle DEC$.

3.31. a) Since $\triangle KAB \sim \triangle KBC$, we have $AB : BC = KB : KC$. Similarly, $AD : DC = KD : KC$. Taking into account that $KB = KD$ we get the desired statement.

b) The problem of this heading reduces to that of the previous one, since

$$\frac{PQ}{BQ} = \frac{\sin\angle PBQ}{\sin\angle BPQ} = \frac{\sin\angle ABD}{\sin\angle KBA} = \frac{\sin\angle ABD}{\sin\angle ADB} = \frac{AD}{AB}, \quad \frac{QR}{BQ} = \frac{CD}{CB}.$$

3.32. Let us drop perpendicular OM to line l from center O of circle S. Let us prove that point X at which AB and OM intersect remains fixed. Points A, B and M lie on the circle with diameter PO. Hence, $\angle AMO = \angle ABO = \angle BAO$ and, therefore, $\triangle AMO \sim \triangle XAO$, because these triangles have a common angle at vertex O. It follows that $AO : MO = XO : AO$, i.e., $OX = \frac{OA^2}{MO}$ is a constant.

3.33. Since $\angle OBP = \angle OAB = \angle OCB$, we deduce that $\triangle OBP \sim \triangle OCB$ and, therefore, $OB^2 = OP \cdot OC$. Let us draw tangent CD to circle S_1 from point C. Then $OD^2 = OB^2 = OP \cdot OC$. Therefore, $\triangle ODC \sim \triangle OPD$ and $\angle OPD = \angle ODC = 90^\circ$.

3.34. Lines BC and AD are heights of triangle APB and, therefore, line PQ that passes through their intersection point Q is perpendicular to line AB.

3.35. Denote the intersection points of lines AC and BD, BC and AD by K and K_1, respectively. Thanks to the above problem, $KK_1 \perp AB$ and, therefore, it suffices to show that the intersection point of tangents at points C and D lies on line KK_1.

Let us prove that the tangent at point C passes through the midpoint of segment KK_1. Let M be the intersection point of the tangent at point C and segment KK_1. The respective sides of acute angles $\angle ABC$ and $\angle CKK_1$ are perpendicular and, therefore, the angles are equal. Similarly, $\angle CAB = \angle CK_1K$. It is also clear that $\angle KCM = \angle ABC$ and, therefore, triangle CMK is an isosceles one. Similarly, triangle CMK_1 is an isosceles one and $KM = CM = K_1M$, i.e., M is the midpoint of segment KK_1.

We similarly prove that the tangent at point D passes through the midpoint of segment KK_1.

3.36. a) Line AC intersects the circle at points A and A_1, line BC does same at points B and B_1. If $A = A_1$ (or $B = B_1$), then line AC (or BC) is the perpendicular to be constructed. If this is not the case, then AB_1 and BA_1 are heights of triangle ABC and the line to be constructed is the line that passes through point C and the intersection point of lines AB_1 and BA_1.

b) Let us take point C_1 that does not lie on the circle and drop from it perpendicular to AB. Let the perpendicular intersect the circle at points D and E. Let us construct the intersection point P of lines DC and AB and then the intersection point F of line PE with the circle. The symmetry through AB sends point C to point F. Therefore, CF is the perpendicular to be constructed.

3.37. Since $PA \perp O_bO_c$, line PA passes through point O_a if and only if line PO_a passes through the intersection point of heights of triangle $O_aO_bO_c$. Similar statements are true for points B and C as well.

The hypothesis of the problem implies that P is the intersection point of heights of triangle $O_aO_bO_c$ and, therefore, $PO_c \perp O_aO_b$.

3.38. Let $2a$ and $2b$ be the lengths of the legs, $2c$ the length of the hypothenuse. The sum of the areas of the "crescents" is equal to $\pi a^2+\pi b^2+S_{ABC}-\pi c^2$. But $\pi(a^2+b^2-c^2) = 0$.

3.39. It suffices to carry out the proof for each of the four parts into which the diameters divide the initial disc (Fig. 30).



Figure 30 (Sol. 3.39)

In the disc, consider the segment cut off by the chord intercepted by the central angle of 90°; let S and s be the areas of such segments for the initial disc and any of the four constructed disks, respectively. Clearly, $S = 4s$. It remains to observe that the area of the part shaded once is equal to $S - 2s = 2s$ and the area of the part shaded twice is equal to $2s$.

3.40. Denote the intersection points of circles constructed on segments OB and OC, OA and OC, OA and OB as on diameters by A_1, B_1, C_1, respectively (Fig. 31). Since $\angle OA_1B = \angle OA_1C = 90°$, it follows that points B, A_1 and C lie on one line and since all the circles have equal radii, $BA_1 = A_1C$.

Points A_1, B_1, C_1 are the midpoints of sides of triangle ABC, therefore, $BA_1 = C_1B_1$ and $BC = A_1B_1$. Since the disks are of the same radius, the equal chords BA_1 and C_1B_1 cut off the disks parts of equal area and equal chords C_1B and B_1A_1 also cut off the disc's parts of equal area. Therefore, the area of curvilinear triangle $A_1B_1C_1$ is equal to the area of parallelogram $A_1B_1C_1B$, i.e., is equal to half the area of triangle ABC.



Figure 31 (Sol. 3.40)



Figure 32 (Sol. 3.41)

3.41. The considered circles pass through the bases of the triangle's heights and, therefore, their intersection points lie on the triangle's sides. Let x, y, z and u be the areas of the considered curvilinear triangles; let a, b, c, d, e and f be the areas of the segments cut off the circles by the sides of the triangle; let p, q and r be the areas of the parts of the triangle that lie outside the inner curvilinear triangle (see Fig. 32). Then

$$\begin{aligned} x+(a+b) &= u+p+q+(c+f), \\ y+(c+d) &= u+q+r+(e+b), \\ z+(e+f) &= u+r+p+(a+d) \end{aligned}$$

By adding up these equalities we get

$$x+y+z=2(p+q+r+u)+u.$$

3.42. a) Let O and O_1 be the centers of circles S and S_1. The triangles MO_1N and PON are isosceles ones and $\angle MO_1N = \angle PON$. Therefore, points P, M and N lie on one line.

b) It is clear that $PQ^2 = PM \cdot PN = PM \cdot (PM + MN)$. Let K be the midpoint of chord AB. Then

$$PM^2 = PK^2 + MK^2 \quad \text{and } PM \cdot MN = AM \cdot MB = AK^2 - MK^2.$$

Therefore, $PQ^2 = PK^2 + AK^2 = PA^2$.

3.43. By Problem 3.42 b) $BE = BD$. Hence,

$$\angle DAE + \angle ADE = \angle DEB = \angle BDE = \angle BDC + \angle CDE.$$

Since $\angle DAB = \angle BDC$, it follows that $\angle ADE = \angle CDE$.

3.44. Let O_1 and O_2 be the centers of the inscribed circles, CP and CQ the tangents to them. Then $CO_1^2 = CP^2+PO_1^2 = CP^2+O_1M^2$ and since $CQ = CA = CP$ (by Problem 3.42

b), we have $CO_2^2 = CQ^2 + QO_2^2 = CP^2 + O_2M^2$. It follows that $CO_1^2 - CO_2^2 = MO_1^2 - MO_2^2$ and, therefore, line CM is perpendicular to O_1O_2 (see Problem 7.6). Therefore, line MN passes through point C.

Remark. If the circles do not intersect but are tangent to each other the statement is still true; in this case, however, one should replace line MN with the tangent to the circles at their common point.

3.45. Let A_1 and B_1 be the midpoints of arcs $\smile BC$ and $\smile AC$;let O the center of the inscribed circle. Then $A_1B_1 \perp CO$ (cf. Problem 2.19 a) and $MN \perp CO$, consequently, $MN \parallel A_1B_1$. Let us move points M' and N' along rays CA and CB, respectively, so that $M'N' \parallel A_1B_1$. Only for one position of points M' and N' does point L at which lines B_1M' and A_1N' intersect lie on the circumscribed circle of triangle ABC.

On the other hand, if segment MN passes through point O, then point L lies on this circle (cf. Problem 2.49).

3.46. The solution of this problem generalizes the solution of the preceding problem. It suffices to prove that the center O_1 of the inscribed circle of triangle ABC_1 lies on segment M_2N_1. Let A_1 and A_2 be the midpoints of arcs $\smile BC_1$ and $\smile BC_2$; let B_1 and B_2 be the midpoints of arcs $\smile AC_1$ and $\smile AC_2$; let PQ be the diameter of circle S perpendicular to chord AB and let points Q and C_1 lie on one side of line AB. Point O_1 is the intersection point of chords AA_1 and BB_1 and point L of tangent of circles S and S_1 is the intersection point of lines A_1N_1 and B_2M_2 (Fig. 33).



Figure 33 (Sol. 3.46)

Let $\angle C_1AB = 2\alpha$, $\angle C_1BA = 2\beta$, $\angle C_1AC_2 = 2\varphi$. Then $\smile A_1A_2 = 2\varphi = \smile B_1B_2$, i.e., $A_1B_2 \parallel B_1A_2$. For the angles between chords we have:

$$\angle(A_1B_2, BC_1) = \tfrac{1}{2}(\smile B_2C_1 + \smile A_1B) = \beta - \varphi + \alpha,$$
$$\angle(BC_1, AC_2) = \tfrac{1}{2}(\smile C_1C_2 + \smile AB) = 2\varphi + 180^\circ - 2\alpha - 2\beta.$$

Consequently, chord M_2N_1 constitutes equal angles with tangents BC_1 and AC_2, each angle equal to $\alpha + \beta - \varphi$. Therefore, $M_2N_1 \parallel A_1B_2$.

Now, suppose that points M_2' and N_1' are moved along chords AC_2 and BC_1 so that $M_2'N_1' \parallel A_1B_2$. Let lines A_1N_1' and B_2M_2' meet at point L'. Point L' lies on circle S for one position of points M_2' and N_1' only. Therefore, it suffices to indicate on arc $\smile AB$ a point L_1 such that if M_2'', N_1'' are the intersection points of chords AC_2 and L_1B_2, BC_1 and L_1A_1, respectively, then $M_2''N_1'' \parallel A_1B_2$ and point O_1 lies on segment $M_2''N_1''$. Let Q_1 be a point on circle S such that $2\angle(PQ, PQ_1) = \angle(PC_2, PC_1)$ and L_1 the intersection point of line Q_1O_1 with S.

Let us prove that L_1 is the desired point. Since $\smile B_1Q = 2\alpha$, it follows that $\smile B_2Q_1 = 2(\alpha - 2\varphi) =\smile C_2A_1$. Hence, quadrilateral $AM_2''O_1L_1$ is an inscribed one and, therefore, $\angle M_2''O_1A = \angle M_2''L_1A = \angle B_2A_1A$, i.e., $M_2''O_1 \parallel B_2A_1$.

Similarly, $N_1''O_1 \parallel B_2A_1$.

3.47. Let circles centered at O_1 and O_2 pass through point A. The radii O_1A and O_2A are perpendicular to the tangents to circles at point A and, therefore, the circles are orthogonal if and only if $\angle O_1AO_2 = 90^\circ$, i.e., $\angle O_1O_2^2 = O_1A^2 + O_2A^2$.

3.48. Let A_1, B_1 and C_1 be the centers of the given circles so that points A, B and C lie on segments B_1C_1, C_1A_1 and A_1B_1, respectively. Since $A_1B = A_1C$, $B_1A = B_1C$ and $CA = C_1B$, it follows that A, B and C are the tangent points of the inscribed circle of triangle $A_1B_1C_1$ with its sides (cf. Problem 5.1). Therefore, the radii A_1B, BC and C_1A of the given circles are tangent to the circumscribed circle of triangle ABC.

3.49. It is easy to verify that the angle of rotation from vector $\overrightarrow{O_iB}$ to vector $\overrightarrow{O_iM_i}$ (counterclockwise) is equal to $2\angle(AB, AM_i)$. It is also clear that $\angle(AB, AM_1) = \angle(AB, AM_2)$.

3.50. Let us draw through point P another line that intersects the circle at points A_1 and B_1. Then $\triangle PAA_1 \sim \triangle PB_1B$ and, therefore, $PA : PA_1 = PB_1 : PB$.

3.51. Let us draw through point P tangent PC. Since $\triangle PAC \sim \triangle PCB$, it follows that $PA : PC = PC : PB$.

3.52. Let the line that passes through point P and the center of the circle intersect the circle at points A and B. Then $PA = d+R$ and $PB = |d-R|$. Therefore, $PA \cdot PB = |d^2-R^2|$. It is also clear that the signs of the expression $d^2 - R^2$ and of the degree of point P with respect to to S are the same.

3.53. Let R_1 and R_2 be the radii of the circles. Let us consider the coordinate system in which the coordinates of the centers of the circles are $(-a, 0)$ and $(a, 0)$. By Problem 3.52 the degrees of the point with coordinates (x, y) with respect to the given circles are equal to $(x + a)^2 + y^2 - R_1^2$ and $(x - a)^2 + y^2 - R_2^2$, respectively. By equating these expressions we get $x = \frac{R_1^2-R_2^2}{4a}$. This equation determines the perpendicular to the segment that connects the centers of the circles.

3.54. The degrees of the intersection point of the circles with respect to each one of the cicles are equal to zero and, therefore, the point belongs to the radical axis. If there are two intersection points, then they uniquely determine the radical axis.

3.55. Since the centers of the circles do not lie on one line, the radical axis of the first and the second circles intersects with the radical axis of the second and third circles. The degrees of the intersection point with respect to all three circles are equal and, therefore, this intersection point lies on the radical axis of the first and third circles.

3.56. By Problem 3.54 the lines that contain chords are radical axes. By Problem 3.55 the radical axes meet at one point if the centers of the circles do not lie on one line. Otherwise they are perpendicular to this line.

3.57. Let O_1 and O_2 be the centers of given circles, r_1 and r_2 their radii. The circle S of radius r centered at O is orthogonal to circle S_i if and only if $r^2 = OO_i^2 - r_i^2$, i.e., the squared radius of S is equal to the degree of point O with respect to circle S_i. Therefore, the locus of the centers of the circles to be found is the set of the points of the radical axis whose degrees with respect to the given circles are positive.

3.58. a) The indicated points lie on the radical axis.

b) The tangent points of the outer tangents with the circles are vertices of trapezoid $ABCD$ with base AB. The midpoints of lateral sides AD and BC belong to the radical axis and, therefore, the midpoint O of diagonal AC also belongs to the radical axis. If line AC intersects the circles at points A_1 and C_1, then $OA_1 \cdot OA = OC_1 \cdot OC$; consequently, $OA_1 = OC_1$ and $AA_1 = CC_1$.

3.59. a) Let S_A and S_B be circles with diameters AA_1 and BB_1; let S be the circle with diameter AB. The common chords of circles S and S_A, S and S_B are heights AH_a and BH_b and, therefore, these heights (or their extensions) intersect at point H. By Problem 3.56 the common chord of circles S_A and S_B passes through the intersection point of chords AH_a and BH_b.

b) The common chord of circles S_A and S_B passes through the intersection point of lines A_1H_a and B_1H_b (i.e., through point C) if and only if $CB_1 \cdot CH_b = CA_1 \cdot CH_a$ (here we should consider the lengths of segments as oriented). Since

$$CH_b = \frac{a^2+b^2-c^2}{2b} \quad \text{and} \quad CH_a = \frac{a^2+b^2-c^2}{2a},$$

we deduce that $\frac{CB_1}{b} = \frac{CA_1}{a}$.

3.60. In triangle CDE, draw heights CC_1 and DD_1; let H be their intersection point. The circles with diameters AC and BD pass through points C_1 and D_1, respectively, therefore, the degree of point H with respect to each of these circles is equal to its degree with respect to the circle with diameter CD (this circle passes through points C_1 and D_1). We similarly prove that the degrees of point H with respect to to circles with diameters AC, BD and EF are equal, i.e., the radical axes of these circles pass through point H.

For the intersection points of heights of the other three triangles the proof is carried out in a similar way.

Remark. The centers of the considered circles lie on the Gauss' line (cf. Problem 4.55) and, therefore, their common radical axis is perpendicular to the Gauss line.

3.61. Lines A_1A_2, B_1B_2 and C_1C_2 meet at a point O (cf. Problem 3.56). Since $\triangle A_1OB_2 \sim \triangle B_1OA_2$, it follows that $A_1B_2 : A_2B_1 = OA_1 : OB_1$. Similarly, $B_1C_2 : B_2C_1 = OB_1 : OC_1$ and $C_1A_2 : C_2A_1 = OC_1 : OA_1$. By multiplying these equalities we get the statement desired.

3.62. Denote by B' and C' the intersection points of lines $A'M$ and $A'N$, respectively, with the line drawn through point A parallel to BC (Fig. 34).



Figure 34 (Sol. 3.62)

Since triangles $A'BM$ and $A'NC$ are isosceles ones, $\triangle ABC = \triangle A'B'C'$. Since $AM \cdot BM = A'M \cdot B'M$, the degrees of point M with respect to circles S and S' circumscribed about triangles ABC and $A'B'C'$, respectively, are equal. This is true for point N as well and, therefore, line MN is the radical axis of circles S and S'. Circles S and S' have equal radii and, therefore, their radical axis is their axis of symmetry. The symmetry through line MN sends a point A' that lies on circle S' into a point that lies on circle S.

3.63. Let AC and BD be the tangents; E and K the intersection points of lines AC and BD, AB and CD, respectively; O_1 and O_2 the centers of the circles (Fig. 35).



Figure 35 (Sol. 3.63)

Since $AB \perp O_1E$, $O_1E \perp O_2E$ and $O_2E \perp CD$, it follows that $AB \perp CD$ and, therefore, K is the intersection point of circles S_1 and S_2 with diameters AC and BD, respectively. Point K lies on the radical axis of circles S_1 and S_2; it remains to verify that line O_1O_2 is this radical axis. The radii O_1A and O_1B are tangent to S_1 and S_2, respectively, and, therefore, point O_1 lies on the radical axis. Similarly, point O_2 also lies on the radical axis.

3.64. Denote the given circles by $S_1, \dots, S_n$. For each circle S_i consider the set M_i that consists of all the points X whose degree with respect to S_i does not exceed their degrees with respect to the other circles $S_1, \dots, S_{i-1}, S_{i+1}, \dots, S_n$.

The set M_i is a convex one. Indeed, let M_{ij} be the set of points X whose degree with respect to S_i does not exceed the degree with respect to S_j. The set M_{ij} is a half plane that consists of the points that lie on the same side of the radical axis of circles S_i and S_j as S_i does. The set M_i is the intersection of the convex sets M_{ij} for all j and, therefore, is a convex set itself. Moreover, since each of the sets M_{ij} contains circle S_i, then M_i also contains S_i. Since for each point of the plane at least one of the degrees with respect to $S_1, \dots, S_n$ is the least one, the sets M_i cover the whole plane.

Now, by considering the parts of the sets M_i that lie inside the initial polygon we get the partition statement desired.

3.65. a) Points B_1 and C_1 lie on the circle with diameter BC and, therefore, the degrees of point A' with respect to the circumscribed circles of triangles $A_1B_1C_1$ and ABC are equal to the degrees of point A' with respect to this circle. This means that point A' lies on the radical axis of the Euler circle and the circumscribed circle of triangle ABC. For points B' and C' the proof is similar.

b) Let us consider triangle $A_1B_1C_1$ formed by the outer bisectors of triangle ABC (triangle $A_1B_1C_1$ is an acute one). Thanks to heading a) points A', B' and C' lie on the radical axis of the circumscribed circles of triangles ABC and $A_1B_1C_1$. The radical axis of these circles is perpendicular to the line that connects their centers, i.e., the Euler line of triangle $A_1B_1C_1$. It remains to notice that the intersection point of the heights of triangle $A_1B_1C_1$ is the intersection point of the bisectors of triangle ABC, cf. Problem 1.56 a).

3.66. Let a convex hexagon $ABCDEF$ be tangent to the circle at points R, Q, T, S, P, U (point R lies on AB, point Q lies on BC, etc.).

Take a number $a > 0$ and construct points Q' and P' on lines BC and EF so that $QQ' = PP' = a$ and vectors $\overrightarrow{QQ'}$ and $\overrightarrow{PP'}$ are codirected with vectors $\overrightarrow{CB}$ and $\overrightarrow{EF}$.

Let us similarly construct points R', S', T', U' (see Fig. 36, where $RR' = SS' = TT' = UU' = a$). Let us construct circle S_1 tangent to lines BC and EF at points Q' and P'. Let us similarly construct circles S_2 and S_3.



Figure 36 (Sol. 3.66)

Let us prove that points B and E lie on the radical axis of circles S_1 and S_2. We have

$$BQ' = QQ' - BQ = RR' - BR = BR'$$

(if $QQ' < BQ$, then $BQ' = BQ - QQ' = BR - RR' = BR'$) and

$$EP' = EP + PP' = ES + SS' = ES'.$$

We similarly prove that lines FC and AD are the radical axes of circles S_1 and S_3, S_2 and S_3, respectively. Since the radical axes of three circles meet at one point, lines AD, BE and CF meet at one point.

3.67. Let A_i be the tangent point of circles S_i and S_{i+1} and X be the intersection point of lines A_1A_4 and A_2A_3. Then X is the intersection point of the common outer tangents to circles S_2 and S_4 (cf. Problem 5.60). Since quadrilateral $A_1A_2A_3A_4$ is an inscribed one (by Problem 3.22), $XA_1 \cdot XA_4 = XA_2 \cdot XA_3$; consequently, point X lies on the radical axis of circles S_1 and S_3.

3.68. a) Let us consider the coordinate system whose origin O is at the center of the segment that connects the centers of the circles and the Ox-axis is directed along this segment. Let (x, y) be the coordinates of point P; let R and r be the radii of circles S_1 and S_2, respectively; $a = \frac{1}{2}d$. Then $(x + a)^2 + y^2 = R^2$ and

$$p = (x - a)^2 + y^2 - r^2 = ((x + a)^2 + y^2 - R^2) - 4ax - r^2 + R^2 = R^2 - r^2 - 4ax.$$

Let (x_0, y_0) be the coordinates of point A. Then

$$(x_0 + a)^2 + y_0^2 - R^2 = (x_0 - a)^2 + y_0^2 - r^2, \quad \text{i.e.,} \ x_0 = \frac{R^2 - r^2}{4a}.$$

Therefore,

$$2dh = 4a|x_0 - x| = |R^2 - r^2 - 4ax| = |p|.$$

b) Let d be the distance between the centers of the circumscribed circles of triangles ACD and BCD; let h_a and h_b be the distances from points A and B to line CD. By heading a) $|p_a| = 2dh_a$ and $|p_b| = 2dh_b$. Taking into account that $S_{BCD} = \frac{1}{2}h_bCD$ and $S_{ACD} = \frac{1}{2}h_aCD$ we get the statement desired.

CHAPTER 4. AREA

Background

1. One can calculate the area S of triangle ABC with the help of the following formulas:

a) $S = \frac{1}{2}ah_a$, where $a = BC$ and h_a is the length of the height dropped to BC;

b) $S = \frac{1}{2}bc\sin\angle A$, where b, c are sides of the triangle, $\angle A$ the angle between these sides;

c) $S = pr$, where p is a semiperimeter, r the radius of the inscribed circle. Indeed, if O is the center of the inscribed circle, then

$$S = S_{ABO} + S_{AOC} + S_{OBC} = \frac{1}{2}(c + b + a)r = pr.$$

2. If a polygon is cut into several polygons, then the sum of their areas is equal to the area of the initial polygon.

Introductory problems

1. Prove that the area of a convex quadrilateral is equal to $\frac{1}{2}d_1d_2\sin\varphi$, where d_1 and d_2 are the lengths of the diagonals and φ is the angle between them.

2. Let E and F be the midpoints of sides BC and AD of parallelogram $ABCD$. Find the area of the quadrilateral formed by lines AE, ED, BF and FC if it is known that the area of $ABCD$ is equal to S.

3. A polygon is circumscribed about a circle of radius r. Prove that the area of the polygon is equal to pr, where p is the semiperimeter of the polygon.

4. Point X is inside parallelogram $ABCD$. Prove that $S_{ABX} + S_{CDX} = S_{BCX} + S_{ADX}$.

5. Let A_1, B_1, C_1 and D_1 be the midpoints of sides CD, DA, AB, BC, respectively, of square $ABCD$ whose area is equal to S. Find the area of the quadrilateral formed by lines AA_1, BB_1, CC_1 and DD_1.

§1. A median divides the triangle into triangles of equal areas

4.1. Prove that the medians divide any triangle into six triangles of equal area.

4.2. Given triangle ABC, find all points P such that the areas of triangles ABP, BCP and ACP are equal.

4.3. Inside given triangle ABC find a point O such that the areas of triangles BOL, COM and AON are equal (points L, M and N lie on sides AB, BC and CA so that $OL \parallel BC$, $OM \parallel AC$ and $ON \parallel AB$; see Fig. 37).

4.4. On the extensions of the sides of triangle ABC points A_1, B_1 and C_1 are taken so that $\overrightarrow{AB_1} = 2\overrightarrow{AB}$, $\overrightarrow{BC_1} = 2\overrightarrow{BC}$ and $\overrightarrow{CA_1} = 2\overrightarrow{AC}$. Find the area of triangle $A_1B_1C_1$ if it is known that the area of triangle ABC is equal to S.

4.5. On the extensions of sides DA, AB, BC, CD of convex quadrilateral $ABCD$ points A_1, B_1, C_1, D_1 are taken so that $\overrightarrow{DA_1} = 2\overrightarrow{DA}$, $\overrightarrow{AB_1} = 2\overrightarrow{AB}$, $\overrightarrow{BC_1} = 2\overrightarrow{BC}$ and $\overrightarrow{CD_1} = 2\overrightarrow{CD}$. Find the area of the obtained quadrilateral $A_1B_1C_1D_1$ if it is known that the area of quadrilateral $ABCD$ is equal to S.



Figure 37 (4.3)

4.6. Hexagon $ABCDEF$ is inscribed in a circle. Diagonals AD, BE and CF are diameters of this circle. Prove that $S_{ABCDEF} = 2S_{ACE}$.

4.7. Inside a convex quadrilateral $ABCD$ there exists a point O such that the areas of triangles OAB, OBC, OCD and ODA are equal. Prove that one of the diagonals of the quadrilateral divides the other diagonal in halves.

§2. Calculation of areas

4.8. The height of a trapezoid whose diagonals are mutually perpendicular is equal to 4. Find the area of the trapezoid if it is known that the length of one of its diagonals is equal to 5.

4.9. Each diagonal of convex pentagon $ABCDE$ cuts off it a triangle of unit area. Calculate the area of pentagon $ABCDE$.

4.10. In a rectangle $ABCD$ there are inscribed two distinct rectangles with a common vertex K lying on side AB. Prove that the sum of their areas is equal to the area of rectangle $ABCD$.

4.11. In triangle ABC, point E is the midpoint of side BC, point D lies on side AC; let $AC = 1$, $\angle BAC = 60^\circ$, $\angle ABC = 100^\circ$, $\angle ACB = 20^\circ$ and $\angle DEC = 80^\circ$ (Fig. 38). Find $S_{\triangle ABC} + 2S_{\triangle CDE}$.



Figure 38 (4.11)

4.12. Triangle $T_a = \triangle A_1A_2A_3$ is inscribed in triangle $T_b = \triangle B_1B_2B_3$ and triangle T_b is inscribed in triangle $T_c = \triangle C_1C_2C_3$ so that the sides of triangles T_a and T_c are pairwise parallel. Express the area of triangle T_b in terms of the areas of triangles T_a and T_c.



Figure 39 (4.12)

4.13. On sides of triangle ABC, points A_1, B_1 and C_1 that divide its sides in ratios $BA_1 : A_1C = p$, $CB_1 : B_1A = q$ and $AC_1 : C_1B = r$, respectively, are taken. The intersection points of segments AA_1, BB_1 and CC_1 are situated as depicted on Fig. 39. Find the ratio of areas of triangles PQR and ABC.

§3. The areas of the triangles into which a quadrilateral is divided

4.14. The diagonals of quadrilateral $ABCD$ meet at point O. Prove that $S_{AOB} = S_{COD}$ if and only if $BC \parallel AD$.

4.15. a) The diagonals of convex quadrilateral $ABCD$ meet at point P. The areas of triangles ABP, BCP, CDP are known. Find the area of triangle ADP.

b) A convex quadrilateral is divided by its diagonals into four triangles whose areas are expressed in integers. Prove that the product of these integers is a perfect square.

4.16. The diagonals of quadrilateral $ABCD$ meet at point P and $S^2_{ABP} + S^2_{CDP} = S^2_{BCP} + S^2_{ADP}$. Prove that P is the midpoint of one of the diagonals.

4.17. In a convex quadrilateral $ABCD$ there are three inner points P_1, P_2, P_3 not on one line and with the property that

$$S_{ABP_i} + S_{CDP_i} = S_{BCP_i} + S_{ADP_i}$$

for $i = 1, 2, 3$. Prove that $ABCD$ is a parallelogram.

§4. The areas of the parts into which a quadrilateral is divided

4.18. Let K, L, M and N be the midpoints of sides AB, BC, CD and DA, respectively, of convex quadrilateral $ABCD$; segments KM and LN intersect at point O. Prove that

$$S_{AKON} + S_{CLOM} = S_{BKOL} + S_{DNOM}.$$

4.19. Points K, L, M and N lie on sides AB, BC, CD and DA, respectively, of parallelogram $ABCD$ so that segments KM and LN are parallel to the sides of the parallelogram. These segments meet at point O. Prove that the areas of parallelograms $KBLO$ and $MDNO$ are equal if and only if point O lies on diagonal AC.

4.20. On sides AB and CD of quadrilateral $ABCD$, points M and N are taken so that $AM : MB = CN : ND$. Segments AN and DM meet at point K, and segments BN and CM meet at point L. Prove that $S_{KMLN} = S_{ADK} + S_{BCL}$.

4.21. On side AB of quadrilateral $ABCD$, points A_1 and B_1 are taken, on side CD points C_1 and D_1 are taken so that $AA_1 = BB_1 = pAB$ and $CC_1 = DD_1 = pCD$, where $p < 0.5$. Prove that $\frac{S_{A_1B_1C_1D_1}}{S_{ABCD}} = 1 - 2p$.

4.22. Each of the sides of a convex quadrilateral is divided into five equal parts and the corresponding points of the opposite sides are connected as on Fig. 40. Prove that the area of the middle (shaded) quadrilateral is 25 times smaller than the area of the initial quadrilateral.



Figure 40 (4.22)

4.23. On each side of a parallelogram a point is taken. The area of the quadrilateral with vertices at these points is equal to half the area of the parallelogram. Prove that at least one of the diagonals of the quadrilateral is parallel to a side of the parallelogram.

4.24. Points K and M are the midpoints of sides AB and CD, respectively, of convex quadrilateral $ABCD$, points L and N lie on sides BC and AD so that $KLMN$ is a rectangle. Prove that $S_{ABCD} = S_{KLMN}$.

4.25. A square is divided into four parts by two perpendicular lines whose intersection point lies inside the square. Prove that if the areas of three of these parts are equal, then the area of all four parts are equal.

§5. Miscellaneous problems

4.26. Given parallelogram $ABCD$ and a point M, prove that

$$S_{ACM} = |S_{ABM} \pm S_{ADM}|.$$

4.27. On sides AB and BC of triangle ABC, parallelograms are constructed outwards; let P be the intersection point of the extensions of the sides of these parallelograms parallel to AB and BC. On side AC, a parallelogram is constructed whose other side is equal and parallel to BP. Prove that the area of this parallelogram is equal to the sum of areas of the first two parallelograms.

4.28. Point O inside a regular hexagon is connected with the vertices. The six triangles obtained in this way are alternately painted red and blue. Prove that the sum of areas of red triangles is equal to the sum of areas of blue ones.

4.29. The extensions of sides AD and BC of convex quadrilateral $ABCD$ meet at point O; let M and N be the midpoints of sides AB and CD; let P and Q be the midpoints of diagonals AC and BD. Prove that:

a) $S_{PMQN} = \frac{1}{2}|S_{ABD} - S_{ACD}|$;

b) $S_{OPQ} = \frac{1}{2}S_{ABCD}$.

4.30. On sides AB and CD of a convex quadrilateral $ABCD$ points E and F are taken. Let K, L, M and N be the midpoints of segments DE, BF, CE and AF, respectively. Prove that quadrilateral $KLMN$ is a convex one and its area does not depend on the choice of points E and F.

4.31. The midpoints of diagonals AC, BD, $CE, \dots$ of convex hexagon $ABCDEF$ are vertices of a convex hexagon. Prove that the area of the new hexagon is $\frac{1}{4}$ of that of the initial one.

4.32. The diameter PQ and the chord RS perpendicular to it intersect in point A. Point C lies on the circle, point B lies inside the circle and we know that $BC \parallel PQ$ and $BC = RA$. From points A and B perpendiculars AK and BL are dropped to line CQ. Prove that $S_{ACK} = S_{BCL}$.

* * *

4.33. Through point O inside triangle ABC segments are drawn parallel to its sides (Fig. 41). Segments AA_1, BB_1 and CC_1 divide triangle ABC into four triangles and three quadrilaterals. Prove that the sum of areas of the triangles adjacent to vertices A, B and C is equal to the area of the fourth triangle.

4.34. On the bisector of angle $\angle A$ of triangle ABC a point A_1 is taken so that $AA_1 = p - a = \frac{1}{2}(b + c - a)$ and through point A_1 line l_a perpendicular to the bisector is drawn. If we similarly construct lines l_b and l_c, then triangle ABC will be divided into parts among



Figure 41 (4.33)

which there are four triangles. Prove that the area of one of these triangles is equal to the sum of areas of the three other triangles.

See also problems 3.38–3.41, 13.52–13.56, 16.5, 24.5.

§6. Lines and curves that divide figures into parts of equal area

4.35. Segment MN parallel to side CD of quadrilateral $ABCD$ divides its area in halves (points M and N lie on sides BC and AD). The lengths of segments drawn from points A and B parallel to CD till they intersect with lines BC and AD are equal to a and b, respectively. Prove that $MN^2 = \frac{1}{2}(ab + c^2)$, where $c = CD$.

4.36. Each of certain three lines divides the area of a figure in halves. Prove that the area of the part of the figure confined inside the triangle formed by these lines does not exceed $\frac{1}{4}$ of the area of the whole figure.

4.37. Line l divides the area of a convex polygon in halves. Prove that this line divides the projection of the given polygon onto a line perpendicular to l in the ratio that does not exceed $1 + \sqrt{2}$.

4.38. Prove that any convex polygon can be cut by two mutually perpendicular lines in four figures of equal area.

4.39. a) Prove that any line that divides the area and the perimeter of the triangle in halves passes through the center of the inscribed circle.

b) Prove a similar statement for any circumscribed polygon.

4.40. Points A and B of circle S_1 are connected by an arc of circle S_2 that divides the area of the disk bounded by S_1 into equal parts. Prove that the length of the arc of S_2 that connects A and B is greater than that of the diameter of S_1.

4.41. Curve Γ divides a square into two parts of equal area. Prove that on Γ we can select two points A and B so that line AB passes through the center O of the square.

See also problems 6.51, 6.52, 16.8, 18.29.

§7. Formulas for the area of a quadrilateral

4.42. The diagonals of quadrilateral $ABCD$ meet at point P. The distances from points A, B and P to line CD are equal to a, b and p, respectively. Prove that the area of quadrilateral $ABCD$ is equal to $\frac{ab\cdot CD}{2p}$.

4.43. Quadrilateral $ABCD$ is inscribed into a circle of radius R; let φ be the angle between the diagonals of $ABCD$. Prove that the area S of $ABCD$ is equal to $2R^2 \cdot \sin\angle A \cdot \sin\angle B \cdot \sin\varphi$.

4.44. Prove that the area of a quadrilateral whose diagonals are not perpendicular is equal to $\frac{1}{4}\tan\varphi\cdot|a^2+c^2-b^2-d^2|$, where a, b, c and d are the lengths of the consecutive sides and φ is the angle between the diagonals.

4.45. a) Prove that the area of a convex quadrilatral $ABCD$ can be computed with the help of the formula

$$S^2=(p-a)(p-b)(p-c)(p-d)-abcd\cos^2\left(\frac{\angle B+\angle D}{2}\right),$$

where p is the semiperimeter, a, b, c, d are the lengths of the quadrilateral's sides.

b) Prove that if quadrilateral $ABCD$ is an inscribed one, then

$$S^2=(p-a)(p-b)(p-c)(p-d).$$

c) Prove that if quadrilateral $ABCD$ is a circumscribed one, then

$$S^2=abcd\sin^2\left(\frac{\angle B+\angle D}{2}\right).$$

See also Problem 11.34.

§8. An auxiliary area

4.46. Prove that the sum of distances from an arbitrary point within an equilateral triangle to the triangle's sides is constant (equal to the length of the triangle's height).

4.47. Prove that the length of the bisector AD of triangle ABC is equal to $\frac{2bc}{b+c}\cos\frac{1}{2}\alpha$.

4.48. Inside triangle ABC, point O is taken; lines AO, BO and CO meet the sides of the triangle at points A_1, B_1 and C_1, respectively. Prove that:

a) $\frac{OA_1}{AA_1}+\frac{OB_1}{BB_1}+\frac{OC_1}{CC_1}=1$;

b) $\frac{AC}{CB}\cdot\frac{BA_1}{A_1C}\cdot\frac{CB_1}{B_1A}=1$.

4.49. A $(2n-1)$-gon $A_1\dots A_{2n-1}$ and a point O are given. Lines A_kO and $A_{n+k-1}A_{n+k}$ meet at point B_k. Prove that the product of ratios $\frac{A_{n+k-1}B_k}{A_{n+k}B_k}$ for $k=1,\dots,n$ is equal to 1.

4.50. A convex polygon $A_1A_2\dots A_n$ is given. On side A_1A_2 points B_1 and D_2 are taken, on side A_2A_3 points B_2 and D_3, etc. so that if we construct parallelograms $A_1B_1C_1D_1,\dots,A_nB_nC_nD_n$, then lines $A_1C_1,\dots,A_nC_n$ would meet at one point O. Prove that

$$A_1B_1\cdot A_2B_2\cdot\dots\cdot A_nB_n=A_1D_1\cdot A_2D_2\cdot\dots\cdot A_nD_n.$$

4.51. The lengths of the sides of a triangle form an arithmetic progression. Prove that the (length of the) radius of the inscribed circle is equal to one third of the length of one of the triangle's heights.

4.52. The distances from point X on side BC of triangle ABC to lines AB and AC are equal to d_b and d_c, respectively. Prove that $\frac{d_b}{d_c}=\frac{BX\cdot AC}{CX\cdot AB}$.

4.53. A polygon circumscribed about a circle of radius r is divided into triangles (in an arbitrary way). Prove that the sum of radii of the inscribed circles of these triangles is greater than r.

4.54. Through point M inside parallelogram $ABCD$ lines PR and QS parallel to sides BC and AB are drawn (points P, Q, R and S lie on sides AB, BC, CD and DA, respectively). Prove that lines BS, PD and MC meet at one point.

4.55. Prove that if no side of a quadrilateral is parallel to any other side, then the midpoint of the segment that connects the intersection points of the opposite sides lies on the line that connects the midpoints of the diagonals. (The *Gauss line*.)

4.56. In an acute triangle ABC heights BB_1 and CC_1 are drawn and points K and L are taken on sides AB and AC so that $AK=BC_1$ and $AL=CB_1$. Prove that line AO, where O is the center of the circumscribed circle of triangle ABC, divides segment KL in halves.

4.57. Medians AA_1 and CC_1 of triangle ABC meet at point M. Prove that if quadrilateral A_1BC_1M is a circumscribed one, then $AB = BC$.

4.58. Inside triangle ABC a point O is taken. Denote the distances from O to sides BC, CA, AB of the triangle by d_a, d_b, d_c, respectively, and the distances from point O to vertices A, B, C by R_a, R_b, R_c, respectively. Prove that:

a) $aR_a \geq cd_c + bd_b$;

b) $d_aR_a + d_bR_b + d_cR_c \geq 2(d_ad_b + d_bd_c + d_cd_a)$;

c) $R_a + R_b + R_c \geq 2(d_a + d_b + d_c)$;

d) $R_aR_bR_c \geq \frac{R}{2r}(d_a + d_b)(d_b + d_c)(d_c + d_a)$.

See also problems 5.5, 10.6.

§9. Regrouping areas

4.59. Prove that the area of a regular octagon is equal to the product of the lengths of its greatest and smallest diagonals.

4.60. From the midpoint of each side of an acute triangle perpendiculars are dropped to two other sides. Prove that the area of the hexagon bounded by these perpendiculars is equal to a half area of the initial triangle.

4.61. Sides AB and CD of parallelogram $ABCD$ of unit area are divided into n equal parts; sides AD and BC are divided into m equal parts. The division points are connected as indicated on a) Fig. 42 a); b) Fig. 42 b).



Figure 42 (4.61)

What are the areas of small parallelograms obtained in this way?

4.62. a) Four vertices of a regular 12-gon lie in the midpoints of a square (Fig. 43). Prove that the area of the shaded part is equal to $\frac{1}{12}$ that of the 12-gon.



Figure 43 (4.62)

b) Prove that the area of a 12-gon inscribed in the unit circle is equal to 3.

Problems for independent study

4.63. The sides of an inscribed quadrilateral $ABCD$ satisfy the relation $AB \cdot BC = AD \cdot DC$. Prove that the areas of triangles ABC and ADC are equal.

4.64. Is it possible to use two straight cuts passing through two vertices of a triangle to divide the triangle into four parts so that three triangles (of these parts) were of equal area?

4.65. Prove that all the convex quadrilaterals with common midpoints of sides are of equal area.

4.66. Prove that if two triangles obtained by extention of sides of a convex quadrilateral to their intersection are of equal area, then one of the diagonals divides the other one in halves.

4.67. The area of a triangle is equal to S, its perimeter is equal to P. Each of the lines on which the sides of the triangle lie are moved (outwards) by a distance of h. Find the area and the perimeter of the triangle formed by the three obtained lines.

4.68. On side AB of triangle ABC, points D and E are taken so that $\angle ACD = \angle DCE = \angle ECB = \varphi$. Find the ratio $CD : CE$ if the lengths of sides AC and BC and angle φ are known.

4.69. Let AA_1, BB_1 and CC_1 be the bisectors of triangle ABC. Prove that

$$\frac{S_{A_1B_1C_1}}{S_{ABC}} = \frac{2abc}{(a+b)\cdot(b+c)\cdot(c+a)}.$$

4.70. Points M and N are the midpoints of lateral sides AB and CD of trapezoid $ABCD$. Prove that if the doubled area of the trapezoid is equal to $AN \cdot NB + CM \cdot MD$, then $AB = CD = BC + AD$.

4.71. If a quadrilateral with sides od distinct lengths is inscribed into a circle of radius R, then there exist two more quadrilaterals not equal to it with the same lengths of sides inscribed in the same circle. These quadrilaterals have not more than three distinct lengths of diagonals: d_1, d_2 and d_3. Prove that the area of the quadrilateral is equal to $\frac{d_1d_2d_3}{4R}$.

4.72. On sides AB, BC and CA of triangle ABC points C_1, A_1 and B_1 are taken; points C_2, A_2 and B_2 are symmetric to these points through the midpoints of the corresponding sides. Prove that $S_{A_1B_1C_1} = S_{A_2B_2C_2}$.

4.73. Inside triangle ABC, point P is taken. The lines that pass through P and vertices of the triangle intersect the sides at points A_1, B_1 and C_1. Prove that the area of the triangle determined by the midpoints of segments AA_1, BB_1 and CC_1 is equal to $\frac{1}{4}$ of the area of triangle $A_1B_1C_1$.

Solutions

4.1. The triangles adjacent to one side have equal bases and a common height and, therefore, are of equal area. Let M be the intersection point of the medians of triangle ABC. Line BM divides each of the triangles ABC and AMC into two triangles of equal area; consequently, $S_{ABM} = S_{BCM}$. Similarly, $S_{BCM} = S_{CAM}$.

4.2. The equality of areas of triangles ABP and BCP implies that the distances from points A and C to line BP are equal. Therefore, either line BP passes through the midpoint of segment AC or it is parallel to it. The points to be found are depicted on Fig. 44.

4.3. Denote the intersection point of line LO with side AC by L_1. Since $S_{LOB} = S_{MOC}$ and $\triangle MOC = \triangle L_1OC$, it follows that $S_{LOB} = S_{L_1CO}$. The heights of triangles LOB and L_1OC are equal and, therefore, $LO = L_1O$, i.e., point O lies on the median drawn from vertex A.



Figure 44 (Sol. 4.2)

We similarly prove that point O lies on the medians drawn from vertices B and C, i.e., O is the intersection point of the medians of the triangle. These arguments also demonstrate that the intersection point of the medians of the triangle possesses the necessary property.

4.4. Since $S_{A_1BB_1} = S_{A_1AB} = S_{ABC}$, it follows that $S_{AA_1B_1} = 2S$. Similarly, $S_{BB_1C_1} = S_{CC_1A_1} = 2S$. Therefore, $S_{ABC} = 7S$.

4.5. Since $AB = BB_1$, it follows that $S_{BB_1C} = S_{BAC}$. Since $BC = CC_1$, we have $S_{B_1C_1C} = S_{BB_1C} = S_{BAC}$ and $S_{BB_1C_1} = 2S_{BAC}$. Similarly, $S_{DD_1A_1} = 2S_{ACD}$ and, consequently,

$$S_{BB_1C_1} + S_{DD_1A_1} = 2S_{ABC} + 2S_{ACD} = 2S_{ABCD}.$$

Similarly, $S_{AA_1B_1} + S_{CC_1D_1} = 2S_{ABCD}$, consequently,

$$S_{A_1B_1C_1D_1} = S_{ABCD} + S_{AA_1B_1} + S_{BB_1C_1} + S_{CC_1D_1} + S_{DD_1A_1} = 5S_{ABCD}.$$

4.6. Let O be the center of the circumscribed circle. Since AD, BE and CF are diameters,

$$S_{ABO} = S_{DEO} = S_{AEO}, \quad S_{BCO} = S_{EFO} = S_{CEO}, \quad S_{CDO} = S_{AFO} = S_{ACO}.$$

It is also clear that $S_{ABCDEF} = 2(S_{ABO} + S_{BCO} + S_{CDO})$ and $S_{ACE} = S_{AEO} + S_{CEO} + S_{ACO}$. Therefore, $S_{ABCDEF} = 2S_{ACE}$.

4.7. Let E and F be the midpoints of diagonals AC and BD, respectively. Since $S_{AOB} = S_{AOD}$, point O lies on line AF. Similarly, point O lies on line CF. Suppose that the intersection point of the diagonals is not the midpoint of either of them. Then the lines AF and CF have a unique common point, F; hence, $O = F$. We similarly prove that $O = E$. Contradiction.

4.8. Let the length of diagonal AC of trapezoid $ABCD$ with base AD be equal to 5. Let us complement triangle ACB to parallelogram $ACBE$. The area of trapezoid $ABCD$ is equal to the area of the right triangle DBE. Let BH be a height of triangle DBE. Then $EH^2 = BE^2 - BH^2 = 5^2 - 4^2 = 3^2$ and $ED = \frac{BE^2}{EH} = \frac{25}{3}$. Therefore, $S_{DBE} = \frac{1}{2} ED \cdot BH = \frac{50}{3}$.

4.9. Since $S_{ABE} = S_{ABC}$, it follows that $EC \parallel AB$. The remaining diagonals are also parallel to the corresponding sides. Let P be the intersection point of BD and EC. If $S_{BPC} = x$, then

$$S_{ABCDE} = S_{ABE} + S_{EPB} + S_{EDC} + S_{BPC} = 3 + x.$$

(we have $S_{EPB} = S_{ABE} = 1$ because $ABPE$ is a parallelogram). Since $S_{BPC} : S_{DPC} = BP : DP = S_{EPB} : S_{EPD}$, it follows that $x : (1 - x) = 1 : x$ and, therefore, $x = \frac{\sqrt{5}-1}{2}$ and $S_{ABCDE} = \frac{\sqrt{5}+5}{2}$.

4.10. The centers of all the three rectangles coincide (see Problem 1.7) and, therefore, two smaller rectangles have a common diagonal, KL. Let M and N be the vertices of these rectangles that lie on side BC. Points M and N lie on the circle with diameter KL. Let O be the center of the circle, O_1 the projection of O to BC. Then $BO_1 = CO_1$ and $MO_1 = NO_1$ and, therefore, $BM = NC$. To prove that $S_{KLM} + S_{KLN} = S_{KBCL}$ it suffices to verify that

$$(S_{KBM} + S_{LCM}) + (S_{KBN} + S_{LCN}) = S_{KBCL} = \frac{1}{2}BC(KB + CL) = \frac{1}{2}BC \cdot AB.$$

It remains to observe that

$$KB \cdot BM + KB \cdot BN = KB \cdot BC,$$
$$LC \cdot CM + LC \cdot CN = LC \cdot BC,$$
$$KB \cdot BC + LC \cdot BC = AB \cdot BC.$$

4.11. Let us drop perpendicular l from point C to line AB. Let points A', B' and E' be symmetric to points A, B and E, respectively, through line l. Then triangle $AA'C$ is an equilateral one and $\angle ACB = \angle BCB' = \angle B'CA' = 20^\circ$. Triangles $EE'C$ and DEC are isosceles ones with the angle of 20° at the vertex and a common lateral side EC. Therefore, $S_{ABC} + 2S_{EDC} = S_{ABC} + 2S_{EE'C}$. Since E is the midpoint of BC, it follows that $2S_{EE'C} = S_{BE'C} = \frac{1}{2}S_{BB'C}$. Hence,

$$S_{ABC} + 2S_{EDC} = \frac{S_{AA'C}}{2} = \frac{\sqrt{3}}{8}.$$

4.12. Let the areas of triangles T_a, T_b and T_c be equal to a, b and c, respectively. Triangles T_a and T_c are homothetic and, therefore, the lines that connect their respective vertices meett at one point, O. The similarity coefficient k of these triangles is equal to $\sqrt{\frac{a}{c}}$. Clearly, $S_{A_1B_3O} : S_{C_1B_3O} = A_1O : C_1O = k$. Writing similar equations for $??? and adding them, we get $a : b = k$ and, therefore, $b = \sqrt{ac}$.

4.13. Making use of the result of Problem 1.3 it is easy to verify that

$$\frac{BQ}{BB_1} = \frac{p + pq}{1 + p + pq}, \qquad \frac{B_1R}{BB_1} = qr1 + q + qr,$$
$$\frac{CR}{CC_1} = \frac{q + qr}{1 + q + qr}, \qquad \frac{CP}{CC_1} = \frac{pr}{1 + r + pr}. \tag{1}$$

It is also clear that $\frac{S_{PQR}}{S_{RB_1C}} = \frac{QR}{RB_1} \cdot \frac{PR}{RC}$ and $\frac{S_{RB_1C}}{S_{ABC}} = \frac{B_1C}{AC} \cdot \frac{B_1R}{BB_1}$. Hence,

$$\frac{S_{PQR}}{S_{ABC}} = \frac{QR}{BB_1} \cdot \frac{PR}{RC} \cdot \frac{B_1C}{AC} = \frac{QR}{BB_1} \cdot \frac{PR}{CC_1} \cdot \frac{CC_1}{CR} \cdot \frac{B_1C}{AC}.$$

Taking into account that

$$\frac{QR}{BB_1} = 1 - \frac{p+pq}{1+p+pq} - \frac{qr}{1+q+rq} = \frac{1}{1+p+pq} - \frac{rq}{1+q+rq}$$
$$= \frac{(1+q)(1-pqr)}{(1+p+pq)(1+q+qr)}$$

and

$$\frac{PR}{CC_1} = \frac{(1 + r)(1 - pqr)}{(1 + q + qr)(1 + r + pr)}$$

we get

$$\frac{S_{PQR}}{S_{ABC}} = \frac{(1 - pqr)^2}{(1 + p + pq)(1 + q + qr)(1 + r + pr)}.$$

4.14. If $S_{AOB} = S_{COD}$, then $AO \cdot BO = CO \cdot DO$. Hence, $\triangle AOD \sim \triangle COB$ and $AD \parallel BC$. These arguments are invertible.

4.15. a) Since $S_{ADP} : S_{ABP} = DP : BP = S_{CDP} : S_{BCP}$, we have

$$S_{ADP} = \frac{S_{ABP} \cdot S_{CDP}}{S_{BCP}}.$$

b) Thanks to heading a) $S_{ADP} \cdot S_{CBP} = S_{ABP} \cdot S_{CDP}$. Therefore,

$$S_{ABP} \cdot S_{CBP} \cdot S_{CDP} \cdot S_{ADP} = (S_{ADP} \cdot S_{CBP})^2.$$

4.16. After division by $\frac{1}{4}\sin^2\varphi$, where φ is the angle between the diagonals, we rewrite the given equality of the areas in the form

$$(AP \cdot BP)^2 + (CP \cdot DP)^2 = (BP \cdot CP)^2 + (AP \cdot DP)^2,$$

i.e.,

$$(AP^2 - CP^2)(BP^2 - DP^2) = 0.$$

4.17. Suppose that quadrilateral $ABCD$ is not a parallelogram; for instance, let lines AB and CD intersect. By Problem 7.2 the set of points P that lie inside quadrilateral $ABCD$ for which

$$S_{ABP} + S_{CDP} = S_{BCP} + S_{ADP} = \frac{1}{2}S_{ABCD}$$

is a segment. Therefore, points P_1, P_2 and P_3 lie on one line. Contradiction.

4.18. Clearly,

$$S_{AKON} = S_{AKO} + S_{ANO} = \frac{1}{2}(S_{AOB} + S_{AOD}).$$

Similarly, $S_{CLOM} = \frac{1}{2}(S_{BCO} + S_{COD})$. Hence, $S_{AKON} + S_{CLOM} = \frac{1}{2}S_{ABCD}$.

4.19. If the areas of the parallelograms $KBLO$ and $MDNO$ are equal, then $OK \cdot OL = OM \cdot ON$. Taking into account that $ON = KA$ and $OM = LC$, we get $KO : KA = LC : LO$. Therefore, $\triangle KOA \sim \triangle LCO$ which means that point O lies on diagonal AC. These arguments are invertible.

4.20. Let h_1, h and h_2 be the distances from points A, M and B to line CD, respectively. By Problem 1.1 b) we have $h = ph_2 + (1-p)h_1$, where $p = \frac{AM}{AB}$. Therefore,

$$S_{DMC} = \frac{h \cdot DC}{2} = \frac{h_2 p \cdot DC + h_1(1-p) \cdot DC}{2} = S_{BCN} + S_{ADN}.$$

Subtracting $S_{DKN} + S_{CLN}$ from both sides of this equality we get the desired statement.

4.21. Thanks to Problem 4.20,

$$S_{ABD_1} + S_{CDB_1} = S_{ABCD}.$$

Hence,

$$\begin{gathered} S_{A_1B_1C_1D_1} = S_{A_1B_1D_1} + S_{C_1D_1B_1} \\ = (1-2p)S_{ABD_1} + (1-2p)S_{CDB_1} = (1-2p)S_{ABCD}. \end{gathered}$$

4.22. By Problem 4.21 the area of the middle quadrilateral of those deteremined by segments that connect points of sides AB and CD is $\frac{1}{5}$ of the area of the initial quadrilateral. Since each of the considered segments is divided by segments that connect the corresponding points of the other pair of opposite sides into 5 equal parts (see Problem 1.16). By making use once again of the result of Problem 4.21, we get the desired statement.

4.23. On sides AB, BC, CD and AD points K, L, M and N, respectively, are taken. Suppose that diagonal KM is not parallel to side AD. Fix points K, M and N and let us move point L along side BC. In accordance with this movement the area of triangle KLM varies strictly monotonously. Moreover, if $LN \parallel AB$, then the equality $S_{AKN} + S_{BKL} + S_{CLM} + S_{DMN} = \frac{1}{2}S_{ABCD}$ holds, i.e., $S_{KLMN} = \frac{1}{2}S_{ABCD}$.

4.24. Let L_1 and N_1 be the midpoints of sides BC and AD, respectively. Then KL_1MN_1 is a parallelogram and its area is equal to a half area of quadrilateral $ABCD$, cf. Problem 1.37 a). Therefore, it suffices to prove that the areas of parallelograms $KLMN$ and KL_1MN_1 are equal. If these parallelograms coincide, then there is nothing more to prove and if they do not coincide, then $LL_1 \parallel NN_1$ and $BC \parallel AD$ because the midpoint of segment KM is their center of symmetry. In this case the midline KM of trapezoid $ABCD$ is parallel to bases BC and AD and therefore, heights of triangles KLM and KL_1M dropped to side KM are equal, i.e., the areas of parallelograms $KLMN$ and KL_1MN_1 are equal.

4.25. Let the given lines l_1 and l_2 divide the square into four parts whose areas are equal to S_1, S_2, S_3 and S_4 so that for the first line the areas of the parts into which it divides the square are equal to S_1+S_2 and S_3+S_4 and for the second line they are equal to S_2+S_3 and S_1+S_4. Since by assumption $S_1=S_2=S_3$, it follows that $S_1+S_2=S_2+S_3$. This means that the image of line l_1 under the rotation about the center of the square through an angle of $+90^\circ$ or -90° is not just parallel to line l_2 but coincides with it.

It remains to prove that line l_1 (hence, line l_2) passes through the center of the square. Suppose that this is not true. Let us consider the images of lines l_1 and l_2 under rotations through an angle of $\pm 90^\circ$ and denote the areas of the parts into which they divide the square as plotted on Fig. 45 (on this figure both distinct variants of the disposition of the lines are plotted).



Figure 45 (Sol. 4.25)

Lines l_1 and l_2 divide the square into four parts whose areas are equal to a, $a+b$, $a+2b+c$ and $a+b$, where numbers a, b and c are nonzero. It is clear that three of the four numbers indicated cannot be equal. Contradiction.

4.26. All the three triangles considered have a common base AM. Let h_b, h_c and h_d be the distances from points B, C and D, respectively, to line AM. Since $\overrightarrow{AC}=\overrightarrow{AB}+\overrightarrow{AD}$, it follows that $h_c=|h_b\pm h_d|$.

4.27. We may assume that P is a common point of parallelograms constructed on sides AB and BC, i.e., these parallelograms are of the form $ABPQ$ and $CBPR$. It is clear that $S_{ACRQ}=S_{ABPQ}+S_{CBPR}$.

4.28. Let the length of the hexagon's side be equal to a. The extensions of red sides of the hexagon form an equilateral triangle with side $3a$ and the sum of areas of red triangles is equal to a half product of a by the sum of distances from point O to a side of this triangle and, therefore, it is equal to $\frac{3\sqrt{3}}{4}a^2$, cf. Problem 4.46.

The sum of areas of blue triangles is similarly calculated.

4.29. a) The area of parallelogram $PMQN$ is equal to $\frac{1}{4}BC\cdot AD\sin\alpha$, where α is the angle between lines AD and BC. The heights of triangles ABD and ACD dropped from vertices B and C are equal to $OB\sin\alpha$ and $OC\sin\alpha$, respectively; hence,

$$|S_{ABD}-S_{ACD}|=\frac{|OB-OC|\cdot AD\sin\alpha}{2}=\frac{BC\cdot AD\sin\alpha}{2}.$$

b) Let, for definiteness, rays AD and BC intersect. Since $PN\parallel AO$ and $QN\parallel CO$, point N lies inside triangle OPQ. Therefore,

$$S_{OPQ}=S_{PQN}+S_{PON}+S_{QON}=\tfrac{1}{2}S_{PMQN}+\tfrac{1}{4}S_{ACD}+\tfrac{1}{4}S_{BCD}$$
$$=\tfrac{1}{4}(S_{ABD}-S_{ACD}+S_{ACD}+S_{BCD}=\tfrac{1}{4}S_{ABCD}.$$

4.30. Segments KM and LN are the midlines of triangles CED and AFB and, therefore, they have a common point — the midpoint of segment EF. Moreover, $KM = \frac{1}{2}CD$, $LN = \frac{1}{2}AB$ and the angle between lines KM and LN is equal to the angle α between lines AB and CD. Therefore, the area of quadrilateral $KLMN$ is equal to $\frac{1}{8}AB \cdot CD \sin\alpha$.



Figure 46 (Sol. 4.31)

4.31. Denote the midpoints of the diagonals of hexagon $ABCDEF$ as shown on Fig. 46. Let us prove that the area of quadrilateral $A_1B_1C_1D_1$ is $\frac{1}{4}$ of the area of quadrilateral $ABCD$. To this end let us make use of the fact that the area of the quadrilateral is equal to a half product of the lengths of the diagonals by the sine of the angle between them. Since A_1C_1 and B_1D_1 are the midlines of triangles BDF and ACE, we get the desired statement.

We similarly prove that the area of quadrilateral $D_1E_1F_1A_1$ is $\frac{1}{4}$ of the area of quadrilateral $DEFA$.

4.32. Let $\alpha = \angle PQC$. Then

$$\begin{aligned} 2S_{ACK} &= CK \cdot AK = (AP\cos\alpha)\cdot(AQ\sin\alpha) = AR^2 \sin\alpha\cdot\cos\alpha \\ &= BC^2 \sin\alpha\cdot\cos\alpha = BL\cdot CL = 2S_{BCL}. \end{aligned}$$

4.33. Let S_a, S_b and S_c be the areas of the triangles adjacent to vertices A, B and C; let S be the area of the fourth of the triangles considered. Clearly,

$$S_{ACC_1} + S_{BAA_1} + S_{CBB_1} = S_{ABC} - S + S_a + S_b + S_c.$$

Moreover,

$$S_{ABC} = S_{AOC} + S_{AOB} + S_{BOC} = S_{ACC_1} + S_{BAA_1} + S_{CBB_1}.$$

4.34. Let O be the center of the inscribed circle of triangle ABC, let B_1 be the tangent point of the inscribed circle and side AC. Let us cut off triangle ABC triangle AOB_1 and reflect AOB_1 symmetrically through the bisector of angle OAB_1. Under this reflection line OB_1 turns into line l_a. Let us perform a similar operation for the remaining triangles. The common parts of the triangles obtained in this way are three triangles of the considered partition and the uncovered part of triangle ABC is the fourth triangle. It is also clear that the area of the uncovered part is equal to the sum of areas of the parts covered twice.

4.35. Let, for definiteness, rays AD and BC meet at point O. Then $S_{CDO} : S_{MNO} = c^2 : x^2$, where $x = MN$ and $S_{ABO} : S_{MNO} = ab : x^2$ because $OA : ON = a : x$ and $OB : OM = b : x$. It follows that $x^2 - c^2 = ab - x^2$, i.e., $2x^2 = ab + c^2$.

4.36. Denote the areas of the parts of the figure into which it is divided by lines as shown on Fig. 47. Let us denote by S the area of the whole figure. Since

$$S_3 + (S_2 + S_7) = \frac{1}{2}S = S_1 + S_6 + (S_2 + S_7),$$



Figure 47 (Sol. 4.36)

it follows that $S_3 = S_1 + S_6$. Adding this equality to the equality $\frac{1}{2}S = S_1 + S_2 + S_3 + S_4$ we get

$$\frac{1}{2}S = 2S_1 + S_2 + S_4 + S_6 \geq 2S_1, \quad \text{i.e.,} \quad S_1 \leq \frac{1}{4}S.$$

4.37. Let us denote the projection of line l by B and the endpoints of the projection of the polygon by A and C. Let C_1 be a point of the polygon whose projection is C. Then line l intersects the polygon at points K and L; let points K_1 and L_1 be points on lines C_1K and C_1L that have point A as their projection (Fig. 48).



Figure 48 (Sol. 4.37)

One of the parts into which line l divides the polygon is contained in trapezoid K_1KLL_1, the other part contains triangle C_1KL. Therefore, $S_{K_1KLL_1} \geq S_{C_1KL}$, i.e., $AB \cdot (KL + K_1L_1) \geq BC \cdot KL$. Since $K_1L_1 = KL \cdot \frac{AB+BC}{BC}$, we have $AB \cdot \left(2 + \frac{AB}{BC}\right) \geq BC$. Solving this inequality we get $\frac{BC}{AB} \leq 1 + \sqrt{2}$.

Similarly, $\frac{AB}{BC} \leq 1 + \sqrt{2}$. (We have to perform the same arguments but interchange A and C.)

4.38. Let S denote the area of the polygon, l an arbitrary line. Let us introduce a coordinate system in which line l is Ox-axis. Let $S(a)$ be the area of the part of the polygon below the line $y = a$. Clearly, $S(a)$ varies continuously from 0 to S as a varies from $-\infty$ to $+\infty$ and, therefore (by Calculus, see, e.g., ??), $S(a) = \frac{1}{2}S$ for some a, i.e., the line $y = a$ divides the area of the polygon in halves.

Similarly, there exists a line perpendicular to l and this perpendicular also divides the area of the polygon in halves. These two lines divide the polygon into parts whose areas are equal to S_1, S_2, S_3 and S_4 (see Fig. 49). Since $S_1 + S_2 = S_3 + S_4$ and $S_1 + S_4 = S_2 + S_3$, we have $S_1 = S_3 = A$ and $S_2 = S_4 = B$. The rotation of line l by 90° interchanges points A



Figure 49 (Sol. 4.38)

and B. Since A and B vary continuously under the rotation of l, it follows that $A = B$ for a certain position of l, i.e., the areas of all the four figures are equal at this moment.

4.39. a) Let the line that divides the area and the perimeter of triangle ABC in halves intersect sides AC and BC at points P and Q, respectively. Denote the center of the inscribed circle of triangle ABC by O and the radius of the inscribed circle by r. Then $S_{ABQOP} = \frac{1}{2}r(AP + AB + BQ)$ and $S_{OQCP} = \frac{1}{2}r(QC + CP)$. Since line PQ divides the perimeter in halves, $AP+AB+BQ = QC+CP$ and, therefore, $S_{ABQOP} = S_{OQCP}$. Moreover, $S_{ABQP} = S_{QCP}$ by the hypothesis. Therefore, $S_{OQP} = 0$, i.e., line QP passes through point O.

b) Proof is carried out similarly to that of heading a).

4.40. By considering the image of circle S_2 under the symmetry through the center of circle S_1 and taking into account the equality of areas, it is possible to prove that diameter AA_1 of circle S_1 intersects S_2 at a point K distinct from A and so that $AK > A_1K$. The circle of radius KA_1 centered at K is tangent to S_1 at point A_1 and, therefore, $BK > A_1K$, i.e., $BK + KA > A_1A$. It is also clear that the sum of the lengths of segments BK and KA is smaller than the length of the arc of S_2 that connects points A and B.

4.41. The case when point O belongs to Γ is obvious; therefore, let us assume that O does not belong to Γ. Let Γ' be the image of the curve Γ under the symmetry through point O. If curves Γ and Γ' do not intersect, then the parts into which Γ divides the square cannot be of equal area. Let X be the intersection point of Γ and Γ'; let X' be symmetric to X through point O. Since under the symmetry through point O curve Γ' turns into Γ, it follows that X' belongs to Γ. Hence, line XX' is the desired one.

4.42. Let the areas of triangles APB, BPC, CPD and DPA be equal to S_1, S_2, S_3 and S_4, respectively. Then $\frac{a}{p} = \frac{S_3+S_4}{S_3}$ and $\frac{b \cdot CD}{2} = S_3 + S_2$; consequently,

$$\frac{ab \cdot CD}{2p} = \frac{(S_3 + S_4)(S_3 + S_2)}{S_3}.$$

Taking into account that $S_2S_4 = S_1S_3$ we get the desired statement.

4.43. By applying the law of sines to triangles ABC and ABD we get $AC = 2R \sin \angle B$ and $BD = 2R \cdot \sin \angle A$. Therefore,

$$S = \frac{1}{2}AC \cdot BD \sin\varphi = 2R^2 \sin\angle A \cdot \sin\angle B \cdot \sin\varphi.$$

4.44. Since the area of the quadrilateral is equal to $\frac{1}{2}d_1d_2 \sin\varphi$, where d_1 and d_2 are the lengths of the diagonals, it remains to verify that $2d_1d_2 \cos\varphi = |a^2 + c^2 - b^2 - d^2|$. Let O be the intersection point of the diagonals of quadrilateral $ABCD$ and $\varphi = \angle AOB$. Then

$$AB^2 = AO^2 + BO^2 - 2AO \cdot OB \cos\varphi; \quad BC^2 = BO^2 + CO^2 + 2BO \cdot CO \cos\varphi.$$

Hence,

$$AB^2 - BC^2 = AO^2 - CO^2 - 2BO \cdot AC \cos\varphi.$$

Similarly,

$$CD^2 - AD^2 = CO^2 - AO^2 - 2DO \cdot AC \cos\varphi.$$

By adding these equalities we get the desired statement.

Remark. Since

$$16S^2 = 4d_1^2d_2^2\sin^2\varphi = 4d_1^2d_2^2 - (2d_1d_2\cos\varphi)^2,$$

it follows that $16S^2 = 4d_1^2d_2^2 - (a^2+c^2-b^2-d^2)^2$.

4.45. a) Let $AB = a$, $BC = b$, $CD = c$ and $AD = d$. Clearly,

$$S = S_{ABC} + S_{ADC} = \tfrac{1}{2}ab\sin\angle B + cd\sin\angle D;$$
$$a^2 + b^2 - 2ab\cos\angle B = AC^2 = c^2 + d^2 - 2cd\cos\angle D.$$

Therefore,

$$16S^2 = 4a^2b^2 - 4a^2b^2\cos^2\angle B + 8abcd\sin\angle B\sin\angle D + 4c^2d^2 - 4c^2d^2\cos^2\angle D,$$
$$(a^2+b^2-c^2-d^2)^2 + 8abcd\cos\angle B\cos\angle D = 4a^2b^2\cdot\cos^2\angle B + 4c^2d^2\cos^2\angle D.$$

By inserting the second equality into the first one we get

$$16S^2 = 4(ab+cd)^2 - (a^2+b^2-c^2-d^2)^2 - 8abcd(1+\cos\angle B\cos\angle D - \sin\angle B\sin\angle D).$$

Clearly,

$$4(ab+cd)^2 - (a^2+b^2-c^2-d^2)^2 = 16(p-a)(p-b)(p-c)(p-d);$$
$$1 + \cos\angle B\cos\angle D - \sin\angle B\sin\angle D = 2\cos^2\tfrac{\angle B+\angle D}{2}.$$

b) If $ABCD$ is an inscribed quadrilateral, then $\angle B + \angle D = 180^\circ$ and, therefore, $\cos^2\frac{\angle B+\angle D}{2} = 0$.

c) If $ABCD$ is a circumscribed quadrilateral, then $a + c = b + d$ and, therefore, $p = a + c = b + d$ and $p - a = c$, $p - b = d$, $p - c = a$, $p - d = b$. Hence,

$$S^2 = abcd\left(1 - \cos^2\frac{\angle B+\angle D}{2}\right) = abcd\sin^2\frac{\angle B+\angle D}{2}.$$

If $ABCD$ is simultaneously an inscribed and circumscribed quadrilateral, then $S^2 = abcd$.

4.46. Let us drop perpendiculars OA_1, OB_1 and OC_1 to sides BC, AC and AB, respectively, of an equilateral triangle ABC from a point O inside it. In triangle ABC, let a be the length of the side, h the length of the height. Clearly, $S_{ABC} = S_{BCO} + S_{ACO} + S_{ABO}$. Therefore, $ah = a\cdot OA_1 + a\cdot OB_1 + a\cdot OC_1$, i.e., $h = OA_1 + OB_1 + OC_1$.

4.47. Let $AD = l$. Then

$$2S_{ABD} = cl\sin\frac{\alpha}{2},\quad 2S_{ACD} = bl\sin\frac{\alpha}{2},\quad 2S_{ABD} = bc\sin\alpha.$$

Hence,

$$cl\sin\frac{\alpha}{2} + bl\sin\frac{\alpha}{2} = bc\sin\alpha = 2bc\sin\frac{\alpha}{2}\cos\frac{\alpha}{2}.$$

4.48. a) Let the distances from points A and O to line BC be equal to h and h_1, respectively. Then $S_{OBC} : S_{ABC} = h_1 : H = OA_1 : AA_1$. Similarly, $S_{OAC} : S_{ABC} = OB_1 : BB_1$ and $S_{OAB} : S_{ABC} = OC_1 : CC_1$. By adding these equalities and taking into account that $S_{OBC} + S_{OAC} + S_{OAB} = S_{ABC}$ we get the desired statement.

b) Let the distances from points B and C to line AA_1 be equal to d_b and d_c, respectively. Then $S_{ABO} : S_{ACO} = d_b : d_c = BA_1 : A_1C$. Similarly, $S_{ACO} : S_{BCO} = AC_1 : C_1B$ and $S_{BCO} : S_{ABO} = CB_1 : B_1A$. It remains to multiply these equalities.

4.49. It is easy to verify that the ratio of the lengths of segments $A_{n+k-1}B_k$ and $A_{n+k}B_k$ is equal to the ratio of areas of triangles $A_{n+k-1}OA_k$ and A_kOA_{n+k}. By multiplying these equalities we get the desired statement.

4.50. Since $A_iB_iC_iD_i$ is a parallelogram and point O lies on the extension of its diagonal A_iC_i, it follows that $S_{A_iB_iO} = S_{A_iD_iO}$ and, therefore, $A_iB_i : A_iD_i = h_i : h_{i-1}$, where h_i is the distance from point O to side A_iA_{i+1}. It remains to multiply these equalities for $i = 1, \dots, n$.

4.51. Let the lengths of sides of triangle ABC be equal to a, b and c, where $a \leq b \leq c$. Then $2b = a + c$ and $2S_{ABC} = r(a + b + c) = 3rb$, where r is the radius of the inscribed circle. On the other hand, $2S_{ABC} = h_b b$. Therefore, $r = \frac{1}{3}h_b$.

4.52. It suffices to observe that

$$d_b \cdot AB = 2S_{AXB} = BX \cdot AX \sin\varphi,$$

where $\varphi = \angle AXB$ and $d_c \cdot AC = 2S_{AXC} = CX \cdot AX \sin\varphi$.

4.53. Let $r_1, \dots, r_n$ be the radii of the inscribed circles of the obtained triangles, let $P_1, \dots, P_n$ their perimeters and $S_1, \dots, S_n$ their areas. Let us denote the area and the perimeter of the initial polygon by S and P, respectively.

It is clear that $P_i < P$ (cf. Problem 9.27, b). Hence,

$$r_1 + \dots + r_n = 2\frac{S_1}{P_1} + \dots + 2\frac{S_n}{P_n} > 2\frac{S_1}{P} + \dots + 2\frac{S_n}{P} = 2\frac{S}{P} = r.$$

4.54. Let us draw lines Q_1S_1 and P_1R_1 parallel to lines QS and PR through the intersection point N of lines BS and CM (points P_1, Q_1, R_1 and S_1 lie on sides AB, BC, CD and DA, respectively). Let F and G be the intersection points of lines PR and Q_1S_1, P_1R_1 and QS, respectively. Since point M lies on diagonal NC of parallelogram NQ_1CR_1, it follows that $S_{FQ_1QM} = S_{MRR_1G}$ (by Problem 4.19) and, therefore, $S_{NQ_1QG} = S_{NFRR_1}$. Point N lies on diagonal BS of parallelogram $ABQS$ and, therefore, $S_{AP_1NS_1} = S_{NQ_1QG} = S_{NFRR_1}$. It follows that point N lies on diagonal PD of parallelogram $APRD$.

4.55. Let E and F be the intersection points of the extensions of sides of the given quadrilateral. Denote the vertices of the quadrilateral so that E is the intersection point of the extensions of sides AB and CD beyond points B and C and F is the intersection point of rays BC and AD. Let us complement triangles AEF and ABD to parallelograms $AERF$ and $ABLD$, respectively.

The homothety with center A and coefficient 2 sends the midpoint of the diagonal BD, the midpoint of the diagonal AC and the midpoint of segment EF to points L, C and R, respectively. Therefore, it suffices to prove that points L, C and R lie on one line. This is precisely the fact proved in the preceding problem.

4.56. It suffices to verify that $S_{AKO} = S_{ALO}$, i.e., $AO \cdot AL \sin\angle OAL = AO \cdot AK \sin\angle OAK$. Clearly,

$$AL = CB_1 = BC\cos\angle C, \quad \sin\angle OAL = \cos\angle B,$$
$$AK = BC_1 = BC\cos\angle B, \quad \sin\angle OAK = \cos\angle C.$$

4.57. Since quadrilateral A_1BC_1M is a circumscribed one, then, first, the sums of the lengths of its opposite sides are equal:

$$\frac{a}{2} + \frac{m_c}{3} = \frac{c}{2} + \frac{m_a}{3}$$

and, second, its inscribed circle is simultaneously the inscribed circle of triangles AA_1B and CC_1B. Since these triangles have equal areas, their perimeters are equal:

$$c + m_a + \frac{a}{2} = a + m_c + \frac{c}{2}.$$

By multiplying the first equality by 3 and adding to the second one we get the desired statement.

4.58. First, let us prove a general inequality that will be used in the proof of headings a)–d):

$$(*)\qquad BC_1 \cdot R_a \geq B_1K \cdot R_a + C_1L \cdot R_a = 2S_{AOB_1} + 2S_{AOC_1} = AB_1 \cdot d_c + AC_1 \cdot d_b.$$

On rays AB and AC take arbitrary points B_1 and C_1 and drop from them perpendiculars B_1K and C_1L to line AO. Since $B_1C_1 \geq B_1K + C_1L$, inequality $(*)$ follows.

a) Setting $B_1 = B$ and $C_1 = C$ we get the desired statement.

b) By multiplying both sides of the inequality $aR_a \geq cd_c + bd_b$ by $\frac{d_a}{a}$ we get

$$d_aR_a \geq \frac{c}{a}d_ad_c + \frac{b}{a}d_ad_b.$$

Taking the sum of this inequality with the similar inequalities for d_bR_b and d_cR_c and taking into account that $\frac{x}{y} + \frac{y}{x} \geq 2$ we get the desired statement.

c) Take points B_1 and C_1 such that $AB_1 = AC$ and $AC_1 = AB$. Then $aR_a \geq bd_c + cd_b$, i.e., $R_a \geq \frac{b}{a}d_c + \frac{c}{a}d_b$. Taking the sum of this inequality with similar inequalities for R_b and R_c and taking into account that $\frac{x}{y} + \frac{y}{x} \geq 2$ we get the desired statement.

d) Take points B_1 and C_1 such that $AB_1 = AC_1 = 1$; then $B_1C_1 = 2\sin\frac{1}{2}\angle A$ and, therefore, $2\sin\frac{1}{2}R_a \geq d_c + d_b$. By multiplying this inequality by similar inequalities for R_b and R_c and taking into account that $\sin\frac{1}{2}\angle A \sin\frac{1}{2}\angle B \sin\frac{1}{2}\angle C = \frac{r}{4R}$ (by Problem 12.36 a)) we get the desired statement.

4.59. Let us cut triangles off a regular octagon and replace the triangles as shown on Fig. 50. As a result we get a rectangle whose sides are equal to the longest and shortest diagonals of the octagon.



Figure 50 (Sol. 4.59)

4.60. Let A_1, B_1 and C_1 be the midpoints of sides BC, CA and AB, respectively, of triangle ABC. The drawn segments are heights of triangles AB_1C_1, A_1BC_1 and A_1B_1C, respectively. Let P, Q and R be the respective intersection points of the heights of these triangles and O the intersection point of the heights of triangle $A_1B_1C_1$ (Fig. 51).

The considered hexagon consists of triangle $A_1B_1C_1$ and triangles B_1C_1P, C_1A_1Q and A_1BR. Clearly, $\triangle B_1C_1P = \triangle C_1B_1O$, $\triangle C_1A_1Q = \triangle A_1C_1O$ and $\triangle A_1B_1R = \triangle B_1A_1O$. Therefore, the area of the considered hexagon is equal to the doubled area of triangle $A_1B_1C_1$. It remains to observe that $S_{ABC} = 4S_{A_1B_1C_1}$.

4.61. a) Let us cut two parts off the parallelogram (Fig. 52 a)) and replace these parts as shown on Fig. 52 b). We get a figure composed of $mn+1$ small parallelograms. Therefore, the area of a small parallelogram is equal to $\frac{1}{mn+1}$.

b) Let us cut off the parallelogram three parts (Fig. 53 a)) and replace these parts as indicated on Fig. 53 b). We get a figure that consists of $mn-1$ small parallelograms. Therefore, the area of a small parallelogram is equal to $\frac{1}{mn-1}$.



Figure 51 (Sol. 4.60)



Figure 52 (Sol. 4.61 a))



Figure 53 (Sol. 4.61 b))

4.62. a) Let us cut the initial square into four squares and consider one of them (Fig. 54). Let point B' be symmetric to point B through line PQ. Let us prove that $\triangle APB = \triangle OB'P$. Indeed, triangle APB is an isosceles one and angle at its base is equal to 15° (Problem 2.26), hence, triangle BPQ is an isosceles one. Therefore,

$$\angle OPB' = \angle OPQ - \angle B'PQ = 75^\circ - 60^\circ = 15^\circ$$

and $\angle POB' = \frac{1}{2}\angle OPQ = 15^\circ$. Moreover, $AB = OP$. We similarly prove that $\triangle BQC = \triangle OB'Q$. It follows that the area of the shaded part on Fig. 43 is equal to the area of triangle OPQ.



Figure 54 (Sol. 4.62)

b) Let the area of the regular 12-gon inscribed in a circle of radius 1 be equal to $12x$. Thanks to heading a) the area of the square circumscribed around this circle is equal to

$12x + 4x = 16x$; on the other hand, the area of the square is equal to 4; hence, $x = \frac{1}{4}$ and $12x = 3$.

CHAPTER 5. TRIANGLES

Background

1) The *inscribed circle* of a triangle is the circle tangent to all its sides. The *center* of an inscribed circle is the intersection point of the bisectors of the triangle's angles.

An *escribed circle* of triangle ABC is the circle tangent to one side of the triangle and extensions of the other two sides. For each triangle there are exactly three escribed circles. The *center* of an escribed circle tangent to side AB is the intersection point of the bisector of angle C and the bisectors of the *outer* angles A and B.

The *circumscribed circle* of a triangle is the circle that passes through the vertices of the triangle. The *center* of the circumscribed circle of a triangle is the intersection point of the midperpendiculars to the triangle's sides.

2) For elements of a triangle ABC the following notations are often used:

a, b and c are the lengths of sides BC, CA and AB, respectively;

α, β and γ are the values of angles at vertices A, B, C;

R is the radius of the circumscribed cirlce;

r is the radius of the inscribed circle;

r_a, r_b and r_c are the radii of the escribed circles tangent to sides BC, CA and AB, respectively;

h_a, h_b and h_c the lengths of the heights dropped from vertices A, B and C, respectively.

3) If AD is the bisector of angle A of triangle ABC (or the bisector of the outer angle A), then $BD : CD = AB : AC$ (cf. Problem 1.17).

4) In a right triangle, the median drawn from the vertex of the right angle is equal to a half the hypothenuse (cf. Problem 5.16).

5) To prove that the intersection points of certain lines lie on one line *Menelaus's theorem* (Problem 5.58) is often used.

6) To prove that certain lines intersect at one point *Ceva's theorem* (Problem 5.70) is often used.

Introductory problems

1. Prove that the triangle is an isosceles one if a) one of its medians coincides with a height;

b) if one of its bisectors coincides with a height.

2. Prove that the bisectors of a triangle meet at one point.

3. On height AH of triangle ABC a point M is taken. Prove that $AB^2 - AC^2 = MB^2 - MC^2$.

4. On sides AB, BC, CA of an equilateral triangle ABC points P, Q and R, respectively, are taken so that

$$AP : PB = BQ : QC = CR : RA = 2 : 1.$$

Prove that the sides of triangle PQR are perpendicular to the respective sides of triangle ABC.

1. The inscribed and the circumscribed circles

5.1. On sides BC, CA and AB of triangle ABC, points A_1, B_1 and C_1, respectively, are taken so that $AC_1 = AB_1$, $BA_1 = BC_1$ and $CA_1 = CB_1$. Prove that A_1, B and C_1 are the points at which the inscribed circle is tangent to the sides of the triangle.

5.2. Let O_a, O_b and O_c be the centers of the escribed circles of triangle ABC. Prove that points A, B and C are the bases of heights of triangle $O_aO_bO_c$.

5.3. Prove that side BC of triangle ABC subtends (1) an angle with the vertex at the center O of the inscribed circle; the value of the angle is equal to $90^\circ + \frac{1}{2}\angle A$ and (2) an angle with the vertex at the center O_a of the escribed circle; the value of the angle is equal to $90^\circ - \frac{1}{2}\angle A$.

5.4. Inside triangle ABC, point P is taken such that

$$\angle PAB : \angle PAC = \angle PCA : \angle PCB = \angle PBC : \angle PBA = x.$$

Prove that $x = 1$.

5.5. Let A_1, B_1 and C_1 be the projections of an inner point O of triangle ABC to the heights. Prove that if the lengths of segments AA_1, BB_1 and CC_1 are equal, then they are equal to $2r$.

5.6. An angle of value $\alpha = \angle BAC$ is rotated about its vertex O, the midpoint of the basis AC of an isosceles triangle ABC. The legs of this angle meet the segments AB and BC at points P and Q, respectively. Prove that the perimeter of triangle PBQ remains constant under the rotation.

5.7. In a scalene triangle ABC, line MO is drawn through the midpoint M of side BC and the center O of the inscribed circle. Line MO intersects height AH at point E. Prove that $AE = r$.

5.8. A circle is tangent to the sides of an angle with vertex A at points P and Q. The distances from points P, Q and A to a tangent to this circle are equal to u, v and w, respectively. Prove that $\frac{uv}{w^2} = \sin^2 \frac{1}{2}\angle A$.

* * *

5.9. Prove that the points symmetric to the intersection point of the heights of triangle ABC through its sides lie on the circumscribed circle.

5.10. From point P of arc BC of the circumscribed circle of triangle ABC perpendiculars PX, PY and PZ are dropped to BC, CA and AB, respectively. Prove that $\frac{BC}{PX} = \frac{AC}{PY} + \frac{AB}{PZ}$.

* * *

5.11. Let O be the center of the circumscribed circle of triangle ABC, let I be the center of the inscribed circle, I_a the center of the escribed circle tangent to side BC. Prove that

a) $d^2 = R^2 - 2Rr$, where $d = OI$;

b) $d_a^2 = R^2 + 2Rr_a$, where $d_a = OI_a$.

5.12. The extensions of the bisectors of the angles of triangle ABC intersect the circumscribed circle at points A_1, B_1 and C_1; let M be the intersection point of bisectors. Prove that a) $\frac{MA \cdot MC}{MB_1} = 2r$; b) $\frac{MA_1 \cdot MC_1}{MB} = R$.

5.13. The lengths of the sides of triangle ABC form an arithmetic progression: a, b, c, where $a < b < c$. The bisector of angle $\angle B$ intersects the circumscribed circle at point B_1. Prove that the center O of the inscribed circle divides segment BB_1 in halves.

5.14. In triangle ABC side BC is the shortest one. On rays BA and CA, segments BD and CE, respectively, each equal to BC, are marked. Prove that the radius of the circumscribed circle of triangle ADE is equal to the distance between the centers of the inscribed and circumscribed circles of triangle ABC.

§2. Right triangles

5.15. In triangle ABC, angle $\angle C$ is a right one. Prove that $r = \frac{a+b-c}{2}$ and $r_c = \frac{a+b+c}{2}$.

5.16. In triangle ABC, let M be the midpoint of side AB. Prove that $CM = \frac{1}{2}AB$ if and only if $\angle ACB = 90°$.

5.17. Consider trapezoid $ABCD$ with base AD. The bisectors of the outer angles at vertices A and B meet at point P and the bisectors of the angles at vertices C and D meet at point Q. Prove that the length of segment PQ is equal to a half perimeter of the trapezoid.

5.18. In an isosceles triangle ABC with base AC bisector CD is drawn. The line that passes through point D perpendicularly to DC intersects AC at point E. Prove that $EC = 2AD$.

5.19. The sum of angles at the base of a trapezoid is equal to $90°$. Prove that the segment that connects the midpoints of the bases is equal to a half difference of the bases.

5.20. In a right triangle ABC, height CK from the vertex C of the right angle is drawn and in triangle ACK bisector CE is drawn. Prove that $CB = BE$.

5.21. In a right triangle ABC with right angle $\angle C$, height CD and bisector CF are drawn; let DK and DL be bisectors in triangles BDC and ADC. Prove that $CLFK$ is a square.

5.22. On hypothenuse AB of right triangle ABC, square $ABPQ$ is constructed outwards. Let $\alpha = \angle ACQ$, $\beta = \angle QCP$ and $\gamma = \angle PCB$. Prove that $\cos\beta = \cos\alpha \cdot \cos\gamma$.

See also Problems 2.65, 5.62.

§3. The equilateral triangles

5.23. From a point M inside an equilateral triangle ABC perpendiculars MP, MQ and MR are dropped to sides AB, BC and CA, respectively. Prove that

$$AP^2 + BQ^2 + CR^2 = PB^2 + QC^2 + RA^2,$$
$$AP + BQ + CR = PB + QC + RA.$$

5.24. Points D and E divide sides AC and AB of an equilateral triangle ABC in the ratio of $AD : DC = BE : EA = 1 : 2$. Lines BD and CE meet at point O. Prove that $\angle AOC = 90°$.

* * *

5.25. A circle divides each of the sides of a triangle into three equal parts. Prove that this triangle is an equilateral one.

5.26. Prove that if the intersection point of the heights of an acute triangle divides the heights in the same ratio, then the triangle is an equilateral one.

5.27. a) Prove that if $a + h_a = b + h_b = c + h_c$, then triangle ABC is a equilateral one.

b) Three squares are inscribed in triangle ABC: two vertices of one of the squares lie on side AC, those of another one lie on side BC, and those of the third lie one on AB. Prove that if all the three squares are equal, then triangle ABC is an equilateral one.

5.28. The circle inscribed in triangle ABC is tangent to the sides of the triangle at points A_1, B_1, C_1. Prove that if triangles ABC and $A_1B_1C_1$ are similar, then triangle ABC is an equilateral one.

5.29. The radius of the inscribed circle of a triangle is equal to 1, the lengths of the heights of the triangle are integers. Prove that the triangle is an equilateral one.

See also Problems 2.18, 2.26, 2.36, 2.44, 2.54, 4.46, 5.56, 7.45, 10.3, 10.77, 11.3, 11.5, 16.7, 18.9, 18.12, 18.15, 18.17-18.20, 18.22, 18.38, 24.1.

§4. Triangles with angles of 60° and 120°

5.30. In triangle ABC with angle A equal to 120° bisectors AA_1, BB_1 and CC_1 are drawn. Prove that triangle $A_1B_1C_1$ is a right one.

5.31. In triangle ABC with angle A equal to 120° bisectors AA_1, BB_1 and CC_1 meet at point O. Prove that $\angle A_1C_1O = 30^\circ$.

5.32. a) Prove that if angle $\angle A$ of triangle ABC is equal to 120° then the center of the circumscribed circle and the orthocenter are symmetric through the bisector of the outer angle $\angle A$.

b) In triangle ABC, the angle $\angle A$ is equal to 60°; O is the center of the circumscribed circle, H is the orthocenter, I is the center of the inscribed circle and I_a is the center of the escribed circle tangent to side BC. Prove that $IO = IH$ and $I_aO = I_aH$.

5.33. In triangle ABC angle $\angle A$ is equal to 120°. Prove that from segments of lengths a, b and $b+c$ a triangle can be formed.

5.34. In an acute triangle ABC with angle $\angle A$ equal to 60° the heights meet at point H.

a) Let M and N be the intersection points of the midperpendiculars to segments BH and CH with sides AB and AC, respectively. Prove that points M, N and H lie on one line.

b) Prove that the center O of the circumscribed circle lies on the same line.

5.35. In triangle ABC, bisectors BB_1 and CC_1 are drawn. Prove that if $\angle CC_1B_1 = 30^\circ$, then either $\angle A = 60^\circ$ or $\angle B = 120^\circ$.

See also Problem 2.33.

§5. Integer triangles

5.36. The lengths of the sides of a triangle are consecutive integers. Find these integers if it is known that one of the medians is perpendicular to one of the bisectors.

5.37. The lengths of all the sides of a right triangle are integers and the greatest common divisor of these integers is equal to 1. Prove that the legs of the triangle are equal to $2mn$ and $m^2 - n^2$ and the hypothenuse is equal to $m^2 + n^2$, where m and n are integers.

A right triangle the lengths of whose sides are integers is called a *Pythagorean triangle.*

5.38. The radius of the inscribed circle of a triangle is equal to 1 and the lengths of its sides are integers. Prove that these integers are equal to 3, 4, 5.

5.39. Give an example of an inscribed quadrilateral with pairwise distinct integer lengths of sides and the lengths of whose diagonals, the area and the radius of the circumscribed circle are all integers. (*Brakhmagupta.*)

5.40. a) Indicate two right triangles from which one can compose a triangle so that the lengths of the sides and the area of the composed triangle would be integers.

b) Prove that if the area of a triangle is an integer and the lengths of the sides are consecutive integers then this triangle can be composed of two right triangles the lengths of whose sides are integers.

5.41. a) In triangle ABC, the lengths of whose sides are rational numbers, height BB_1 is drawn.

Prove that the lengths of segments AB_1 and CB_1 are rational numbers.

b) The lengths of the sides and diagonals of a convex quadrilateral are rational numbers. Prove that the diagonals cut it into four triangles the lengths of whose sides are rational numbers.

See also Problem 26.7.

§6. Miscellaneous problems

5.42. Triangles ABC and $A_1B_1C_1$ are such that either their corresponding angles are equal or their sum is equal to 180°. Prove that the corresponding angles are equal, actually.

5.43. Inside triangle ABC an arbitrary point O is taken. Let points A_1, B_1 and C_1 be symmetric to O through the midpoints of sides BC, CA and AB, respectively. Prove that $\triangle ABC = \triangle A_1B_1C_1$ and, moreover, lines AA_1, BB_1 and CC_1 meet at one point.

5.44. Through the intersection point O of the bisectors of triangle ABC lines parallel to the sides of the triangle are drawn. The line parallel to AB meets AC and BC at points M and N, respectively, and lines parallel to AC and BC meet AB at points P and Q, respectively. Prove that $MN = AM + BN$ and the perimeter of triangle OPQ is equal to the length of segment AB.

5.45. a) Prove that the heigths of a triangle meet at one point.

b) Let H be the intersection point of heights of triangle ABC and R the radius of the circumscribed circle. Prove that

$$AH^2 + BC^2 = 4R^2 \quad \text{and} \quad AH = BC|\cot\alpha|.$$

5.46. Let $x = \sin 18^\circ$. Prove that $4x^2 + 2x = 1$.

5.47. Prove that the projections of vertex A of triangle ABC on the bisectors of the outer and inner angles at vertices B and C lie on one line.

5.48. Prove that if two bisectors in a triangle are equal, then the triangle is an isosceles one.

5.49. a) In triangles ABC and $A'B'C'$, sides AC and $A'C'$ are equal, the angles at vertices B and B' are equal, and the bisectors of angles $\angle B$ and $\angle B'$ are equal. Prove that these triangles are equal. (More precisely, either $\triangle ABC = \triangle A'B'C'$ or $\triangle ABC = \triangle C'B'A'$.)

b) Through point D on the bisector BB_1 of angle ABC lines AA_1 and CC_1 are drawn (points A_1 and C_1 lie on sides of triangle ABC). Prove that if $AA_1 = CC_1$, then $AB = BC$.

5.50. Prove that a line divides the perimeter and the area of a triangle in equal ratios if and only if it passes through the center of the inscribed circle.

5.51. Point E is the midpoint of arc $\smile AB$ of the circumscribed circle of triangle ABC on which point C lies; let C_1 be the midpoint of side AB. Perpendicular EF is dropped from point E to AC. Prove that:

a) line C_1F divides the perimeter of triangle ABC in halves;

b) three such lines constructed for each side of the triangle meet at one point.

5.52. On sides AB and BC of an acute triangle ABC, squares ABC_1D_1 and A_2BCD_2 are constructed outwards. Prove that the intersection point of lines AD_2 and CD_1 lies on height BH.

5.53. On sides of triangle ABC squares centered at A_1, B_1 and C_1 are constructed outwards. Let a_1, b_1 and c_1 be the lengths of the sides of triangle $A_1B_1C_1$; let S and S_1 be the areas of triangles ABC and $A_1B_1C_1$, respectively. Prove that:

a) $a_1^2 + b_1^2 + c_1^2 = a^2 + b^2 + c^2 + 6S$.

b) $S_1 - S = \frac{1}{8}(a^2 + b^2 + c^2)$.

5.54. On sides AB, BC and CA of triangle ABC (or on their extensions), points C_1, A_1 and B_1, respectively, are taken so that $\angle(CC_1, AB) = \angle(AA_1, BC) = \angle(BB_1, CA) =$

α. Lines AA_1 and BB_1, BB_1 and CC_1, CC_1 and AA_1 intersect at points C', A' and B', respectively. Prove that:

a) the intersection point of heights of triangle ABC coincides with the center of the circumscribed circle of triangle $A'B'C'$;

b) $\triangle A'B'C' \sim \triangle ABC$ and the similarity coefficient is equal to $2\cos\alpha$.

5.55. On sides of triangle ABC points A_1, B_1 and C_1 are taken so that $AB_1 : B_1C = c^n : a^n$, $BC_1 : CA = a^n : b^n$ and $CA_1 : A_1B = b^n : c^n$ (here a, b and c are the lengths of the triangle's sides). The circumscribed circle of triangle $A_1B_1C_1$ singles out on the sides of triangle ABC segments of length $\pm x, \pm y$ and $\pm z$, where the signs are chosen in accordance with the *orientation* of the triangle. Prove that

$$\frac{x}{a^{n-1}} + \frac{y}{b^{n-1}} + \frac{z}{c^{n-1}} = 0.$$

5.56. In triangle ABC *trisectors* (the rays that divide the angles into three equal parts) are drawn. The nearest to side BC trisectors of angles B and C intersect at point A_1; let us define points B_1 and C_1 similarly, (Fig. 55). Prove that triangle $A_1B_1C_1$ is an equilateral one. (*Morlie's theorem.*)



Figure 55 (5.56)

5.57. On the sides of an equilateral triangle ABC as on bases, isosceles triangles A_1BC, AB_1C and ABC_1 with angles α, β and γ at the bases such that $\alpha+\beta+\gamma = 60°$ are constructed inwards. Lines BC_1 and B_1C meet at point A_2, lines AC_1 and A_1C meet at point B_2, and lines AB_1 and A_1B meet at point C_2. Prove that the angles of triangle $A_2B_2C_2$ are equal to 3α, 3β and 3γ.

§7. Menelaus's theorem

Let $\overrightarrow{AB}$ and $\overrightarrow{CD}$ be colinear vectors. Denote by $\frac{\overline{AB}}{\overline{CD}}$ the quantity $\pm\frac{AB}{CD}$, where the plus sign is taken if the vectors $\overrightarrow{AB}$ and $\overrightarrow{CD}$ are codirected and the minus sign if the vectors are directed opposite to each other.

5.58. On sides BC, CA and AB of triangle ABC (or on their extensions) points A_1, B_1 and C_1, respectively, are taken. Prove that points A_1, B_1 and C_1 lie on one line if and only if

$$\frac{\overline{BA_1}}{\overline{CA_1}} \cdot \frac{\overline{CB_1}}{\overline{AB_1}} \cdot \frac{\overline{AC_1}}{\overline{BC_1}} = 1. \qquad \text{(\textit{Menelaus's theorem})}$$

5.59. Prove Problem 5.85 a) with the help of Menelaus's theorem.

5.60. A circle S is tangent to circles S_1 and S_2 at points A_1 and A_2, respectively. Prove that line A_1A_2 passes through the intersection point of either common outer or common inner tangents to circles S_1 and S_2.

5.61. a) The midperpendicular to the bisector AD of triangle ABC intersects line BC at point E. Prove that $BE : CE = c^2 : b^2$.

b) Prove that the intersection point of the midperpendiculars to the bisectors of a triangle and the extensions of the corresponding sides lie on one line.

5.62. From vertex C of the right angle of triangle ABC height CK is dropped and in triangle ACK bisector CE is drawn. Line that passes through point B parallel to CE meets CK at point F. Prove that line EF divides segment AC in halves.

5.63. On lines BC, CA and AB points A_1, B_1 and C_1, respectively, are taken so that points A_1, B_1 and C_1 lie on one line. The lines symmetric to lines AA_1, BB_1 and CC_1 through the corresponding bisectors of triangle ABC meet lines BC, CA and AB at points A_2, B_2 and C_2, respectively. Prove that points A_2, B_2 and C_2 lie on one line.

* * *

5.64. Lines AA_1, BB_1 and CC_1 meet at one point, O. Prove that the intersection points of lines AB and A_1B_1, BC and B_1C_1, AC and A_1C_1 lie on one line. (*Desargues's theorem.*)

5.65. Points A_1, B_1 and C_1 are taken on one line and points A_2, B_2 and C_2 are taken on another line. The intersection pointa of lines A_1B_2 with A_2B_1, B_1C_2 with B_2C_1 and C_1A_2 with C_2A_1 are C, A and B, respectively. Prove that points A, B and C lie on one line. (*Pappus' theorem.*)

5.66. On sides AB, BC and CD of quadrilateral $ABCD$ (or on their extensions) points K, L and M are taken. Lines KL and AC meet at point P, lines LM and BD meet at point Q. Prove that the intersection point of lines KQ and MP lies on line AD.

5.67. The extensions of sides AB and CD of quadrilateral $ABCD$ meet at point P and the extensions of sides BC and AD meet at point Q. Through point P a line is drawn that intersects sides BC and AD at points E and F. Prove that the intersection points of the diagonals of quadrilaterals $ABCD$, $ABEF$ and $CDFE$ lie on the line that passes through point Q.

5.68. a) Through points P and Q triples of lines are drawn. Let us denote their intersection points as shown on Fig. 56. Prove that lines KL, AC and MN either meet at one point or are parallel.



Figure 56 (5.68)

b) Prove further that if point O lies on line BD, then the intersection point of lines KL, AC and MN lies on line PQ.

5.69. On lines BC, CA and AB points A_1, B_1 and C_1 are taken. Let P_1 be an arbitrary point of line BC, let P_2 be the intersection point of lines P_1B_1 and AB, let P_3 be the intersection point of lines P_2A_1 and CA, let P_4 be the intersection point of P_3C_1 and BC, etc. Prove that points P_7 and P_1 coincide.

See also Problem 6.98.

§8. Ceva's theorem

5.70. Triangle ABC is given and on lines AB, BC and CA points C_1, A_1 and B_1, respectively, are taken so that k of them lie on sides of the triangle and $3-k$ on the extensions of the sides. Let

$$R = \frac{BA_1}{CA_1} \cdot \frac{CB_1}{AB_1} \cdot \frac{AC_1}{BC_1}.$$

Prove that

a) points A_1, B_1 and C_1 lie on one line if and only if $R=1$ and k is even. (*Menelaus's theorem.*)

b) lines AA_1, BB_1 and CC_1 either meet at one point or are parallel if and only if $R=1$ and k is odd. (*Ceva's theorem.*)

5.71. The inscribed (or an escribed) circle of triangle ABC is tangent to lines BC, CA and AB at points A_1, B_1 and C_1, respectively. Prove that lines AA_1, BB_1 and CC_1 meet at one point.

5.72. Prove that the heights of an acute triangle intersect at one point.

5.73. Lines AP, BP and CP meet the sides of triangle ABC (or their extensions) at points A_1, B_1 and C_1, respectively. Prove that:

a) lines that pass through the midpoints of sides BC, CA and AB parallel to lines AP, BP and CP, respectively, meet at one point;

b) lines that connect the midpoints of sides BC, CA and AB with the midpoints of segments AA_1, BB_1, CC_1, respectively, meet at one point.

5.74. On sides BC, CA, and AB of triangle ABC, points A_1, B_1 and C_1 are taken so that segments AA_1, BB_1 and CC_1 meet at one point. Lines A_1B_1 and A_1C_1 meet the line that passes through vertex A parallel to side BC at points C_2 and B_2, respectively. Prove that $AB_2 = AC_2$.

5.75. a) Let α, β and γ be arbitrary angles such that the sum of any two of them is not less than 180°. On sides of triangle ABC, triangles A_1BC, AB_1C and ABC_1 with angles at vertices A, B, and C equal to α, β and γ, respectively, are constructed outwards. Prove that lines AA_1, BB_1 and CC_1 meet at one point.

b) Prove a similar statement for triangles constructed on sides of triangle ABC inwards.

5.76. Sides BC, CA and AB of triangle ABC are tangent to a circle centered at O at points A_1, B_1 and C_1. On rays OA_1, OB_1 and OC_1 equal segments OA_2, OB_2 and OC_2 are marked. Prove that lines AA_2, BB_2 and CC_2 meet at one point.

5.77. Lines AB, BP and CP meet lines BC, CA and AB at points A_1, B_1 and C_1, respectively. Points A_2, B_2 and C_2 are selected on lines BC, CA and AB so that

$$\overline{BA_2} : \overline{A_2C} = \overline{A_1C} : \overline{BA_1},$$
$$\overline{CB_2} : \overline{B_2A} = \overline{B_1A} : \overline{CB_1},$$
$$\overline{AC_2} : \overline{C_2B} = \overline{C_1B} : \overline{AC_1}.$$

Prove that lines AA_2, BB_2 and CC_2 also meet at one point, Q (or are parallel).

Such points P and Q are called *isotomically conjugate with respect to triangle ABC.*

5.78. On sides BC, CA, AB of triangle ABC points A_1, B_1 and C_1 are taken so that lines AA_1, BB_1 and CC_1 intersect at one point, P. Prove that lines AA_2, BB_2 and CC_2 symmetric to these lines through the corresponding bisectors also intersect at one point, Q.

Such points P and Q are called *isogonally conjugate with respect to triangle ABC*.

5.80. The opposite sides of a convex hexagon are pairwise parallel. Prove that the lines that connect the midpoints of opposite sides intersect at one point.

5.81. From a point P perpendiculars PA_1 and PA_2 are dropped to side BC of triangle ABC and to height AA_3. Points B_1, B_2 and C_1, C_2 are similarly defined. Prove that lines A_1A_2, B_1B_2 and C_1C_2 either meet at one point or are parallel.

5.82. Through points A and D lying on a circle tangents that intersect at point S are drawn. On arc $\smile AD$ points B and C are taken. Lines AC and BD meet at point P, lines AB and CD meet at point Q. Prove that line PQ passes through point S.

5.83. a) On sides BC, CA and AB of an isosceles triangle ABC with base AB, points A_1, B_1 and C_1, respectively, are taken so that lines AA_1, BB_1 and CC_1 meet at one point. Prove that

$$\frac{AC_1}{C_1B} = \frac{\sin\angle ABB_1 \cdot \sin\angle CAA_1}{\sin\angle BAA_1 \cdot \sin\angle CBB_1}.$$

b) Inside an isosceles triangle ABC with base AB points M and N are taken so that $\angle CAM = \angle ABN$ and $\angle CBM = \angle BAN$. Prove that points C, M and N lie on one line.

5.84. In triangle ABC bisectors AA_1, BB_1 and CC_1 are drawn. Bisectors AA_1 and CC_1 intersect segments C_1B_1 and B_1A_1 at points M and N, respectively. Prove that $\angle MBB_1 = \angle NBB_1$.

See also Problems 10.56, 14.7, 14.38.

§9. Simson's line

5.85. a) Prove that the bases of the perpendiculars dropped from a point P of the circumscribed circle of a triangle to the sides of the triangle or to their extensions lie on one line.

This line is called *Simson's line* of point P with respect to the triangle.

b) The bases of perpendiculars dropped from a point P to the sides (or their extensions) of a triangle lie on one line. Prove that point P lies on the circumscribed circle of the triangle.

5.86. Points A, B and C lie on one line, point P lies outside this line. Prove that the centers of the circumscribed circles of triangles ABP, BCP, ACP and point P lie on one circle.

5.87. In triangle ABC the bisector AD is drawn and from point D perpendiculars DB' and DC' are dropped to lines AC and AB, respectively; point M lies on line $B'C'$ and $DM \perp BC$. Prove that point M lies on median AA_1.

5.88. a) From point P of the circumscribed circle of triangle ABC lines PA_1, PB_1 and PC_1 are drawn at a given (oriented) angle α to lines BC, CA and AB, respectively, so that points A_1, B_1 and C_1 lie on lines BC, CA and AB, respectively. Prove that points A_1, B_1 and C_1 lie on one line.

b) Prove that if in the definition of Simson's line we replace the angle $90°$ by an angle α, i.e., replace the perpendiculars with the lines that form angles of α, their intersection points with the sides lie on the line and the angle between this line and Simson's line becomes equal to $90° - \alpha$.

5.89. a) From a point P of the circumscribed circle of triangle ABC perpendiculars PA_1 and PB_1 are dropped to lines BC and AC, respectively. Prove that $PA \cdot PA_1 = 2Rd$, where R is the radius of the circumscribed circle, d the distance from point P to line A_1B_1.

b) Let α be the angle between lines A_1B_1 and BC. Prove that $\cos\alpha = \frac{PA}{2R}$.

5.90. Let A_1 and B_1 be the projections of point P of the circumscribed circle of triangle ABC to lines BC and AC, respectively. Prove that the length of segment A_1B_1 is equal to the length of the projection of segment AB to line A_1B_1.

5.91. Points P and C on a circle are fixed; points A and B move along the circle so that angle $\angle ACB$ remains fixed. Prove that Simson's lines of point P with respect to triangle ABC are tangent to a fixed circle.

5.92. Point P moves along the circumscribed circle of triangle ABC. Prove that Simson's line of point P with respect to triangle ABC rotates accordingly through the angle equal to a half the angle value of the arc circumvent by P.

5.93. Prove that Simson's lines of two diametrically opposite points of the circumscribed circle of triangle ABC are perpendicular and their intersection point lies on the circle of 9 points, cf. Problem 5.106.

5.94. Points A, B, C, P and Q lie on a circle centered at O and the angles between vector $\overrightarrow{OP}$ and vectors $\overrightarrow{OA}$, $\overrightarrow{OB}$, $\overrightarrow{OC}$ and $\overrightarrow{OQ}$ are equal to α, β, γ and $\frac{1}{2}(\alpha+\beta+\gamma)$, respectively. Prove that Simson's line of point P with respect to triangle ABC is parallel to OQ.

5.95. Chord PQ of the circumscribed circle of triangle ABC is perpendicular to side BC. Prove that Simson's line of point P with respect to triangle ABC is parallel to line AQ.

5.96. The heights of triangle ABC intersect at point H; let P be a point of its circumscribed circle. Prove that Simson's line of point P with respect to triangle ABC divides segment PH in halves.

5.97. Quadrilateral $ABCD$ is inscribed in a circle; l_a is Simson's line of point A with respect to triangle BCD; let lines l_b, l_c and l_d be similarly defined. Prove that these lines intersect at one point.

5.98. a) Prove that the projection of point P of the circumscribed circle of quadrilateral $ABCD$ onto Simson's lines of this point with respect to triangles BCD, CDA, DAB and BAC lie on one line. (*Simson's line of the inscribed quadrilateral.*)

b) Prove that by induction we can similarly define Simson's line of an inscribed n-gon as the line that contains the projections of a point P on Simson's lines of all $(n-1)$-gons obtained by deleting one of the vertices of the n-gon.

See also Problems 5.10, 5.59.

§10. The pedal triangle

Let A_1, B_1 and C_1 be the bases of the perpendiculars dropped from point P to lines BC, CA and AB, respectively. Triangle $A_1B_1C_1$ is called the *pedal* triangle of point P with respect to triangle ABC.

5.99. Let $A_1B_1C_1$ be the pedal triangle of point P with respect to triangle ABC. Prove that $B_1C_1 = \frac{BC\cdot AP}{2R}$, where R is the radius of the circumscribed circle of triangle ABC.

5.100. Lines AP, BP and CP intersect the circumscribed circle of triangle ABC at points A_2, B_2 and C_2; let $A_1B_1C_1$ be the pedal triangle of point P with respect to triangle ABC. Prove that $\triangle A_1B_1C_1 \sim \triangle A_2B_2C_2$.

5.101. Inside an acute triangle ABC a point P is given. If we drop from it perpendiculars PA_1, PB_1 and PC_1 to the sides, we get $\triangle A_1B_1C_1$. Performing for $\triangle A_1B_1C_1$ the same operation we get $\triangle A_2B_2C_2$ and then we similarly get $\triangle A_3B_3C_3$. Prove that $\triangle A_3B_3C_3 \sim \triangle ABC$.

5.102. A triangle ABC is inscribed in the circle of radius R centered at O. Prove that the area of the pedal triangle of point P with respect to triangle ABC is equal to $\frac{1}{4}\left|1-\frac{d^2}{R^2}\right| S_{ABC}$, where $d = |PO|$.

5.103. From point P perpendiculars PA_1, PB_1 and PC_1 are dropped on sides of triangle ABC. Line l_a connects the midpoints of segments PA and B_1C_1. Lines l_b and l_c are similarly defined. Prove that l_a, l_b and l_c meet at one point.

5.104. a) Points P_1 and P_2 are isogonally conjugate with respect to triangle ABC, cf. Problem 5.79. Prove that their pedal triangles have a common circumscribed circle whose center is the midpoint of segment P_1P_2.

b) Prove that the above statement remains true if instead of perpendiculars we draw from points P_1 and P_2 lines forming a given (oriented) angle to the sides.

See also Problems 5.132, 5.133, 14.19 b).

§11. Euler's line and the circle of nine points

5.105. Let H be the point of intersection of heights of triangle ABC, O the center of the circumscribed circle and M the point of intersection of medians. Prove that point M lies on segment OH and $OM : MH = 1 : 2$.

The line that contains points O, M and H is called *Euler's line*.

5.106. Prove that the midpoints of sides of a triangle, the bases of heights and the midpoints of segments that connect the intersection point of heights with the vertices lie on one circle and the center of this circle is the midpoint of segment OH.

The circle defined above is called the *circle of nine points*.

5.107. The heights of triangle ABC meet at point H.

a) Prove that triangles ABC, HBC, AHC and ABH have a common circle of 9 points.

b) Prove that Euler's lines of triangles ABC, HBC, AHC and ABH intersect at one point.

c) Prove that the centers of the circumscribed circles of triangles ABC, HBC, AHC and ABH constitute a quadrilateral symmetric to quadrilateral $HABC$.

5.108. What are the sides the Euler line intersects in an acute and an obtuse triangles?

5.109. a) Prove that the circumscribed circle of triangle ABC is the circle of 9 points for the triangle whose vertices are the centers of escribed circles of triangle ABC.

b) Prove that the circumscribed circle divides the segment that connects the centers of the inscribed and an escribed circles in halves.

5.110. Prove that Euler's line of triangle ABC is parallel to side BC if and only if $\tan B \tan C = 3$.

5.111. On side AB of acute triangle ABC the circle of 9 points singles out a segment. Prove that the segment subtends an angle of $2|\angle A - \angle B|$ with the vertex at the center.

5.112. Prove that if Euler's line passes through the center of the inscribed circle of a triangle, then the triangle is an isosceles one.

5.113. The inscribed circle is tangent to the sides of triangle ABC at points A_1, B_1 and C_1. Prove that Euler's line of triangle $A_1B_1C_1$ passes through the center of the circumscribed circle of triangle ABC.

5.114. In triangle ABC, heights AA_1, BB_1 and CC_1 are drawn. Let A_1A_2, B_1B_2 and C_1C_2 be diameters of the circle of nine points of triangle ABC. Prove that lines AA_2, BB_2 and CC_2 either meet at one point or are parallel.

See also Problems 3.65 a), 13.34 b).

§12. Brokar's points

5.115. a) Prove that inside triangle ABC there exists a point P such that $\angle ABP = \angle CAP = \angle BCP$.

b) On sides of triangle ABC, triangles CA_1B, CAB_1 and C_1AB similar to ABC are constructed outwards (the angles at the first vertices of all the four triangles are equal, etc.). Prove that lines AA_1, BB_1 and CC_1 meet at one point and this point coincides with the point found in heading a).

This point P is called *Brokar's point* of triangle ABC. The proof of the fact that there exists *another* Brokar's point Q for which $\angle BAQ = \angle ACQ = \angle CBQ$ is similar to the proof of existence of P given in what follows. We will refer to P and Q as the *first* and the *second* Brokar's points.

5.116. a) Through Brokar's point P of triangle ABC lines AB, BP and CP are drawn. They intersect the circumscribed circle at points A_1, B_1 and C_1, respectively. Prove that $\triangle ABC = \triangle B_1C_1A_1$.

b) Triangle ABC is inscribed into circle S. Prove that the triangle formed by the intersection points of lines PA, PB and PC with circle S can be equal to triangle ABC for no more than 8 distinct points P. (We suppose that the intersection points of lines PA, PB and PC with the circle are distinct from points A, B and C.)

5.117. a) Let P be Brokar's point of triangle ABC. Let $\varphi = \angle ABP = \angle BCP = \angle CAP$. Prove that $\cot\varphi = \cot\alpha + \cot\beta + \cot\gamma$.

The angle φ from Problem 5.117 is called *Brokar's angle* of triangle ABC.

b) Prove that Brokar's points of triangle ABC are isogonally conjugate to each other (cf. Problem 5.79).

c) The tangent to the circumscribed circle of triangle ABC at point C and the line passing through point B parallel to AC intersect at point A_1. Prove that Brokar's angle of triangle ABC is equal to angle $\angle A_1AC$.

5.118. a) Prove that Brokar's angle of any triangle does not exceed 30°.

b) Inside triangle ABC, point M is taken. Prove that one of the angles $\angle ABM$, $\angle BCM$ and $\angle CAM$ does not exceed 30°.

5.119. Let Q be the second Brokar's point of triangle ABC, let O be the center of its circumscribed circle; A_1, B_1 and C_1 the centers of the circumscribed circles of triangles CAQ, ABQ and BCQ, respectively. Prove that $\triangle A_1B_1C_1 \sim \triangle ABC$ and O is the first Brokar's point of triangle $A_1B_1C_1$.

5.120. Let P be Brokar's point of triangle ABC; let R_1, R_2 and R_3 be the radii of the circumscribed circles of triangles ABP, BCP and CAP, respectively. Prove that $R_1R_2R_3 = R^3$, where R is the radius of the circumscribed circle of triangle ABC.

5.121. Let P and Q be the first and the second Brokar's points of triangle ABC. Lines CP and BQ, AP and CQ, BP and AQ meet at points A_1, B_1 and C_1, respectively. Prove that the circumscribed circle of triangle $A_1B_1C_1$ passes through points P and Q.

5.122. On sides CA, AB and BC of an acute triangle ABC points A_1, B_1 and C_1, respectively, are taken so that $\angle AB_1A_1 = \angle BC_1B_1 = \angle CA_1C_1$. Prove that $\triangle A_1B_1C_1 \sim \triangle ABC$ and the center of the rotational homothety that sends one triangle into another coincides with the first Brokar's point of both triangles.

See also Problem 19.55.

§13. Lemoine's point

Let AM be a median of triangle ABC and line AS be symmetric to line AM through the bisector of angle A (point S lies on segment BC). Then segment AS is called a *simedian* of triangle ABC; sometimes the whole ray AS is referred to as a simedian.

Simedians of a triangle meet at the point *isogonally conjugate* to the intersection point of medians (cf. Problem 5.79). The intersection point of simedians of a triangle is called *Lemoine's point*.

5.123. Let lines AM and AN be symmetric through the bisector of angle $\angle A$ of triangle ABC (points M and N lie on line BC). Prove that $\frac{BM \cdot BN}{CM \cdot CN} = \frac{c^2}{b^2}$. In particular, if AS is a simedian, then $\frac{BS}{CS} = \frac{c^2}{b^2}$.

5.124. Express the length of simedian AS in terms of the lengths of sides of triangle ABC.

Segment B_1C_1, where points B_1 and C_1 lie on rays AC and AB, respectively, is said to be *antiparallel* to side BC if $\angle AB_1C_1 = \angle ABC$ and $\angle AC_1B_1 = \angle ACB$.

5.125. Prove that simedian AS divides any segment B_1C_1 antiparallel to side BC in halves.

5.126. The tangent at point B to the circumscribed circle S of triangle ABC intersects line AC at point K. From point K another tangent KD to circle S is drawn. Prove that BD is a simedian of triangle ABC.

5.127. Tangents to the circumscribed circle of triangle ABC at points B and C meet at point P. Prove that line AP contains simedian AS.

5.128. Circle S_1 passes through points A and B and is tangent to line AC, circle S_2 passes through points A and C and is tangent to line AB. Prove that the common chord of these circles is a simedian of triangle ABC.

5.129. Bisectors of the outer and inner angles at vertex A of triangle ABC intersect line BC at points D and E, respectively. The circle with diameter DE intersects the circumscribed circle of triangle ABC at points A and X. Prove that AX is a simedian of triangle ABC.

* * *

5.130. Prove that Lemoine's point of right triangle ABC with right angle $\angle C$ is the midpoint of height CH.

5.131. Through a point X inside triangle ABC three segments antiparallel to its sides are drawn, cf. Problem 5.125?. Prove that these segments are equal if and only if X is Lemoine's point.

5.132. Let A_1, B_1 and C_1 be the projections of Lemoine's point K to the sides of triangle ABC. Prove that K is the intersection point of medians of triangle $A_1B_1C_1$.

5.133. Let A_1, B_1 and C_1 be the projections of Lemoine's point K of triangle ABC on sides BC, CA and AB, respectively. Prove that median AM of triangle ABC is perpendicular to line B_1C_1.

5.134. Lines AK, BK and CK, where K is Lemoine's point of triangle ABC, intersect the circumscribed circle at points A_1, B_1 and C_1, respectively. Prove that K is Lemoine's point of triangle $A_1B_1C_1$.

5.135. Prove that lines that connect the midpoints of the sides of a triangle with the midpoints of the corresponding heights intersect at Lemoine's point.

See also Problems 11.22, 19.54, 19.55.

Problems for independent study

5.136. Prove that the projection of the diameter of a circumscribed circle perpendicular to a side of the triangle to the line that contains the second side is equal to the third side.

5.137. Prove that the area of the triangle with vertices in the centers of the escribed circles of triangle ABC is equal to $2pR$.

5.138. An isosceles triangle with base a and the lateral side b, and an isosceles triangle with base b and the lateral side a are inscribed in a circle of radius R. Prove that if $a \neq b$, then $ab = \sqrt{5}R^2$.

5.139. The inscribed circle of right triangle ABC is tangent to the hypothenuse AB at point P; let CH be a height of triangle ABC. Prove that the center of the inscribed circle of triangle ACH lies on the perpendicular dropped from point P to AC.

5.140. The inscribed circle of triangle ABC is tangent to sides CA and AB at points B_1 and C_1, respectively, and an escribed circle is tangent to the extension of sides at points B_2 and C_2. Prove that the midpoint of side BC is equidistant from lines B_1C_1 and B_2C_2.

5.141. In triangle ABC, bisector AD is drawn. Let O, O_1 and O_2 be the centers of the circumscribed circles of triangles ABC, ABD and ACD, respectively. Prove that $OO_1 = OO_2$.

5.142. The triangle constructed from a) medians, b) heights of triangle ABC is similar to triangle ABC. What is the ratio of the lengths of the sides of triangle ABC?

5.143. Through the center O of an equilateral triangle ABC a line is drawn. It intersects lines BC, CA and AB at points A_1, B_1 and C_1, respectively. Prove that one of the numbers $\frac{1}{OA_1}$, $\frac{1}{OB_1}$ and $\frac{1}{OC_1}$ is equal to the sum of the other two numbers.

5.144. In triangle ABC heights BB_1 and CC_1 are drawn. Prove that if $\angle A = 45^\circ$, then B_1C_1 is a diameter of the circle of nine points of triangle ABC.

5.145. The angles of triangle ABC satisfy the relation $\sin^2\angle A + \sin^2\angle B + \sin^2\angle C = 1$. Prove that the circumscribed circle and the circle of nine points of triangle ABC intersect at a right angle.

Solutions

5.1. Let $AC_1 = AB_1 = x$, $BA_1 = BC_1 = y$ and $CA_1 = CB_1 = z$. Then

$$a = y + z, \quad b = z + x \quad \text{and} \quad c = x + y.$$

Subtracting the third equality from the sum of the first two ones we get $z = \frac{a+b-c}{2}$. Hence, if triangle ABC is given, then the position of points A_1 and B_1 is uniquely determined. Similarly, the position of point C_1 is also uniquely determined. It remains to notice that the tangency points of the inscribed circle with the sides of the triangle satisfy the relations indicated in the hypothesis of the problem.

5.2. Rays CO_a and CO_b are the bisectors of the outer angles at vertex C, hence, C lies on line O_aO_b and $\angle O_aCB = \angle O_bCA$. Since CO_c is the bisector of angle $\angle BCA$, it follows that $\angle BCO_c = \angle ACO_c$. Adding these equalities we get: $\angle O_aCO_c = \angle O_cCO_b$, i.e., O_cC is a height of triangle $O_aO_bO_c$. We similarly prove that O_aA and O_bB are heights of this triangle.

5.3. Clearly,

$$\angle BOC = 180^\circ - \angle CBO - \angle BCO = 180^\circ - \frac{\angle B}{2} - \frac{\angle C}{2} = 90^\circ + \frac{\angle A}{2}$$

and $\angle BO_aC = 180^\circ - \angle BOC$, because $\angle OBO_a = \angle OCO_a = 90^\circ$.

5.4. Let AA_1, BB_1 and CC_1 be the bisectors of triangle ABC and O the intersection point of these bisectors. Suppose that $x > 1$. Then $\angle PAB > \angle PAC$, i.e., point P lies inside triangle AA_1C. Similarly, point P lies inside triangles CC_1B and BB_1A. But the only common point of these three triangles is point O. Contradiction. The case $x < 1$ is similarly treated.

5.5. Let d_a, d_b and d_c be the distances from point O to sides BC, CA and AB. Then $ad_a + bd_b + cd_c = 2S$ and $ah_a = bh_b = ch_c = 2S$. If $h_a - d_a = h_b - d_b = h_c - d_c = x$, then

$$(a + b + c)x = a(h_a - d_a) = b(h_b - d_b) + c(h_c - d_c) = 6S - 2S = 4S.$$

Hence, $x = \frac{4S}{2p} = 2r$.

5.6. Let us prove that point O is the center of the escribed circle of triangle PBQ tangent to side PQ. Indeed, $\angle POQ = \angle A = 90^\circ - \frac{1}{2}\angle B$. The angle of the same value with the vertex at the center of the escribed circle subtends segment PQ (Problem 5.3). Moreover, point O lies on the bisector of angle B. Hence, the semiperimeter of triangle PBQ is equal to the length of the projection of segment OB to line CB.

5.7. Let P be the tangent point of the inscribed circle with side BC, let PQ be a diameter of the inscribed circle, R the intersection point of lines AQ and BC. Since $CR = BP$ (cf. Problem 19.11 a)) and M is the midpoint of side BC, we have: $RM = PM$. Moreover, O is the midpoint of diameter PQ, hence, $MO \parallel QR$ and since $AH \parallel PQ$, we have $AE = OQ$.

5.8. The given circle can be the inscribed as well as the escribed circle of triangle ABC cut off by the tangent from the angle. Making use of the result of Problem 3.2 we can verify that in either case

$$\frac{uv}{w^2} = \frac{(p-b)(p-c)\sin\angle B \sin\angle C}{h_a^2}.$$

It remains to notice that $h_a = b\sin\angle C = c\sin\angle B$ and $\frac{(p-b)(p-c)}{bc} = \sin^2\frac{1}{2}\angle A$ (Problem 12.13).

5.9. Let A_1, B_1 and C_1 be points symmetric to point H through sides BC, CA and AB, respectively. Since $AB \perp CH$ and $BC \perp AH$, it follows that $\angle(AB, BC) = \angle(CH, HA)$ and since triangle AC_1H is an isosceles one, $\angle(CH, HA) = \angle(AC_1, C_1C)$. Hence, $\angle(AB, BC) = \angle(AC_1, C_1C)$, i.e., point C_1 lies on the circumscribed circle of triangle ABC. We similarly prove that points A_1 and B_1 lie on this same circle.

5.10. Let R be the radius of the circumscribed circle of triangle ABC. This circle is also the circumscribed circle of triangles ABP, APC and PBC. Clearly, $\angle ABP = 180^\circ - \angle ACP = \alpha$, $\angle BAP = \angle BCP = \beta$ and $\angle CAP = \angle CBP = \gamma$. Hence,

$$PX = PB\sin\gamma = 2R\sin\beta\sin\gamma,\ PY = 2R\sin\alpha\sin\gamma \text{ and } P = 2R\sin\alpha\sin\beta.$$

It is also clear that

$$BC = 2R\sin\angle BAC = 2R\sin(\beta+\gamma),\ AC = 2R\sin(\alpha-\gamma),\ AB = 2R\sin(\alpha+\beta).$$

It remains to verify the equality

$$\frac{\sin(\beta+\gamma)}{\sin\beta\sin\gamma} = \frac{\sin(\alpha-\gamma)}{\sin\alpha\sin\gamma} + \frac{\sin(\alpha+\beta)}{\sin\alpha\sin\beta}$$

which is subject to a direct calculation.

5.11. a) Let M be the intersection point of line AI with the circumscribed circle. Drawing the diameter through point I we get

$$AI \cdot IM = (R + d)(R - d) = R^2 - d^2.$$

Since $IM = CM$ (by Problem 2.4 a)), it follows that $R^2 - d^2 = AI \cdot CM$. It remains to observe that $AI = \frac{r}{\sin\frac{1}{2}\angle A}$ and $CM = 2R\sin\frac{1}{2}\angle A$.

b) Let M be the intersection point of line AI_a with the circumscribed circle. Then $AI_a \cdot I_aM = d_a^2 - R^2$. Since $I_aM = CM$ (by Problem 2.4 a)), it follows that $d_a^2 - R^2 = AI_a \cdot CM$. It remains to notice that $AI_a = \frac{r_a}{\sin\frac{1}{2}\angle A}$ and $CM = 2R\sin\frac{1}{2}\angle A$.

5.12. a) Since B_1 is the center of the circumscribed circle of triangle AMC (cf. Problem 2.4 a)), $AM = 2MB_1 \sin\angle ACM$. It is also clear that $MC = \frac{r}{\sin\angle ACM}$. Hence, $\frac{MA\cdot MC}{MB_1} = 2r$.

b) Since

$$\angle MBC_1 = \angle BMC_1 = 180^\circ - \angle BMC \quad \text{and } \angle BC_1M = \angle A,$$

it follows that

$$\frac{MC_1}{BC} = \frac{BM}{BC}\cdot\frac{MC_1}{BM} = \frac{\sin\angle BCM}{\sin\angle BMC}\cdot\frac{\sin\angle MBC_1}{\sin\angle BC_1M} = \frac{\sin\angle BCM}{\sin\angle A}.$$

Moreover, $MB = 2MA_1 \sin\angle BCM$. Therefore, $\frac{MC_1\cdot MA_1}{MB} = \frac{BC}{2\sin\angle A} = R$.

5.13. Let M be the midpoint of side AC, and N the tangent point of the inscribed circle with side BC. Then $BN = p - b$ (see Problem 3.2), hence, $BN = AM$ because $p = \frac{3}{2}b$ by assumption. Moreover, $\angle OBN = \angle B_1AM$ and, therefore, $\triangle OBN = \triangle B_1AM$, i.e., $OB = B_1A$. But $B_1A = B_1O$ (see Problem 2.4 a)).

5.14. Let O and O_1 be the centers of the inscribed and circumscribed circles of triangle ABC. Let us consider the circle of radius $d = OO_1$ centered at O. In this circle, let us draw chords O_1M and O_1N parallel to sides AB and AC, respectively. Let K be the tangent point of the inscribed circle with side AB and L the midpoint of side AB. Since $OK \perp AB$, $O_1L \perp AB$ and $O_1M \parallel AB$, it follows that

$$O_1M = 2KL = 2BL - 2BK = c - (a + c - b) = b - a = AE.$$

Similarly, $O_1N = AD$ and, therefore, $\triangle MO_1N = \triangle EAD$. Consequently, the radius of the circumscribed circle of triangle EAD is equal to d.

5.15. Let the inscribed circle be tangent to side AC at point K and the escribed circle be tangent to the extension of side AC at point L. Then $r = CK$ and $r_c = CL$. It remains to make use of the result of Problem 3.2.

5.16. Since $\frac{1}{2}AB = AM = BM$, it follows that $CM = \frac{1}{2}AB$ if and only if point C lies on the circle with diameter AB.

5.17. Let M and N be the midpoints of sides AB and CD. Triangle APB is a right one; hence, $PM = \frac{1}{2}AB$ and $\angle MPA = \angle PAM$ and, therefore, $PM \parallel AD$. Similar arguments show that points P, M and Q lie on one line and

$$PQ = PM + MN + NQ = \frac{AB + (BC + AD) + CD}{2}.$$

5.18. Let F be the intersection point of lines DE and BC; let K be the midpoint of segment EC. Segment CD is simultaneosly a bisector and a height of triangle ECF, hence, $ED = DF$ and, therefore, $DK \parallel FC$. Median DK of right triangle EDC is twice shorter its hypothenuse EC (Problem 5.16), hence, $AD = DK = \frac{1}{2}EC$.

5.19. Let the sum of the angles at the base AD of trapezoid $ABCD$ be equal to 90°. Denote the intersection point of lines AB and CD by O. Point O lies on the line that passes through the midpoints of the bases. Let us draw through point C line CK parallel to this line and line CE parallel to line AB (points K and E lie on base AD). Then CK is a median of right triangle ECD, hence, $CK = \frac{ED}{2} = \frac{AD-BC}{2}$ (cf. Problem 5.16).

5.20. It is clear that $\angle CEB = \angle A + \angle ACE = \angle BCK + \angle KCE = \angle BCE$.

5.21. Segments CF and DK are bisectors in similar triangles ACB and CDB and, therefore, $AB : FB = CB : KB$. Hence, $FK \parallel AC$. We similarly prove that $LF \parallel CB$.

Therefore, $CLFK$ is a rectangle whose diagonal CF is the bisector of angle LCK, i.e., the rectangle is a square.

5.22. Since $\frac{\sin\angle ACQ}{AQ} = \frac{\sin\angle AQC}{AC}$, it follows that

$$\frac{\sin\alpha}{a} = \frac{\sin(180^\circ - \alpha - 90^\circ - \varphi)}{a\cos\varphi} = \frac{\cos(\alpha+\varphi)}{a\cos\varphi},$$

where a is the (length of the) side of square $ABPQ$ and $\varphi = \angle CAB$. Hence, $\cot\alpha = 1+\tan\varphi$. Similarly,

$$\cot\gamma = 1 + \tan(90^\circ - \varphi) = 1 + \cot\varphi.$$

It follows that

$$\tan\alpha + \tan\gamma = \frac{1}{1+\tan\varphi} + \frac{1}{1+\cot\varphi} = 1$$

and, therefore,

$$\cos\alpha\cos\gamma = \cos\alpha\sin\gamma + \cos\gamma\sin\alpha = \sin(\alpha+\gamma) = \cos\beta.$$

5.23. By Pythagoras theorem

$$AP^2 + BQ^2 + CR^2 + (AM^2 - PM^2) + (BM^2 - QM^2) + (CM^2 - RM^2)$$

and

$$PB^2 + QC^2 + RA^2 = (BM^2 - PM^2) + (CM^2 - QM^2) + (AM^2 - RM^2).$$

These equations are equal.

Since

$$AP^2 + BQ^2 + CR^2 = (a - PB)^2 + (a - QC)^2 + (a - RA)^2 = \\ 3a^2 - 2a(PB + QC + RA) + PB^2 + QC^2 + RA^2,$$

where $a = AB$, it follows that $PB + QC + RA = \frac{3}{2}a$.

5.24. Let point F divide segment BC in the ratio of $CF : FB = 1 : 2$; let P and Q be the intersection points of segment AF with BD and CE, respectively. It is clear that triangle OPQ is an equilateral one. Making use of the result of Problem 1.3 it is easy to verify that $AP : PF = 3 : 4$ and $AQ : QF = 6 : 1$. Hence, $AP : PQ : QF = 3 : 3 : 1$ and, therefore, $AP = PQ = OP$. Hence, $\angle AOP = \frac{180^\circ - \angle APO}{2} = 30^\circ$ and $\angle AOC = \angle AOP + \angle POQ = 90^\circ$.

5.25. Let A and B, C and D, E and F be the intersection points of the circle with sides PQ, QR, RP, respectively, of triangle PQR. Let us consider median PS. It connects the midpoints of parallel chords FA and DC and, therefore, is perpendicular to them. Hence, PS is a height of triangle PQR and, therefore, $PQ = PR$. Similarly, $PQ = QR$.

5.26. Let H be the intersection point of heights AA_1, BB_1 and CC_1 of triangle ABC. By hypothesis, $A_1H \cdot BH = B_1H \cdot AH$. On the other hand, since points A_1 and B_1 lie on the circle with diameter AB, then $AH \cdot A_1H = BH \cdot B_1H$. It follows that $AH = BH$ and $A_1H = B_1H$ and, therefore, $AC = BC$. Similarly, $BC = AC$.

5.27. a) Suppose that triangle ABC is not an equilateral one; for instance, $a \neq b$. Since $a + h_a = a + b\sin\gamma$ and $b + h_b = b + a\sin\gamma$, it follows that $(a-b)(1-\sin\gamma) = 0$; hence, $\sin\gamma = 0$, i.e., $\gamma = 90^\circ$. But then $a \neq c$ and similar arguments show that $\beta = 90^\circ$. Contradiction.

b) Let us denote the (length of the) side of the square two vertices of which lie on side BC by x. The similarity of triangles ABC and APQ, where P and Q are the vertices of the square that lie on AB and AC, respectively, yields $\frac{x}{a} = \frac{h_a - x}{h_a}$, i.e., $x = \frac{ah_a}{a+h_a} = \frac{2S}{a+h_a}$.

Similar arguments for the other squares show that $a + h_a = b + h_b = c + h_c$.

5.28. If α, β and γ are the angles of triangle ABC, then the angles of triangle $A_1B_1C_1$ are equal to $\frac{\beta+\gamma}{2}$, $\frac{\gamma+\alpha}{2}$ and $\frac{\alpha+\beta}{2}$. Let, for definiteness, $\alpha \geq \beta \geq \gamma$. Then $\frac{\alpha+\beta}{2} \geq \frac{\alpha+\gamma}{2} \geq \frac{\beta+\gamma}{2}$. Hence, $\alpha = \frac{\alpha+\beta}{2}$ and $\gamma = \frac{\beta+\gamma}{2}$, i.e., $\alpha = \beta$ and $\beta = \gamma$.

5.29. In any triangle a height is longer than the diameter of the inscribed circle. Therefore, the lengths of heights are integers greater than 2, i.e., all of them are not less than 3. Let S be the area of the triangle, a the length of its longest side and h the corresponding height.

Suppose that the triangle is not an equilateral one. Then its perimeter P is shorter than $3a$. Therefore, $3a > P = \Pr = 2S = ha$, i.e., $h < 3$. Contradiction.

5.30. Since the outer angle at vertex A of triangle ABA_1 is equal to 120° and $\angle A_1AB_1 = 60^\circ$, it follows that AB_1 is the bisector of this outer angle. Moreover, BB_1 is the bisector of the outer angle at vertex B, hence, A_1B_1 is the bisector of angle $\angle AA_1C$. Similarly, A_1C_1 is the bisector of angle $\angle AA_1B$. Hence,

$$\angle B_1A_1C_1 = \frac{\angle AA_1C + \angle AA_1B}{2} = 90^\circ.$$

5.31. Thanks to the solution of the preceding problem ray A_1C_1 is the bisector of angle $\angle AA_1B$. Let K be the intersection point of the bisectors of triangle A_1AB. Then

$$\angle C_1KO = \angle A_1KB = 90^\circ + \frac{\angle A}{2} = 120^\circ.$$

Hence, $\angle C_1KO + \angle C_1AO = 180^\circ$, i.e., quadrilateral $AOKC_1$ is an inscribed one. Hence, $\angle A_1C_1O = \angle KC_1O = \angle KAO = 30^\circ$.

5.32. a) Let S be the circumscribed circle of triangle ABC, let S_1 be the circle symmetric to S through line BC. The orthocenter H of triangle ABC lies on circle S_1 (Problem 5.9) and, therefore, it suffices to verify that the center O of circle S also belongs to S_1 and the bisector of the outer angle A passes through the center of circle S_1. Then $POAH$ is a rhombus, because $PO \parallel HA$.

Let PQ be the diameter of circle S perpendicular to line BC; let points P and A lie on one side of line BC. Then AQ is the bisector of angle A and AP is the bisector of the outer angle $\angle A$. Since $\angle BPC = 120^\circ = \angle BOC$, point P is the center of circle S_1 and point O belongs to circle S_1.

b) Let S be the circumscribed circle of triangle ABC and Q the intersection point of the bisector of angle $\angle BAC$ with circle S. It is easy to verify that Q is the center of circle S_1 symmetric to circle S through line BC. Moreover, points O and H lie on circle S_1 and since $\angle BIC = 120^\circ$ and $\angle BI_aC = 60^\circ$ (cf. Problem 5.3), it follows that II_a is a diameter of circle S_1. It is also clear that $\angle OQI = \angle QAH = \angle AQH$, because $OQ \parallel AH$ and $HA = QO = QH$. Hence, points O and H are symmetric through line II_a.

5.33. On side AC of triangle ABC, construct outwards an equilateral triangle AB_1C. Since $\angle A = 120^\circ$, point A lies on segment BB_1. Therefore, $BB_1 = b + c$ and, moreover, $BC = a$ and $B_1C = b$, i.e., triangle BB_1C is the desired one.

5.34. a) Let M_1 and N_1 be the midpoints of segments BH and CH, respectively; let BB_1 and CC_1 be heights. Right triangles ABB_1 and BHC_1 have a common acute angle — the one at vertex B; hence, $\angle C_1HB = \angle A = 60^\circ$. Since triangle BMH is an isosceles one, $\angle BHM = \angle HBM = 30^\circ$. Therefore, $\angle C_1HM = 60^\circ - 30^\circ = 30^\circ = \angle BHM$, i.e., point M lies on the bisector of angle $\angle C_1HB$. Similarly, point N lies on the bisector of angle $\angle B_1HC$.

b) Let us make use of the notations of the preceding problem and, moreover, let B' and C' be the midpoints of sides AC and AB. Since $AC_1 = AC\cos\angle A = \frac{1}{2}AC$, it follows that $C_1C' = \frac{1}{2}|AB - AC|$. Similarly, $B_1B' = \frac{1}{2}|AB - AC|$, i.e., $B_1B' = C_1C'$. It follows that the parallel lines BB_1 and $B'O$, CC_1 and $C'O$ form not just a parallelogram but a rhombus. Hence, its diagonal HO is the bisector of the angle at vertex H.

5.35. Since

$$\angle BB_1C = \angle B_1BA + \angle B_1AB > \angle B_1BA = \angle B_1BC,$$

it follows that $BC > B_1C$. Hence, point K symmetric to B_1 through bisector CC_1 lies on side BC and not on its extension. Since $\angle CC_1B = 30^\circ$, we have $\angle B_1C_1K = 60^\circ$ and, therefore, triangle B_1C_1K is an equilateral one. In triangles BC_1B_1 and BKB_1 side BB_1 is a common one and sides C_1B_1 and KB_1 are equal; the angles C_1BB_1 and KBB_1 are also equal but these angles are not the ones between equal sides. Therefore, the following two cases are possible:

1) $\angle BC_1B_1 = \angle BKB_1$. Then $\angle BB_1C_1 = \angle BB_1K = \frac{60^\circ}{2} = 30^\circ$. Therefore, if O is the intersection point of bisectors BB_1 and CC_1, then

$$\angle BOC = \angle B_1OC_1 = 180^\circ - \angle OC_1B_1 - \angle OB_1C_1 = 120^\circ.$$

On the other hand, $\angle BOC = 90^\circ + \frac{\angle A}{2}$ (cf. Problem 5.3), i.e., $\angle A = 60^\circ$.

2) $\angle BC_1B_1 + \angle BKB_1 = 180^\circ$. Then quadrilateral BC_1B_1K is an inscribed one and since triangle B_1C_1K is an equilateral one, $\angle B = 180^\circ - \angle C_1B_1K = 120^\circ$.

5.36. Let BM be a median, AK a bisector of triangle ABC and $BM \perp AK$. Line AK is a bisector and a height of triangle ABM, hence, $AM = AB$, i.e., $AC = 2AM = 2AB$. Therefore, $AB = 2$, $BC = 3$ and $AC = 4$.

5.37. Let a and b be legs and c the hypothenuse of the given triangle. If numbers a and b are odd, then the remainder after division of $a^2 + b^2$ by 4 is equal to 2 and $a^2 + b^2$ cannot be a perfect square. Hence, one of the numbers a and b is even and another one is odd; let, for definiteness, $a = 2p$. The numbers b and c are odd, hence, $c + b = 2q$ and $c - b = 2r$ for some q and r. Therefore, $4p^2 = a^2 = c^2 - b^2 = 4qr$. If d is a common divisor of q and r, then $a = 2\sqrt{qr}$, $b = q - r$ and $c = q + r$ are divisible by d. Therefore, q and r are relatively prime, ??? since $p^2 = qr$, it follows that $q = m^2$ and $r = n^2$. As a result we get $a = 2mn$, $b = m^2 - n^2$ and $c = m^2 + n^2$.

It is also easy to verify that if $a = 2mn$, $b = m^2 - n^2$ and $c = m^2 + n^2$, then $a^2 + b^2 = c^2$.

5.38. Let p be the semiperimeter of the triangle and a, b, c the lengths of the triangle's sides. By Heron's formula $S^2 = p(p-a)(p-b)(p-c)$. On the other hand, $S^2 = p^2r^2 = p^2$ since $r = 1$. Hence, $p = (p-a)(p-b)(p-c)$. Setting $x = p - a$, $y = p - b$, $z = p - c$ we rewrite our equation in the form

$$x + y + z = xyz.$$

Notice that p is either integer or half integer (i.e., of the form $\frac{2n+1}{2}$, where n is an integer) and, therefore, all the numbers x, y, z are simultaneously either integers or half integers. But if they are half integers, then $x + y + z$ is a half integer and xyz is of the form $\frac{m}{8}$, where m is an odd number. Therefore, numbers x, y, z are integers. Let, for definiteness, $x \leq y \leq z$. Then $xyz = x + y + z \leq 3z$, i.e., $xy \leq 3$. The following three cases are possible:

1) $x = 1$, $y = 1$. Then $2 + z = z$ which is impossible.

2) $x = 1$, $y = 2$. Then $3 + z = 2z$, i.e., $z = 3$.

3) $x = 1$, $y = 3$. Then $4 + z = 3z$, i.e., $z = 2 < y$ which is impossible.

Thus, $x = 1$, $y = 2$, $z = 3$. Therefore, $p = x + y + z = 6$ and $a = p - x = 5$, $b = 4$, $c = 3$.

5.39. Let a_1 and b_1, a_2 and b_2 be the legs of two distinct Pythagorean triangles, c_1 and c_2 their hypothenuses. Let us take two perpendicular lines and mark on them segments $OA = a_1a_2$, $OB = a_1b_2$, $OC = b_1b_2$ and $OD = a_2b_1$ (Fig. 57). Since $OA \cdot OC = OB \cdot OD$, quadrilateral $ABCD$ is an inscribed one. By Problem 2.71

$$4R^2 = OA^2 + OB^2 + OC^2 + OD^2 = (c_1c_2)^2,$$

i.e., $R = \frac{c_1c_2}{2}$. Magnifying, if necessary, quadrilateral $ABCD$ twice, we get the quadrilateral to be found.



Figure 57 (Sol. 5.39)

5.40. a) The lengths of hypothenuses of right triangles with legs 5 and 12, 9 and 12 are equal to 13 and 15, respectively. Identifying the equal legs of these triangles we get a triangle whose area is equal to $\frac{12(5+9)}{2} = 84$.

b) First, suppose that the length of the shortest side of the given triangle is an even number, i.e., the lengths of the sides of the triangle are equal to $2n$, $2n+1$, $2n+2$. Then by Heron's formula

$$16S^2 = (6n+3)(2n+3)(2n+1)(2n-1) = 4(3n^2+6n+2)(4n^2-1) + 4n^2 - 1.$$

We have obtained a contradiction since the number in the right-hand side is not divisible by 4. Consecutively, the lengths of the sides of the triangle are equal to $2n-1$, $2n$ and $2n+1$, where $S^2 = 3n^2(n^2-1)$. Hence, $S = nk$, where k is an integer and $k^2 = 3(n^2-1)$. It is also clear that k is the length of the height dropped to the side of length $2n$. This height divides the initial triangle into two right triangles with a common leg of length k and hypothenuses of length $2n+1$ and $2n-1$ the squares of the lengths of the other legs of these triangles are equal to

$$(2n \pm 1)^2 - k^2 = 4n^2 \pm 4n + 1 - 3n^2 + 3 = (n \pm 2)^2.$$

5.41. a) Since $AB^2 - AB_1^2 = BB_1^2 = BC^2 - (AC \pm AB_1)^2$, we see that $AB_1 = \pm\frac{AB^2+AC^2-BC^2}{2AC}$.

b) Let diagonals AC and BD meet at point O. Let us prove, for example, that the number $q = \frac{BO}{OD}$ is a rational one (then the number $OD = \frac{BD}{q+1}$ is also a rational one). In triangles ABC and ADC draw heights BB_1 and DD_1. By heading a) the numbers AB_1 and CD_1 — the lengths of the corresponding sides — are rational and, therefore, the number B_1D_1 is also rational.

Let E be the intersection point of line BB_1 and the line that passes through point D parallel to AC. In right triangle BDE, we have $ED = B_1D_1$ and the lengths of leg ED and hypothenuse BD are rational numbers; hence, BE^2 is also a rational number. From triangles ABB_1 and CDD_1 we derive that numbers BB_1^2 and DD_1^2 are rational. Since

$$BE^2 = (BB_1 + DD_1)^2 = BB_1^2 + DD_1^2 + 2BB_1 \cdot DD_1,$$

number $BB_1 \cdot DD_1$ is rational. It follows that the number

$$\frac{BO}{OD} = \frac{BB_1}{DD_1} = \frac{BB_1 \cdot DD_1}{DD_1^2}$$

is a rational one.

5.42. Triangles ABC and $A_1B_1C_1$ cannot have two pairs of corresponding angles whose sum is equal to 180° since otherwise their sum would be equal to 360° and the third angles of these triangles should be equal to zero. Now, suppose that the angles of the first triangle are equal to α, β and γ and the angles of the second one are equal to $180^\circ - \alpha$, β and γ. The sum of the angles of the two triangles is equal to 360°, hence, $180^\circ + 2\beta + 2\gamma = 360^\circ$, i.e., $\beta + \gamma = 90^\circ$. It follows that $\alpha = 90^\circ = 180^\circ - \alpha$.

5.43. Clearly, $\overrightarrow{A_1C} = \overrightarrow{BO}$ and $\overrightarrow{CB_1} = \overrightarrow{OA}$, hence, $\overrightarrow{A_1B_1} = \overrightarrow{BA}$. Similarly, $\overrightarrow{B_1C_1} = \overrightarrow{CB}$ and $\overrightarrow{C_1A_1} = \overrightarrow{AC}$, i.e., $\triangle ABC = \triangle A_1B_1C_1$. Moreover, ABA_1B_1 and ACA_1C_1 are parallelograms. It follows that segments BB_1 and CC_1 pass through the midpoint of segment AA_1.

5.44. Since $\angle MAO = \angle PAO = \angle AOM$, it follows that $AMOP$ is a rhombus. Similarly, $BNOQ$ is a rhombus. It follows that

$$MN = MO + ON = AM + BN \quad \text{and} \quad OP + PQ + QO = AP + PQ + QB = AB.$$

5.45. a) Through vertices of triangle ABC let us draw lines parallel to the triangle's opposite sides. As a result we get triangle $A_1B_1C_1$; the midpoints of the sides of the new triangle are points A, B and C. The heights of triangle ABC are the midperpendiculars to the sides of triangle $A_1B_1C_1$ and, therefore, the center of the circumscribed circle of triangle $A_1B_1C_1$ is the intersection point of heights of triangle ABC.

b) Point H is the center of the circumscribed circle of triangle $A_1B_1C_1$, hence,

$$4R^2 = B_1H^2 = B_1A^2 + AH^2 = BC^2 + AH^2.$$

Therefore,

$$AH^2 = 4R^2 - BC^2 = \left(\frac{1}{\sin^2\alpha} - 1\right) BC^2 = (BC\cot\alpha)^2.$$

5.46. Let AD be the bisector of an equilateral triangle ABC with base AB and angle 36° at vertex C. Then triangle ACD is an isosceles one and $\triangle ABC \sim \triangle BDA$. Therefore, $CD = AD = AB = 2xBC$ and $DB = 2xAB = 4x^2BC$; hence,

$$BC = CD + DB = (2x + 4x^2)BC.$$

5.47. Let B_1 and B_2 be the projections of point A to bisectors of the inner and outer angles at vertex B; let M the midpoint of side AB. Since the bisectors of the inner and outer angles are perpendicular, it follows that AB_1BB_2 is a rectangular and its diagonal B_1B_2 passes through point M. Moreover,

$$\angle B_1MB = 180^\circ - 2\angle MBB_1 = 180^\circ - \angle B.$$

Hence, $B_1B_2 \parallel BC$ and, therefore, line B_1B_2 coincides with line l that connects the midpoints of sides AB and AC.

We similarly prove that the projections of point A to the bisectors of angles at vertex C lie on line l.

5.48. Suppose that the bisectors of angles A and B are equal but $a > b$. Then $\cos\frac{1}{2}\angle A < \cos\frac{1}{2}\angle B$ and $\frac{1}{c} + \frac{1}{b} > \frac{1}{c} + \frac{1}{a}$, i.e., $\frac{bc}{b+c} < \frac{ac}{a+c}$. By multiplying these inequalities we get a contradiction, since $l_a = \frac{2bc\cos\frac{\angle A}{2}}{b+c}$ and $l_b = \frac{2ac\cos\frac{\angle B}{2}}{a+c}$ (cf. Problem 4.47).

5.49. a) By Problem 4.47 the length of the bisector of angle $\angle B$ of triangle ABC is equal to $\frac{2ac\cos\frac{\angle B}{2}}{a+c}$ and, therefore, it suffices to verify that the system of equations

$$\frac{ac}{a+c} = p, \quad a^2 + c^2 - 2ac\cos\angle B = q$$

has (up to a transposition of a with c) a unique positive solution. Let $a+c=u$. Then $ac=pu$ and $q=u^2-2pu(1+\cos\beta)$. The product of the roots of this quadratic equation for u is equal to $-q$ and, therefore, it has one positive root. Clearly, the system of equations

$$a+c=u, \quad ac=pu$$

has a unique solution.

b) In triangles AA_1B and CC_1B, sides AA_1 and CC_1 are equal; the angles at vertex B are equal, and the bisectors of the angles at vertex B are also equal. Therefore, these triangles are equal and either $AB=BC$ or $AB=BC_1$. The second equality cannot take place.

5.50. Let points M and N lie on sides AB and AC. If r_1 is the radius of the circle whose center lies on segment MN and which is tangent to sides AB and AC, then $S_{AMN}=qr_1$, where $q=\frac{AM+AN}{2}$. Line MN passes through the center of the inscribed circle if and only if $r_1=r$, i.e., $\frac{S_{AMN}}{q}=\frac{S_{ABC}}{p}=\frac{S_{BCNM}}{p-q}$.

5.51. a) On the extension of segment AC beyond point C take a point B' such that $CB'=CB$. Triangle BCB' is an isosceles one; hence, $\angle AEB=\angle ACB=2\angle CBB'$ and, therefore, E is the center of the circumscribed circle of triangle ABB'. It follows that point F divides segment AB' in halves; hence, line C_1F divides the perimeter of triangle ABC in halves.

b) It is easy to verify that the line drawn through point C parallel to BB' is the bisector of angle ACB. Since $C_1F\parallel BB'$, line C_1F is the bisector of the angle of the triangle with vertices at the midpoints of triangle ABC. The bisectors of this new triangle meet at one point.

5.52. Let X be the intersection point of lines AD_2 and CD_1; let M, E_1 and E_2 be the projections of points X, D_1 and D_2, respectively, to line AC. Then $CE_2=CD_2\sin\gamma=a\sin\gamma$ and $AE_1=c\sin\alpha$. Since $a\sin\gamma=c\sin\alpha$, it follows that $CE_2=AE_1=q$. Hence,

$$\frac{XM}{AM}=\frac{D_2E_2}{AE_2}=\frac{a\cos\gamma}{b+q} \quad \text{and} \quad \frac{XM}{CM}=\frac{c\cos\alpha}{b+q}.$$

Therefore, $AM:CM=c\cos\alpha:a\cos\gamma$. Height BH divides side AC in the same ratio.

5.53. a) By the law of cosines

$$B_1C_1^2=AC_1^2+AB_1^2-2AC_1\cdot AB_1\cdot\cos(90^\circ+\alpha),$$

i.e.,

$$a_1^2=\frac{c^2}{2}+\frac{b^2}{2}+bc\sin\alpha=\frac{b^2+c^2}{2}+2S.$$

Writing similar equalities for b_1^2 and c_1^2 and taking their sum we get the statement desired.

b) For an acute triangle ABC, add to S the areas of triangles ABC_1, AB_1C and A_1BC; add to S_1 the areas of triangles AB_1C_1, A_1BC_1 and A_1B_1C. We get equal quantities (for a triangle with an obtuse angle $\angle A$ the area of triangle AB_1C_1 should be taken with a minus sign). Hence,

$$S_1=S+\frac{a^2+b^2+c^2}{4}-\frac{ab\cos\gamma+ac\cos\beta+bc\cos\alpha}{4}.$$

It remains to notice that

$$ab\cos\gamma+bc\cos\alpha+ac\cos\beta=2S(\cot\gamma+\cot\alpha+\cot\beta)=\frac{a^2+b^2+c^2}{2};$$

cf. Problem 12.44 a).

5.54. First, let us prove that point B' lies on the circumscribed circle of triangle AHC, where H is the intersection point of heights of triangle ABC. We have

$$\angle(AB', B'C) = \angle(AA_1, CC_1) = \\ \angle(AA_1, BC) + \angle(BC, AB) + \angle(AB, CC_1) = \angle(BC, AB).$$

But as follows from the solution of Problem 5.9 $\angle(BC, AB) = \angle(AH, HC)$ and, therefore, points A, B', H and C lie on one circle and this circle is symmetric to the circumscribed circle of triangle ABC through line AC. Hence, both these circles have the same radius, R, consequently,

$$B'H = 2R\sin B'AH = 2R\cos\alpha.$$

Similarly, $A'H = 2R\cos\alpha = C'H$. This completes solution of heading a); to solve heading b) it remains to notice that $\triangle A'B'C' \sim \triangle ABC$ since after triangle $A'B'C'$ is rotated through an angle of α its sides become parallel to the sides of triangle ABC.

5.55. Let $a_1 = BA_1$, $a_2 = A_1C$, $b_1 = CB_1$, $b_2 = B_1A$, $c_1 = AC_1$ and $c_2 = C_1B$. The products of the lengths of segments of intersecting lines that pass through one point are equal and, therefore, $a_1(a_1 + x) = c_2(c_2 - z)$, i.e.,

$$a_1x + c_2z = c_2^2 - a_1^2.$$

We similarly get two more equations for x, y and z:

$$b_1y + a_2x = a_2^2 - b_1^2 \quad \text{and} \quad c_1z + b_2y = b_2^2 - c_1^2.$$

Let us multiply the first equation by b^{2n}; multiply the second and the third ones by c^{2n} and a^{2n}, respectively, and add the equations obtained. Since, for instance, $c_2b^n - c_1a^n = 0$ by the hypothesis, we get zero in the right-hand side. The coefficient of, say, x in the left-hand side is equal to

$$a_1b^{2n} + a_2c^{2n} = \frac{ac^nb^{2n} + ab^nc^{2n}}{b^n + c^n} = ab^nc^n.$$

Hence,

$$ab^nc^nx + ba^nc^ny + ca^nb^nz = 0.$$

Dividing both sides of this equation by $(abc)^n$ we get the statement desired.

5.56. Let in the initial triangle $\angle A = 3\alpha$, $\angle B = 3\beta$ and $\angle C = 3\gamma$. Let us take an equilateral triangle $A_2B_2C_2$ and construct on its sides as on bases isosceles triangles A_2B_2R, B_2C_2P and C_2A_2Q with angles at the bases equal to $60^\circ - \gamma$, $60^\circ - \alpha$, $60^\circ - \beta$, respectively (Fig. 58).

Let us extend the lateral sides of these triangles beyond points A_2, B_2 and C_2; denote the intersection point of the extensions of sides RB_2 and QC_2 by A_3, that of PC_2 and RA_2 by B_3, that of QA_2 and PB_2 by C_3.Through point B_2 draw the line parallel to A_2C_2 and denote by M and N the its intersection points with lines QA_3 and QC_3, respectively. Clearly, B_2 is the midpoint of segment MN. Let us compute the angles of triangles B_2C_3N and B_2A_3M:

$$\angle C_3B_2N = \angle PB_2M = \angle C_2B_2M = \angle C_2B_2P = \alpha; \\ \angle B_2NC_3 = 180^\circ - \angle C_2A_2Q = 120^\circ + \beta;$$

hence, $\angle B_2C_3N = 180^\circ - \alpha - (120^\circ + \beta) = \gamma$. Similarly, $\angle A_3B_2M = \gamma$ and $\angle B_2A_3M = \alpha$. Hence, $\triangle B_2C_3N \sim \triangle A_3B_2M$. It follows that $C_3B_2 : B_2A_3 = C_3N : B_2M$ and since $B_2M = B_2N$ and $\angle C_3B_2A_3 = \angle C_3NB_2$, it follows that $C_3B_2 : B_2A_3 = C_3N : NB_2$ and $\triangle C_3B_2A_3 \sim \triangle C_3NB_2$; hence, $\angle B_2C_3A_3 = \gamma$.



Figure 58 (Sol. 5.56)

Similarly, $\angle A_2C_3B_3 = \gamma$ and, therefore, $\angle A_3C_3B_3 = 3\gamma = \angle C$ and C_3B_3, C_3A_2 are the trisectors of angle C_3 of triangle $A_3B_3C_3$. Similar arguments for vertices A_3 and B_3 show that $\triangle ABC \sim \triangle A_3B_3C_3$ and the intersection points of the trisectors of triangle $A_3B_3C_3$ are vertices of an equilateral triangle $A_2B_2C_2$.

5.57. Point A_1 lies on the bisector of angle $\angle BAC$, hence, point A lies on the extension of the bisector of angle $\angle B_2A_1C_2$. Moreover, $\angle B_2AC_2 = \alpha = \frac{180^\circ - \angle B_2A_1C_2}{2}$. Hence, A is the center of an escribed circle of triangle $B_2A_1C_2$ (cf. Problem 5.3). Let D be the intersection point of lines AB and CB_2. Then

$$\angle AB_2C_2 = \angle AB_2D = 180^\circ - \angle B_2AD - \angle ADB_2 = 180^\circ - \gamma - (60^\circ + \alpha) = 60^\circ + \beta.$$

Since

$$\angle AB_2C = 180^\circ - (\alpha + \beta) - (\beta + \gamma) = 120^\circ - \beta,$$

it follows that

$$\angle CB_2C_2 = \angle AB_2C - \angle AB_2C_2 = 60^\circ - 2\beta.$$

Similarly, $\angle AB_2A_2 = 60^\circ - 2\beta$. Hence,

$$\angle A_2B_2C_2 = \angle AB_2C - \angle AB_2A_2 - \angle CB_2C_2 = 3\beta.$$

Similarly, $\angle B_2A_2C_2 = 3\alpha$ and $\angle A_2C_2B_2 = 3\gamma$.

5.58. Let the projection to a line perpendicular to line A_1B_1 send points A, B and C to A', B' and C', respectively; point C_1 to Q and points A_1 and B_1 into one point, P. Since

$$\frac{\overline{A_1B}}{\overline{A_1C}} = \frac{\overline{PB'}}{\overline{PC'}}, \quad \frac{\overline{B_1C}}{\overline{B_1A}} = \frac{\overline{PC'}}{\overline{PA'}} \quad \text{and} \quad \frac{\overline{C_1A}}{\overline{C_1B}} = \frac{\overline{QA'}}{\overline{QB'}},$$

it follows that

$$\frac{\overline{A_1B}}{\overline{A_1C}} \cdot \frac{\overline{B_1C}}{\overline{B_1A}} \cdot \frac{\overline{C_1A}}{\overline{C_1B}} = \frac{\overline{PB'}}{\overline{PC'}} \cdot \frac{\overline{PC'}}{\overline{PA'}} \cdot \frac{\overline{QA'}}{\overline{QB'}} = \frac{\overline{PB'}}{\overline{PA'}} \cdot \frac{\overline{QA'}}{\overline{QB'}} = \frac{b'}{a'} \cdot \frac{a'+x}{b'+x},$$

where $|x| = PQ$. The equality $\frac{b'}{a'} \cdot \frac{a'+x}{b'+x} = 1$ is equivalent to the fact that $x = 0$. (We have to take into account that $a' \neq b'$ since $A' \neq B'$.) But the equality $x = 0$ means that $P = Q$, i.e., point C_1 lies on line A_1B_1.

5.59. Let point P lie on arc $\smile BC$ of the circumscribed circle of triangle ABC. Then

$$\frac{\overline{BA_1}}{\overline{CA_1}} = -\frac{BP\cos\angle PBC}{CP\cos\angle PCB}, \quad \frac{\overline{CB_1}}{\overline{AB_1}} = -\frac{CP\cos\angle PCA}{AP\cos PAC}, \quad \frac{\overline{AC_1}}{\overline{BC_1}} = -\frac{AP\cos\angle PAB}{PB\cos\angle PBA}.$$

By multiplying these equalities and taking into account that

$$\angle PAC = \angle PBC, \quad \angle PAB = \angle PCB \quad \text{and} \quad \angle PAC + \angle PBA = 180^\circ$$

we get

$$\frac{\overline{BA_1}}{\overline{CA_1}} \cdot \frac{\overline{CB_1}}{\overline{AB_1}} \cdot \frac{\overline{AC_1}}{\overline{BC_1}} = 1.$$

5.60. Let O, O_1 and O_2 be the centers of circles S, S_1 and S_2; let X be the intersection point of lines O_1O_2 and A_1A_2. By applying Menelaus's theorem to triangle OO_1O_2 and points A_1, A_2 and X we get

$$\frac{O_1X}{O_2X} \cdot \frac{O_2A_2}{OA_2} \cdot \frac{OA_1}{O_1A_1} = 1$$

and, therefore, $O_1X : O_2X = R_1 : R_2$, where R_1 and R_2 are the radii of circles S_1 and S_2, respectively. It follows that X is the intersection point of the common outer or common inner tangents to circles S_1 and S_2.

5.61. a) Let, for definiteness, $\angle B < \angle C$. Then $\angle DAE = \angle ADE = \angle B + \frac{\angle A}{2}$; hence, $\angle CAE = \angle B$. Since

$$\frac{BE}{AB} = \frac{\sin \angle BAE}{\sin \angle AEB} \quad \text{and} \quad \frac{AC}{CE} = \frac{\sin \angle AEC}{\sin \angle CAE},$$

it follows that

$$\frac{BE}{CE} = \frac{c \sin \angle BAE}{b \sin \angle CAE} = \frac{c \sin(\angle A + \angle B)}{b \sin \angle B} = \frac{c \sin \angle C}{b \sin \angle B} = \frac{c^2}{b^2}.$$

b) In heading a) point E lies on the extension of side BC since $\angle ADC = \angle BAD + \angle B > \angle CAD$. Therefore, making use of the result of heading a) and Menelaus's theorem we get the statement desired.

5.62. Since $\angle BCE = 90^\circ - \frac{\angle B}{2}$, we have: $\angle BCE = \angle BEC$ and, therefore, $BE = BC$. Hence,

$$CF : KF = BE : BK = BC : BK \quad \text{and} \quad AE : KE = CA : CK = BC : BK.$$

Let line EF intersect AC at point D. By Menelaus's theorem $\frac{AD}{CD} \cdot \frac{CF}{KF} \cdot \frac{KE}{AE} = 1$. Taking into account that $CF : KF = AE : KE$ we get the statement desired.

5.63. Proof is similar to that of Problem 5.79; we only have to consider the ratio of *oriented* segments and angles.

5.64. Let A_2, B_2 and C_2 be the intersection points of lines BC with B_1C_1, AC with A_1C_1, AB with A_1B_1, respectively. Let us apply Menelaus's theorem to the following triangles and points on their sides: OAB and (A_1, B_1, C_2), OBC and (B_1, C_1, A_2), OAC and (A_1, C_1, B_2). Then

$$\frac{\overline{AA_1}}{\overline{OA_1}} \cdot \frac{\overline{OB_1}}{\overline{BB_1}} \cdot \frac{\overline{BC_2}}{\overline{AC_2}} = 1, \quad \frac{\overline{OC_1}}{\overline{CC_1}} \cdot \frac{\overline{BB_1}}{\overline{OB_1}} \cdot \frac{\overline{CA_2}}{\overline{BA_2}} = 1, \quad \frac{\overline{OA_1}}{\overline{AA_1}} \cdot \frac{\overline{CC_1}}{\overline{OC_1}} \cdot \frac{\overline{AB_2}}{\overline{CB_2}} = 1.$$

By multiplying these equalities we get

$$\frac{\overline{BC_2}}{\overline{AC_2}} \cdot \frac{\overline{AB_2}}{\overline{CB_2}} \cdot \frac{\overline{CA_2}}{\overline{BA_2}} = 1.$$

Menelaus's theorem implies that points A_2, B_2, C_2 lie on one line.

5.65. Let us consider triangle $A_0B_0C_0$ formed by lines A_1B_2, B_1C_2 and C_1A_2 (here A_0 is the intersection point of lines A_1B_2 and A_2C_1, etc), and apply Menelaus's theorem to this triangle and the following five triples of points:

$$(A, B_2, C_1), \ (B, C_2, A_1), \ (C, A_2, B_1), \ (A_1, B_1, C_1) \text{ and } \ (A_2, B_2, C_2).$$

As a result we get

$$\frac{\overline{B_0A}}{\overline{C_0A}}\cdot\frac{\overline{A_0B_2}}{\overline{B_0B_2}}\cdot\frac{\overline{C_0C_1}}{\overline{A_0C_1}}=1,\quad \frac{\overline{C_0B}}{\overline{A_0B}}\cdot\frac{\overline{B_0C_2}}{\overline{C_0C_2}}\cdot\frac{\overline{A_0A_1}}{\overline{B_0A_1}}=1,$$

$$\frac{\overline{A_0C}}{\overline{B_0C}}\cdot\frac{\overline{C_0A_2}}{\overline{A_0A_2}}\cdot\frac{\overline{B_0B_1}}{\overline{C_0B_1}}=1,\quad \frac{\overline{B_0A_1}}{\overline{A_0A_1}}\cdot\frac{\overline{C_0B_1}}{\overline{B_0B_1}}\cdot\frac{\overline{A_0C_1}}{\overline{C_0C_1}}=1, \tag{2}$$

$$\frac{\overline{A_0A_2}}{\overline{C_0A_2}}\cdot\frac{\overline{B_0B_2}}{\overline{A_0B_2}}\cdot\frac{\overline{C_0C_2}}{\overline{B_0C_2}}=1. \tag{3}$$

By multiplying these equalities we get $\frac{\overline{B_0A}}{\overline{C_0A}}\cdot\frac{\overline{C_0B}}{\overline{A_0B}}\cdot\frac{\overline{A_0C}}{\overline{B_0C}}=1$ and, therefore, points A, B and C lie on one line.

5.66. Let N be the intersection point of lines AD and KQ, P' the intersection point of lines KL and MN. By Desargue's theorem applied to triangles KBL and NDM we derive that P', A and C lie on one line. Hence, $P'=P$.

5.67. It suffices to apply Desargues's theorem to triangles AED and BFC and Pappus' theorem to triples of points (B,E,C) and (A,F,D).

5.68. a) Let R be the intersection point of lines KL and MN. By applying Pappus' theorem to triples of points (P,L,N) and (Q,M,K), we deduce that points A, C and R lie on one line.

b) By applying Desargues's theorem to triangles NDM and LBK we see that the intersection points of lines ND with LB, DM with BK, and NM with LK lie on one line.

5.69. Let us make use of the result of Problem 5.68 a). For points P and Q take points P_2 and P_4, for points A and C take points C_1 and P_1 and for K, L, M and N take points P_5, A_1, B_1 and P_3, respectively. As a result we see that line P_6C_1 passes through point P_1.

5.70. a) This problem is a reformulation of Problem 5.58 since the number $\overline{BA_1}:\overline{CA_1}$ is negative if point A_1 lies on segment BC and positive otherwise.

b) First, suppose that lines AA_1, BB_1 and CC_1 meet at point M. Any three (nonzero) vectors in plane are linearly dependent, i.e., there exist numbers λ, μ and ν (not all equal to zero) such that $\lambda\overrightarrow{AM}+\mu\overrightarrow{BM}+\nu\overrightarrow{CM}=0$. Let us consider the projection to line BC parallel to line AM. This projection sends points A and M to A_1 and points B and C into themselves. Therefore, $\mu\overrightarrow{BA_1}+\nu\overrightarrow{CA_1}=0$, i.e.,

$$\frac{\overline{BA_1}}{\overline{CA_1}}=-\frac{\nu}{\mu}.$$

Similarly,

$$\frac{\overline{CB_1}}{\overline{AB_1}}=-\frac{\lambda}{\nu}\quad\text{and}\quad\frac{\overline{AC_1}}{\overline{BC_1}}=-\frac{\mu}{\lambda}.$$

By multiplying these three equalities we get the statement desired.

If lines AA_1, BB_1 and CC_1 are parallel, in order to get the proof it suffices to notice that

$$\frac{\overline{BA_1}}{\overline{CA_1}}=\frac{\overline{BA}}{\overline{C_1A}}\quad\text{and}\quad\frac{\overline{CB_1}}{\overline{AB_1}}=\frac{\overline{C_1B}}{\overline{AB}}.$$

Now, suppose that the indicated relation holds and prove that then lines AA_1, BB_1 and CC_1 intersect at one point. Let C_1^* be the intersection point of line AB with the line that passes through point C and the intersection point of lines AA_1 and BB_1. For point C_1^* the same relation as for point C_1 holds. Therefore, $C_1^*A:C_1^*B=C_1A:C_1B$. Hence, $C_1^*=C_1$, i.e., lines AA_1, BB_1 and CC_1 meet at one point.

It is also possible to verify that if the indicated relation holds and two of the lines AA_1, BB_1 and CC_1 are parallel, then the third line is also parallel to them.

5.71. Clearly, $AB_1 = AC_1$, $BA_1 = BC_1$ and $CA_1 = CB_1$, and, in the case of the inscribed circle, on sides of triangle ABC, there are three points and in the case of an escribed circle there is just one point on sides of triangle ABC. It remains to make use of Ceva's theorem.

5.72. Let AA_1, BB_1 and CC_1 be heights of triangle ABC. Then

$$\frac{AC_1}{C_1B}\cdot\frac{BA_1}{A_1C}\cdot\frac{CB_1}{B_1A}=\frac{b\cos\angle A}{a\cos\angle B}\cdot\frac{c\cos\angle B}{b\cos\angle C}\cdot\frac{a\cos\angle C}{c\cos\angle A}=1.$$

5.73. Let A_2, B_2 and C_2 be the midpoints of sides BC, CA and AB. The considered lines pass through the vertices of triangle $A_2B_2C_2$ and in heading a) they divide its sides in the same ratios in which lines AP, BP and CP divide sides of triangle ABC whereas in heading b) they divide them in the inverse ratios. It remains to make use of Ceva's theorem.

5.74. Since $\triangle AC_1B_2 \sim \triangle BC_1A_1$ and $\triangle AB_1C_2 \sim \triangle CB_1A_1$, it follows that $AB_2\cdot C_1B = AC_1\cdot BA_1$ and $AC_2\cdot CB_1 = A_1C\cdot B_1A$. Hence,

$$\frac{AB_2}{AC_2}=\frac{AC_1}{C_1B}\cdot\frac{BA_1}{A_1C}\cdot\frac{CB_1}{B_1A}=1.$$

5.75. Let lines AA_1, BB_1 and CC_1 intersect lines BC, CA and AB at points A_1, B_2 and C_2.

a) If $\angle B+\beta<180^\circ$ and $\angle C+\gamma<180^\circ$, then

$$\frac{BA_2}{A_2C}=\frac{S_{ABA_1}}{S_{ACA_1}}=\frac{AB\cdot BA_1\sin(\angle B+\beta)}{AC\cdot CA_1\sin(\angle C+\gamma)}=\frac{AB}{AC}\cdot\frac{\sin\gamma}{\sin\beta}\cdot\frac{\sin(\angle B+\beta)}{\sin(\angle C+\gamma)}.$$

The latter expression is equal to $\overline{BA_2}:\overline{A_2C}$ in all the cases. Let us write similar expressions for $\overline{CB_2}:\overline{B_2A}$ and $\overline{AC_2}:\overline{C_2B}$ and multiply them. Now it remains to make use of Ceva's theorem.

b) Point A_2 lies outside segment BC only if precisely one of the angles β and γ is greater than the corresponding angle $\angle B$ or $\angle C$. Hence,

$$\frac{\overline{BA_2}}{\overline{A_2C}}=\frac{AB}{AC}\cdot\frac{\sin\gamma}{\sin\beta}\cdot\frac{\sin(\angle B-\beta)}{\sin(\angle C-\gamma)}.$$

5.76. It is easy to verify that this problem is a particular case of Problem 5.75.

Remark. A similar statement is also true for an escribed circle.

5.77. The solution of the problem obviously follows from Ceva's theorem.

5.78. By applying the sine theorem to triangles ACC_1 and BCC_1 we get

$$\frac{AC_1}{C_1C}=\frac{\sin\angle ACC_1}{\sin\angle A}\quad\text{and}\quad\frac{CC_1}{C_1B}=\frac{\sin\angle B}{\sin\angle C_1CB},$$

i.e.,

$$\frac{AC_1}{C_1B}=\frac{\sin\angle ACC_1}{\sin\angle C_1CB}\cdot\frac{\sin\angle B}{\sin\angle A}.$$

Similarly,

$$\frac{BA_1}{A_1C}=\frac{\sin\angle BAA_1}{\sin\angle A_1AC}\cdot\frac{\sin\angle C}{\sin\angle B}\quad\text{and}\quad\frac{CB_1}{B_1A}=\frac{\sin\angle CBB_1}{\sin\angle B_1BA}\cdot\frac{\sin\angle A}{\sin\angle C}.$$

To complete the proof it remains to multiply these equalities.

Remark. A similar statement is true for the ratios of oriented segments and angles in the case when the points are taken on the extensions of sides.

5.79. We may assume that points A_2, B_2 and C_2 lie on the sides of triangle ABC. By Problem 5.78

$$\frac{AC_2}{C_2B}\cdot\frac{BA_2}{A_2C}\cdot\frac{CB_2}{B_2A}=\frac{\sin\angle ACC_2}{\sin\angle C_2CB}\cdot\frac{\sin\angle BAA_2}{\sin\angle A_2AC}\cdot\frac{\sin\angle CBB_2}{\sin\angle B_2BA}.$$

Since lines AA_2, BB_2 and CC_2 are symmetric to lines AA_1, BB_1 and CC_1, respectively, through the bisectors, it follows that $\angle ACC_2=\angle C_1CB$, $\angle C_2CB=\angle ACC_1$ etc., hence,

$$\frac{\sin\angle ACC_2}{\sin\angle C_2CB}\cdot\frac{\sin\angle BAA_2}{\sin\angle A_2AC}\cdot\frac{\sin\angle CBB_2}{\sin\angle B_2BA}=\frac{\sin\angle C_1CB}{\sin\angle ACC_1}\cdot\frac{\sin\angle A_1AC}{\sin\angle BAA_1}\cdot\frac{\sin\angle B_1BA}{\sin\angle CBB_1}=\frac{C_1B}{AC_1}\cdot\frac{A_1C}{BA_1}\cdot\frac{B_1A}{CB_1}=1.$$

Therefore,

$$\frac{AC_2}{C_2B}\cdot\frac{BA_2}{A_2C}\cdot\frac{CB_2}{B_2A}=1,$$

i.e., lines AA_2, BB_2 and CC_2 meet at one point.

Remark. The statement holds also in the case when points A_1, B_1 and C_1 are taken on the extensions of sides if only point P does not lie on the circumscribed circle S of triangle ABC; if P does lie on S, then lines AA_2, BB_2 and CC_2 are parallel (cf. Problem 2.90).

5.80. Let diagonals AD and BE of the given hexagon $ABCDEF$ meet at point P; let K and L be the midpoints of sides AB and ED, respectively. Since $ABDE$ is a trapezoid, segment KL passes through point P (by Problem 19.2). By the law of sines

$$\sin\angle APK:\sin\angle AKP=AK:AP\quad\text{and}\quad\sin\angle BPK:\sin\angle BKP=BK:BP.$$

Since $\sin\angle AKP=\sin\angle BKP$ and $AK=BK$, we have

$$\sin\angle APK:\sin\angle BPK=BP:AP=BE:AD.$$

Similar relations can be also written for the segments that connect the midpoints of the other two pairs of the opposite sides. By multiplying these relations and applying the result of Problem 5.78 to the triangle formed by lines AD, BE and CF, we get the statement desired.

5.81. Let us consider the homothety with center P and coefficient 2. Since $PA_1A_3A_2$ is a rectangle, this homothety sends line A_1A_2 into line l_a that passes through point A_3; lines l_a and A_3P are symmetric through line A_3A. Line A_3A divides the angle $B_3A_3C_3$ in halves (Problem 1.56 a)).

We similarly prove that lines l_b and l_c are symmetric to lines B_3P and C_3P, respectively, through bisectors of triangle $A_3B_3C_3$. Therefore, lines l_a, l_b and l_c either meet at one point or are parallel (Problem 1.79) and, therefore, lines A_1A_2, B_1B_2 and C_1C_2 meet at one point.

5.82. By Problems 5.78 and 5.70 b)) we have

$$\frac{\sin\angle ASP}{\sin\angle PSD}\cdot\frac{\sin\angle DAP}{\sin\angle PAS}\cdot\frac{\sin\angle SDP}{\sin\angle PDA}=1=\frac{\sin\angle ASQ}{\sin\angle QSD}\cdot\frac{\sin\angle DAQ}{\sin\angle QAS}\cdot\frac{\sin\angle SDQ}{\sin\angle QDA}.$$

But

$$\angle DAP=\angle SDQ,\ \ \angle SDP=\angle DAQ,\ \ \angle PAS=\angle QDA\ \text{ and }\ \angle PDA=\angle QAS.$$

Hence,

$$\frac{\sin\angle ASP}{\sin\angle PSD}=\frac{\sin\angle ASQ}{\sin\angle QSD}.$$

This implies that points S, P and Q lie on one line, since the function $\frac{\sin(\alpha-x)}{\sin x}$ is monotonous with respect to x: indeed,

$$\frac{d}{dx}\left(\frac{\sin(\alpha-x)}{\sin x}\right)=-\frac{\sin\alpha}{\sin^2 x}.$$

5.83. a) By Ceva's theorem

$$\frac{AC_1}{C_1B}=\frac{CA_1}{A_1B}\cdot\frac{AB_1}{B_1C}$$

and by the law of sines

$$\begin{array}{rclrcl} CA_1 & = & \frac{CA\sin\angle CAA_1}{\sin\angle AA_1B}, & A_1B & = & \frac{AB\sin\angle BAA_1}{\sin\angle AA_1B},\\ AB_1 & = & \frac{AB\sin\angle ABB_1}{\sin\angle AB_1B}, & B_1C & = & \frac{BC\sin\angle CBB_1}{\sin\angle AB_1B}.\end{array}$$

Substituting the last four identities in the first identity and taking into account that $AC=BC$, we get the statement desired.

b) Let us denote the intersection points of lines CM and CN with base AB by M_1 and N_1, respectively. We have to prove that $M_1=N_1$. From heading a) it follows that $AM_1:M_1B=AN_1:N_1B$, i.e., $M_1=N_1$.

5.84. Let segments BM and BN meet side AC at points P and Q, respectively. Then

$$\frac{\sin\angle PBB_1}{\sin PBA}=\frac{\sin\angle PBB_1}{\sin\angle BPB_1}\cdot\frac{\sin\angle APB}{\sin\angle PBA}=\frac{PB}{BB_1}\cdot\frac{AB}{PA}.$$

If O is the intersection point of bisectors of triangle ABC, then $\frac{AP}{PB_1}\cdot\frac{B_1O}{OB}\cdot\frac{BC_1}{C_1A}=1$ and, therefore,

$$\frac{\sin\angle PBB_1}{\sin\angle PBA}=\frac{AB}{BB_1}\cdot\frac{B_1O}{OB}\cdot\frac{BC_1}{C_1A}.$$

Observe that $BC_1:C_1A=BC:CA$ and perform similar calculations for $\sin\angle QBB_1:\sin\angle QBC$; we deduce that

$$\frac{\sin\angle PBB_1}{\sin\angle PBA}=\frac{\sin\angle QBB_1}{\sin\angle QBC}.$$

Since $\angle ABB_1=\angle CBB_1$, we have: $\angle PBB_1=\angle QBB_1$.

5.85. a) Let point P lie on arc $\smile AC$ of the circumscribed circle of triangle ABC; let A_1, B_1 and C_1 be the bases of perpendiculars dropped from point P to lines BC, CA and AB. The sum of angles at vertices A_1 and C_1 of quadrilateral A_1BC_1P is equal to 180°, hence, $\angle A_1PC_1=180^\circ-\angle B=\angle APC$. Therefore, $\angle APC_1=\angle A_1PC$, where one of points A_1 and C_1 (say, A_1) lies on a side of the triangle and the other point lies on the extension of a side. Quadrilaterals AB_1PC_1 and A_1B_1PC are inscribed ones, hence,

$$\angle AB_1C_1=\angle APC_1=\angle A_1PC=\angle A_1B_1C$$

and, therefore, point B_1 lies on segment A_1C_1.

b) By the same arguments as in heading a) we get

$$\angle(AP,PC_1)=\angle(AB_1,B_1C)=\angle(CB_1,B_1A_1)=\angle(CP,PA_1).$$

Add $\angle(PC_1,PC)$ to $\angle(AP,PC_1)$; we get

$$\angle(AP,PC)=\angle(PC_1,PA_1)=\angle(BC_1,BA_1)=\angle(AB,BC),$$

i.e., point P lies on the circumscribed circle of triangle ABC.

5.86. Let A_1, B_1 and C_1 be the midpoints of segments PA, PB and PC, respectively; let O_a, O_b and O_c be the centers of the circumscribed circles of triangles BCP, ACP and ABP, respectively. Points A_1, B_1 and C_1 are the bases of perpendiculars dropped from point

P to sides of triangle $O_aO_bO_c$ (or their extensions). Points A_1, B_1 and C_1 lie on one line, hence, point P lies on the circumscribed circle of triangle $O_aO_cO_c$ (cf. Problem 5.85, b).

5.87. Let the extension of the bisector AD intersect the circumscribed circle of triangle ABC at point P. Let us drop from point P perpendiculars PA_1, PB_1 and PC_1 to lines BC, CA and AB, respectively; clearly, A_1 is the midpoint of segment BC. The homothety centered at A that sends P to D sends points B_1 and C_1 to B' and C' and, therefore, it sends point A_1 to M, because M(???) lies on line B_1C_1 and $PA_1 \parallel DM$.

5.88. a) The solution of Problem 5.85 can be adapted without changes to this case.

b) Let A_1 and B_1 be the bases of perpendiculars dropped from point P to lines BC and CA, respectively, and let points A_2 and B_2 from lines BC and AC, respectively, be such that $\angle(PA_2, BC) = \alpha = \angle(PB_2, AC)$. Then $\triangle PA_1A_2 \sim \triangle PB_1B_2$ hence, points A_1 and B_1 turn under a rotational homothety centered at P into A_2 and B_2 and $\angle A_1PA_2 = 90^\circ - \alpha$ is the angle of the rotation.

5.89. a) Let the angle between lines PC and AC be equal to φ. Then $PA = 2R\sin\varphi$. Since points A_1 and B_1 lie on the circle with diameter PC, the angle between lines PA_1 and A_1B_1 is also equal to φ. Hence, $PA_1 = \frac{d}{\sin\varphi}$ and, therefore, $PA \cdot PA_1 = 2Rd$.

b) Since $PA_1 \perp BC$, it follows that $\cos\alpha = \sin\varphi = \frac{d}{PA_1}$. It remains to notice that $PA_1 = \frac{2Rd}{PA}$.

5.90. Points A_1 and B_1 lie on the circle with diameter PC, hence, $A_1B_1 = PC\sin\angle A_1CB_1 = PC\sin\angle C$. Let the angle between lines AB and A_1B_1 be equal to γ and C_1 be the projection of point P to line A_1B_1. Lines A_1B_1 and B_1C_1 coincide, hence, $\cos\gamma = \frac{PC}{2R}$ (cf. Problem 5.89). Therefore, the length of the projection of segment AB to line A_1B_1 is equal to

$$AB\cos\gamma = \frac{(2R\sin\angle C)PC}{2R} = PC\sin\angle C.$$

5.91. Let A_1 and B_1 be the bases of perpendiculars dropped from point P to lines BC and AC. Points A_1 and B_1 lie on the circle with diameter PC. Since $\sin\angle A_1CB_1 = \sin\angle ACB$, the chords A_1B_1 of this circle are of the same length. Therefore, lines A_1B_1 are tangent to a fixed circle.

5.92. Let A_1 and B_1 be the bases of perpendiculars dropped from point P to lines BC and CA. Then

$$\angle(A_1B_1, PB_1) = \angle(A_1C, PC) = \frac{\smile BP}{2}.$$

It is also clear that for all points P lines PB_1 have the same direction.

5.93. Let P_1 and P_2 be diametrically opposite points of the circumscribed circle of triangle ABC; let A_i and B_i be the bases of perpendiculars dropped from point P_i to lines BC and AC, respectively; let M and N be the midpoints of sides AC and BC, respectively; let X be the intersection point of lines A_1B_1 and A_2B_2, respectively. By Problem 5.92 $A_1B_1 \perp A_2B_2$. It remains to verify that $\angle(MX, XN) = \angle(BC, AC)$. Since $AB_2 = B_1C$, it follows that XM is a median of right triangle B_1XB_2. Hence, $\angle(XM, XB_2) = \angle(XB_2, B_2M)$.

Similarly, $\angle(XA_1, XN) = \angle(A_1N, XA_1)$. Therefore,

$$\angle(MX, XN) = \angle(XM, XB_2) + \angle(XB_2, XA_1) + \angle(XA_1, XN) = \angle(XB_2, B_2M) + \angle(A_1N, XA_1) + 90^\circ.$$

Since

$$\angle(XB_2, B_2M) + \angle(AC, CB) + \angle(NA_1, A_1X) + 90^\circ = 0^\circ,$$

we have: $\angle(MN, XN) + \angle(AC, CB) = 0^\circ$.

5.94. If point R on the given circle is such that $\angle(\overrightarrow{OP}, \overrightarrow{OR}) = \frac{1}{2}(\beta+\gamma)$, then $OR \perp BC$. It remains to verify that $\angle(OR, OQ) = \angle(PA_1, A_1B_1)$. But $\angle(OR, OQ) = \frac{1}{2}\alpha$ and

$$\angle(PA_1, A_1B_1) = \angle(PB, BC_1) = \frac{\angle(\overrightarrow{OP}, \overrightarrow{OA})}{2} = \frac{\alpha}{2}.$$

5.95. Let lines AC and PQ meet at point M. In triangle MPC draw heights PB_1 and CA_1. Then A_1B_1 is Simson's line of point P with respect to triangle ABC. Moreover, by Problem 1.52 $\angle(MB_1, B_1A_1) = \angle(CP, PM)$. It is also clear that $\angle(CP, PM) = \angle(CA, AQ) = \angle(MB_1, AQ)$. Hence, $A_1B_1 \parallel AQ$.

5.96. Let us draw chord PQ perpendicular to BC. Let points H' and P' be symmetric to points H and P, respectively, through line BC; point H' lies on the circumscribed circle of triangle ABC (Problem 5.9). First, let us prove that $AQ \parallel P'H$. Indeed, $\angle(AH', AQ) = \angle(PH', PQ) = \angle(AH', P'H)$. Simson's line of point P is parallel to AQ (Problem 5.95), i.e., it passes through the midpoint of side PP' of triangle $PP'H$ and is parallel to side $P'H$; hence, it passes through the midpoint of side PH.

5.97. Let H_a, H_b, H_c and H_d be the orthocenters of triangles BCD, CDA, DAB and ABC, respectively. Lines l_a, l_b, l_c and l_d pass through the midpoints of segments AH_a, BH_b, CH_c and DH_d, respectively (cf. Problem 5.96). The midpoints of these segments coincide with point H such that $2\overrightarrow{OH} = \overrightarrow{OA} + \overrightarrow{OB} + \overrightarrow{OC} + \overrightarrow{OD}$, where O is the center of the circle (cf. Problem 13.33).

5.98. a) Let B_1, C_1 and D_1 be the projections of point P to lines AB, AC and AD, respectively. Points B_1, C_1 and D_1 lie on the circle with diameter AP. Lines B_1C_1, C_1D_1 and D_1B_1 are Simson's lines of point P with respect to triangles ABC, ACD and ADB, respectively. Therefore, projections of point P to Simson's lines of these triangles lie on one line — Simson's line of triangle $B_1C_1D_1$.

We similarly prove that any triple of considered points lies on one line.

b) Let P be a point of the circumscribed circle of n-gon $A_1 \dots A_n$; let B_2, B_3, $\dots$, B_n be the projections of point P to lines A_1A_2, $\dots$, A_1A_n, respectively. Points B_2, $\dots$, B_n lie on the circle with diameter A_1P.

Let us prove by induction that Simson's line of point P with respect to n-gon $A_1 \dots A_n$ coincides with Simson's line of point P with respect to $(n-1)$-gon $B_2 \dots B_n$ (for $n = 4$ this had been proved in heading a)). By the inductive hypothesis Simson's line of the $(n-1)$-gon $A_1A_3 \dots A_n$ coincides with Simson's line of $(n-2)$-gon $B_3 \dots B_n$. Hence, the projections of point P to Simson's line of $(n-1)$-gons whose vertices are obtained by consecutive deleting points $A_2, \dots, A_n$ from the collection $A_1, \dots, A_n$????? lie on Simson's line of the $(n-1)$-gon $B_2 \dots B_n$. The projection of point P to Simson's line of the $(n-1)$-gon $A_2 \dots A_n$ lies on the same line, because our arguments show that any $n-1$ of the considered n points of projections lie on one line.

5.99. Points B_1 and C_1 lie on the circle with diameter AP. Hence, $B_1C_1 = AP \sin \angle B_1AC_1 = AP\left(\frac{BC}{2R}\right)$.

5.100. This problem is a particular case of Problem 2.43.

5.101. Clearly,

$$\angle C_1AP = \angle C_1B_1P = \angle A_2B_1P = \angle A_2C_2P = \angle B_3C_2P = \angle B_3A_3P.$$

(The first, third and fifth equalities are obtained from the fact that the corresponding quadrilaterals are inscribed ones; the remaining equalities are obvious.) Similarly, $\angle B_1AP = \angle C_3A_3P$. Hence,

$$\angle B_3A_3C_3 = \angle B_3A_3P + \angle C_3A_3P = \angle C_1AP + \angle BAP = \angle BAC.$$

Similarly, the equalities of the remaining angles of triangles ABC and $A_3B_3C_3$ are similarly obtained.

5.102. Let A_1, B_1 and C_1 be the bases of perpendiculars dropped from point P to lines BC, CA and AB, respectively; let A_2, B_2 and C_2 be the intersection points of lines PA, PB and PC, respectively, with the circumscribed circle of triangle ABC. Further, let S, S_1 and S_2 be areas of triangles ABC, $A_1B_1C_1$ and $A_2B_2C_2$, respectively. It is easy to verify that $a_1 = \frac{a\cdot AP}{2R}$ (Problem 5.99) and $a_2 = \frac{a\cdot B_2P}{CP}$. Triangles $A_1B_1C_1$ and $A_2B_2C_2$ are similar (Problem 5.100); hence, $\frac{S_1}{S_2} = k^2$, where $k = \frac{a_1}{a_2} = \frac{AP\cdot CP}{2R\cdot B_2P}$. Since $B_2P \cdot BP = |d^2 - R^2|$, we have:

$$\frac{S_1}{S_2} = \frac{(AP\cdot BP\cdot CP)^2}{4R^2(d^2-R^2)^2}.$$

Triangles $A_2B_2C_2$ and ABC are inscribed in one circle, hence, $\frac{S_2}{S} = \frac{a_2b_2c_2}{abc}$ (cf. Problem 12.1). It is also clear that, for instance,

$$\frac{a_2}{a} = \frac{B_2P}{CP} = \frac{|d^2-R^2|}{BP\cdot CP}.$$

Therefore,

$$S_2 : S = |d^2-R^2|^3 : (AP\cdot BP\cdot CP)^2.$$

Hence,

$$\frac{S_1}{S} = \frac{S_1}{S_2}\cdot\frac{S_2}{S} = \frac{|d^2-R^2|}{4R^2}.$$

5.103. Points B_1 and C_1 lie on the circle with diameter PA and, therefore, the midpoint of segment PA is the center of the circumscribed circle of triangle AB_1C_1. Consequenly, l_a is the midperpendicular to segment B_1C_1. Hence, lines l_a, l_b and l_c pass through the center of the circumscribed circle of triangle $A_1B_1C_1$.

5.104. a) Let us drop from points P_1 and P_2 perpendiculars P_1B_1 and P_2B_2, respectively, to AC and perpendiculars P_1C_1 and P_2C_2 to AB. Let us prove that points B_1, B_2, C_1 and C_2 lie on one circle. Indeed,

$$\angle P_1B_1C_1 = \angle P_1AC_1 = \angle P_2AB_2 = \angle P_2C_2B_2;$$

and, since $\angle P_1B_1A = \angle P_2C_2A$, it follows that $\angle C_1B_1A = \angle B_2C_2A$. The center of the circle on which the indicated points lie is the intersection point of the midperpendiculars to segments B_1B_2 and C_1C_2; observe that both these perpendiculars pass through the midpoint O of segment P_1P_2, i.e., O is the center of this circle. In particular, points B_1 and C_1 are equidistant from point O. Similarly, points A_1 and B_1 are equidistant from point O, i.e., O is the center of the circumscribed circle of triangle $A_1B_1C_1$. Moreover, $OB_1 = OB_2$.

b) The preceding proof passes virtually without changes in this case as well.

5.105. Let A_1, B_1 and C_1 be the midpoints of sides BC, CA and AB. Triangles $A_1B_1C_1$ and ABC are similar and the similarity coefficient is equal to 2. The heights of triangle $A_1B_1C_1$ intersect at point O; hence, $OA_1 : HA = 1 : 2$. Let M' be the intersection point of segments OH and AA_1. Then $OM' : M'H = OA_1 : HA = 1 : 2$ and $AM' : M'A_1 = OA_1 : HA = 1 : 2$, i.e., $M' = M$.

5.106. Let A_1, B_1 and C_1 be the midpoints of sides BC, CA and AB, respectively; let A_2, B_2 and C_2 the bases of heights; A_3, B_3 and C_3 the midpoints of segments that connect the intersection point of heights with vertices. Since $A_2C_1 = C_1A = A_1B_1$ and $A_1A_2 \parallel B_1C_1$, point A_2 lies on the circumscribed circle of triangle $A_1B_1C_1$. Similarly, points B_2 and C_2 lie on the circumscribed circle of triangle $A_1B_1C_1$.

Now, consider circle S with diameter A_1A_3. Since $A_1B_3 \parallel CC_2$ and $A_3B_3 \parallel AB$, it follows that $\angle A_1B_3A_3 = 90^\circ$ and, therefore, point B_3 lies on S. We similarly prove that points C_1,

B_1 and C_3 lie on S. Circle S passes through the vertices of triangle $A_1B_1C_1$; hence, it is its circumscribed circle.

The homothety with center H and coefficient $\frac{1}{2}$ sends the circumscribed circle of triangle ABC into the circumscribed circle of triangle $A_3B_3C_3$, i.e., into the circle of 9 points. Therefore, this homothety sends point O into the center of the circle of nine points.

5.107. a) Let us prove that, for example, triangles ABC and HBC share the same circle of nine points. Indeed, the circles of nine points of these triangles pass through the midpoint of side BC and the midpoints of segments BH and CH.

b) Euler's line passes through the center of the circle of 9 points and these triangles share one circle of nine points.

c) The center of symmetry is the center of the circle of 9 points of these triangles.

5.108. Let $AB > BC > CA$. It is easy to verify that for an acute and an obtuse triangles the intersection point H of heights and the center O of the circumscribed circle are positioned precisely as on Fig. 59 (i.e., for an acute triangle point O lies inside triangle BHC_1 and for an acute triangle points O and B lie on one side of line CH).



Figure 59 (Sol. 5.108)

Therefore, in an acute triangle Euler's line intersects the longest side AB and the shortest side AC, whereas in an acute triangle it intersects the longest side AB, and side BC of intermediate length.

5.109. a) Let O_a, O_b and O_c be the centers of the escribed circles of triangle ABC. The vertices of triangle ABC are the bases of the heights of triangle $O_aO_bO_c$ (Problem 5.2) and, therefore, the circle of 9 points of triangle $O_aO_bO_c$ passes through point A, B and C.

b) Let O be the intersection point of heights of triangle $O_aO_bO_c$, i.e., the intersection point of the bisectors of triangle ABC. The circle of 9 points of triangle $O_aO_bO_c$ divides segment OO_a in halves.

5.110. Let AA_1 be an height, H the intersection point of heights. By Problem 5.45 b) $AH = 2R|\cos\angle A|$. The medians are divided by their intersection point in the ratio of 1:2, hence, Euler's line is parallel to BC if and only if $AH : AA_1 = 2 : 3$ and vectors $\overrightarrow{AH}$ and $\overrightarrow{AA_1}$ are codirected, i.e.,

$$2R\cos\angle A : 2R\sin\angle B\sin\angle C = 2 : 3.$$

Taking into account that

$$\cos\angle A = -\cos(\angle B + \angle C) = \sin\angle B\sin\angle C - \cos\angle B\cos\angle C$$

we get

$$\sin\angle B\sin\angle C = 3\cos\angle B\cos\angle C.$$

5.111. Let CD be a height, O the center of the circumscribed circle, N the midpoint of side AB and let point E divide the segment that connects C with the intersection point of the heights in halves. Then $CENO$ is a parallelogram, hence, $\angle NED = \angle OCH = |\angle A - \angle B|$ (cf. Problem 2.88). Points N, E and D lie on the circle of 9 points, hence, segment ND is seen from its center under an angle of $2\angle NED = 2|\angle A - \angle B|$.

5.112. Let O and I be the centers of the circumscribed and inscribed circles, respectively, of triangle ABC, let H be the intersection point of the heights; lines AI and BI intersect the circumscribed circle at points A_1 and B_1. Suppose that triangle ABC is not an isosceles one. Then $OI : IH = OA_1 : AH$ and $OI : IH = OB_1 : BH$. Since $OB_1 = OA_1$, we see that $AH = BH$ and, therefore, $AC = BC$. Contradiction.

5.113. Let O and I be the centers of the circumscribed and inscribed circles, respectively, of triangle ABC, H the orthocenter of triangle $A_1B_1C_1$. In triangle $A_1B_1C_1$, draw heights A_1A_2, B_1B_2 and C_1C_2. Triangle $A_1B_1C_1$ is an acute one (e.g., $\angle B_1A_1C_1 = \frac{\angle B+\angle C}{2} < 90^\circ$), hence, H is the center of the inscribed circle of triangle $A_2B_2C_2$ (cf. Problem 1.56, a). The corresponding sides of triangles ABC and $A_2B_2C_2$ are parallel (cf. Problem 1.54 a) and, therefore, there exists a homothety that sends triangle ABC to triangle $A_2B_2C_2$. This homothety sends point O to point I and point I to point H; hence, line IH passes through point O.

5.114. Let H be be the intersection point of the heights of triangle ABC, let E and M be the midpoints of segments CH and AB, see Fig. 60. Then C_1MC_2E is a rectangle.



Figure 60 (Sol. 5.114)

Let line CC_2 meet line AB at point C_3. Let us prove that $\overline{AC_3} : \overline{C_3B} = \tan 2\alpha : \tan 2\beta$. It is easy to verify that

$$\overline{C_3M} : \overline{C_2E} = \overline{MC_2} : \overline{EC}, \quad \overline{EC} = R\cos\gamma,$$
$$\overline{MC_2} = \overline{C_1E} = 2R\sin\alpha\sin\beta - R\cos\gamma$$
$$\text{and} \quad \overline{C_2E} = \overline{MC_1} = R\sin(\beta-\alpha)$$

Hence,

$$\overline{C_3M} = \frac{R\sin(\beta-\alpha)(2\sin\beta\sin\alpha - \cos\gamma)}{\cos\gamma} = \frac{R\sin(\beta-\alpha)\cos(\beta-\alpha)}{\cos\gamma}.$$

Therefore,

$$\frac{\overline{AC_3}}{\overline{C_3B}} = \frac{\overline{AM}+\overline{MC_3}}{\overline{C_3M}+\overline{MB}} = \frac{\sin 2\gamma + \sin 2(\alpha-\beta)}{\sin 2\gamma - \sin 2(\alpha-\beta)} = \frac{\tan 2\alpha}{\tan 2\beta}.$$

Similar arguments show that

$$\frac{\overline{AC_3}}{\overline{C_3B}} \cdot \frac{\overline{BA_3}}{\overline{A_3C}} \cdot \frac{\overline{CB_3}}{\overline{B_3A}} = \frac{\tan 2\alpha}{\tan 2\beta} \cdot \frac{\tan 2\beta}{\tan 2\gamma} \cdot \frac{\tan 2\gamma}{\tan 2\alpha} = 1.$$

5.115. Let us solve a more general heading b). First, let us prove that lines AA_1, BB_1 and CC_1 meet at one point. Let the circumscribed circles of triangles A_1BC and AB_1C

intersect at point O. Then

$$\begin{aligned}\angle(BO, OA) &= \angle(BO, OC) + \angle(OC, OA) = \angle(BA_1, A_1C) + \angle(CB_1, B_1A) = \\ &= \angle(BA, AC_1) + \angle(C_1B, BA) = \angle(C_1B, AC_1),\end{aligned}$$

i.e., the circumscribed circle of triangle ABC_1 also passes through point O. Hence,

$$\angle(AO, OA_1) = \angle(AO, OB) + \angle(BO, OA_1) = \angle(AC_1, C_1B + \angle(BC, CA_1) = 0^\circ,$$

i.e., line AA_1 passes through point O. We similarly prove that lines BB_1 and CC_1 pass through point O.

Now, let us prove that point O coincides with point P we are looking for. Since $\angle BAP = \angle A - \angle CAP$, the equality $\angle ABP = \angle CAP$ is equivalent to the equality $\angle BAP + \angle ABP = \angle A$, i.e., $\angle APB = \angle B + \angle C$. For point O the latter equality is obvious since it lies on the circumscribed circle of triangle ABC_1.

5.116. a) Let us prove that $\smile AB = \smile B_1C_1$, i.e., $AB = B_1C_1$. Indeed, $\smile AB = \smile AC_1 + \smile C_1B$ and $\smile C_1B = \smile AB_1$; hence, $\smile AB = \smile AC_1 + \smile AB_1 = \smile B_1C_1$.

b) Let us assume that triangles ABC and $A_1B_1C_1$ are inscribed in one circle, where triangle ABC is fixed and triangle $A_1B_1C_1$ rotates. Lines AA_1, BB_1 and CC_1 meet at one point for not more than one position of triangle $A_1B_1C_1$, see Problem 7.20 b). We can obtain 12 distinct families of triangles $A_1B_1C_1$: triangles ABC and $A_1B_1C_1$ can be identified after a rotation or an axial symmetry; moreover, there are 6 distinct ways to associate symbols A_1, B_1 and C_1 to the vertices of the triangle.

From these 12 families of triangles 4 families can never produce the desired point P. For similarly oriented triangles the cases

$$\triangle ABC = \triangle A_1C_1B_1, \quad \triangle ABC = \triangle C_1B_1A_1, \quad \triangle ABC = \triangle B_1A_1C_1$$

are excluded: for example, if $\triangle ABC = \triangle A_1C_1B_1$, then point P is the intersection point of line $BC = B_1C_1$ with the tangent to the circle at point $A = A_1$; in this case triangles ABC and $A_1B_1C_1$ coincide.

For differently oriented triangles the case $\triangle ABC = \triangle A_1B_1C_1$ is excluded: in this case $AA_1 \parallel BB_1 \parallel CC_1$.

Remark. Brokar's points correspond to differently oriented triangles; for the first Brokar's point $\triangle ABC = \triangle B_1C_1A_1$ and for the second Brokar's point we have $\triangle ABC = \triangle C_1A_1B_1$.

5.117. a) Since $PC = \frac{AC \sin\angle CAP}{\sin\angle APC}$ and $PC = \frac{BC \sin\angle CBP}{\sin\angle BPC}$, it follows that

$$\frac{\sin\varphi\sin\beta}{\sin\gamma} = \frac{\sin(\beta - \varphi)\sin\alpha}{\sin\beta}.$$

Taking into account that

$$\sin(\beta - \gamma) = \sin\beta\cos\varphi - \cos\beta\sin\varphi$$

we get $\cot\varphi = \cot\beta + \frac{\sin\beta}{\sin\alpha\sin\gamma}$. It remains to notice that

$$\sin\beta = \sin(\alpha + \gamma) = \sin\alpha\cos\gamma + \sin\gamma\cos\alpha.$$

b) For the second Brokar's angle we get precisely the same expression as in heading a). It is also clear that both Brokar's angles are acute ones.

c) Since $\angle A_1BC = \angle BCA$ and $\angle BCA_1 = \angle CAB$, it follows that $\triangle CA_1B \sim \triangle ABC$. Therefore, Brokar's point P lies on segment AA_1 (cf. Problem 5.115 b)).

5.118. a) By Problem 10.38 a)

$$\cot\varphi = \cot\alpha + \cot\beta + \cot\gamma \geq \sqrt{3} = \cot 30^\circ;$$

hence, $\varphi \leq 30^\circ$.

b) Let P be the first Brokar's point of triangle ABC. Point M lies inside (or on the boundary of) one of the triangles ABP, BCP and CAP. If, for example, point M lies inside triangle ABP, then $\angle ABM \leq \angle ABP \leq 30°$.

5.119. Lines A_1B_1, B_1C_1 and C_1A_1 are the midperpendiculars to segments AQ, BQ and CQ, respectively. Therefore, we have, for instance, $\angle B_1A_1C_1 = 180° - \angle AQC = \angle A$. For the other angles the proof is similar.

Moreover, lines A_1O, B_1O and C_1O are the midperpendiculars to segments CA, AB and BC, respectively. Hence, acute angles $\angle OA_1C_1$ and $\angle ACQ$, for example, have pairwise perpendicular sides and, consecutively, they are equal. Similar arguments show that $\angle OA_1C_1 = \angle OB_1A_1 = \angle OC_1B_1 = \varphi$, where φ is the Brokar's angle of triangle ABC.

5.120. By the law of sines

$$R_1 = \frac{AB}{2\sin\angle APB},\quad R_2 = \frac{BC}{2\sin\angle BPC} \quad\text{and}\quad R_3 = \frac{CA}{2\sin\angle CPA}.$$

It is also clear that

$$\sin\angle APB = \sin\angle A,\quad \sin\angle BPC = \sin\angle B \;\text{ and }\; \sin\angle CPA = \sin\angle C.$$

5.121. Triangle ABC_1 is an isosceles one and the angle at its base AB is equal to Brokar's angle φ. Hence, $\angle(PC_1, C_1Q) = \angle(BC_1, C_1A) = 2\varphi$. Similarly

$$\angle(PA_1, A_1Q) = \angle(PB_1, B_1Q) = \angle(PC_1, C_1Q) = 2\varphi.$$

5.122. Since $\angle CA_1B_1 = \angle A + \angle AB_1A_1$ and $\angle AB_1A_1 = \angle CA_1C_1$, we have $\angle B_1A_1C_1 = \angle A$. We similarly prove that the remaining angles of triangles ABC and $A_1B_1C_1$ are equal.

The circumscribed circles of triangles AA_1B_1, BB_1C_1 and CC_1A_1 meet at one point O. (Problem 2.80 a). Clearly, $\angle AOA_1 = \angle AB_1A_1 = \varphi$. Similarly, $\angle BOB_1 = \angle COC_1 = \varphi$. Hence, $\angle AOB = \angle A_1OB_1 = 180° - \angle A$. Similarly, $\angle BOC = 180° - \angle B$ and $\angle COA = 180° - \angle C$, i.e., O is the first Brokar's point of both triangles. Hence, the rotational homothety by angle φ with center O and coefficient $\frac{AO}{A_1O}$ sends triangle $A_1B_1C_1$ to triangle ABC.

5.123. By the law of sines $\frac{AB}{BM} = \frac{\sin\angle AMB}{\sin\angle BAM}$ and $\frac{AB}{BN} = \frac{\sin\angle ANB}{\sin\angle BAN}$. Hence,

$$\frac{AB^2}{BM\cdot BN} = \frac{\sin\angle AMB\sin\angle ANB}{\sin\angle BAM\sin\angle BAN} = \frac{\sin\angle AMC\sin\angle ANC}{\sin\angle CAN\sin\angle CAM} = \frac{AC^2}{CM\cdot CN}.$$

5.124. Since $\angle BAS = \angle CAM$, we have

$$\frac{BS}{CM} = \frac{S_{BAS}}{S_{CAM}} = \frac{AB\cdot AS}{AC\cdot AM},$$

i.e., $\frac{AS}{AM} = \frac{2b\cdot BS}{ac}$. It remains to observe that, as follows from Problems 5.123 and 12.11 a), $BS = \frac{ac^2}{b^2+c^2}$ and $2AM = \sqrt{2b^2 + 2c^2 - a^2}$.

5.125. The symmetry through the bisector of angle A sends segment B_1C_1 into a segment parallel to side BC, it sends line AS to line AM, where M is the midpoint of side BC.

5.126. On segments BC and BA, take points A_1 and C_1, respectively, so that $A_1C_1 \parallel BK$. Since $\angle BAC = \angle CBK = \angle BA_1C_1$, segment A_1C_1 is antiparallel to side AC. On the other hand, by Problem 3.31 b) line BD divides segment A_1C_1 in halves.

5.127. It suffices to make use of the result of Problem 3.30.

5.128. Let AP be the common chord of the considered circles, Q the intersection point of lines AP and BC. Then

$$\frac{BQ}{AB} = \frac{\sin\angle BAQ}{\sin\angle AQB} \quad\text{and}\quad \frac{AC}{CQ} = \frac{\sin\angle AQC}{\sin\angle CAQ}.$$

Hence, $\frac{BQ}{CQ} = \frac{AB\sin\angle BAP}{AC\sin\angle CAP}$. Since AC and AB are tangents to circles S_1 and S_2, it follows that $\angle CAP = \angle ABP$ and $\angle BAP = \angle ACP$ and, therefore, $\angle APB = \angle APC$. Hence,

$$\frac{AB}{AC} = \frac{AB}{AP}\cdot\frac{AP}{AC} = \frac{\sin\angle APB}{\sin\angle ABP}\cdot\frac{\sin\angle ACP}{\sin\angle APC} = \frac{\sin\angle ACP}{\sin\angle ABP} = \frac{\sin\angle BAP}{\sin\angle CAP}.$$

It follows that $\frac{BQ}{CQ} = \frac{AB^2}{AC^2}$.

5.129. Let S be the intersection point of lines AX and BC. Then $\frac{AS}{AB} = \frac{CS}{CX}$ and $\frac{AS}{AC} = BSBX$ and, therefore,

$$\frac{CS}{BS} = \frac{AC}{AB}\cdot\frac{XC}{XB}.$$

It remains to observe that $\frac{XC}{XB} = \frac{AC}{AB}$ (see the solution of Problem 7.16 a)).

5.130. Let L, M and N be the midpoints of segments CA, CB and CH. Since $\triangle BAC \sim \triangle CAH$, it follows that $\triangle BAM \sim \triangle CAN$ and, therefore, $\angle BAM = \angle CAN$. Similarly, $\angle ABL = \angle CBN$.

5.131. Let B_1C_1, C_2A_2 and A_3B_3 be given segments. Then triangles A_2XA_3, B_1XB_3 and C_1XC_2 are isosceles ones; let the lengths of their lateral sides be equal to a, b and c. Line AX divides segment B_1C_1 in halves if and only if this line contains a simedian. Hence, if X is Lemoin's point, then $a = b$, $b = c$ and $c = a$. And if $B_1C_1 = C_2A_2 = A_3B_3$, then $b + c = c + a = a + b$ and, therefore, $a = b = c$.

5.132. Let M be the intersection point of medians of triangle ABC; let a_1, b_2, c_1 and a_2, b_2, c_2 be the distances from points K and M, respectively, to the sides of the triangle. Since points K and M are isogonally conjugate, $a_1a_2 = b_1b_2 = c_1c_2$. Moreover, $aa_2 = bb_2 = cc_2$ (cf. Problem 4.1). Therefore, $\frac{a}{a_1} = \frac{b}{b_1} = \frac{c}{c_1}$. Making use of this equality and taking into account that areas of triangles A_1B_1K, B_1C_1K and C_1A_1K are equal to $\frac{a_1b_1c}{4R}$, $\frac{b_1c_1a}{4R}$ and $\frac{c_1a_1b}{4R}$, respectively, where R is the radius of the circumscribed circle of triangle ABC, we deduce that the areas of these triangles are equal. Moreover, point K lies inside triangle $A_1B_1C_1$. Therefore, K is the intersection point of medians of triangle $A_1B_1C_1$ (cf. Problem 4.2).

5.133. Medians of triangle $A_1B_1C_1$ intersect at point K (Problem 5.132); hence, the sides of triangle ABC are perpendicular to the medians of triangle $A_1B_1C_1$. After a rotation through an angle of 90° the sides of triangle ABC become pairwise parallel to the medians of triangle $A_1B_1C_1$ and, therefore, the medians of triangle ABC become parallel to the corresponding sides of triangle $A_1B_1C_1$ (cf. Problem 13.2). Hence, the medians of triangle ABC are perpendicular to the corresponding sides of triangle $A_1B_1C_1$.

5.134. Let A_2, B_2 and C_2 be the projections of point K to lines BC, CA and AB, respectively. Then $\triangle A_1B_1C_1 \sim \triangle A_2B_2C_2$ (Problem 5.100) and K is the intersection point of medians of triangle $A_2B_2C_2$ (Problem 5.132). Hence, the similarity transformation that sends triangle $A_2B_2C_2$ to triangle $A_1B_1C_1$ sends point K to the intersection point M of medians of triangle $A_1B_1C_1$. Moreover, $\angle KA_2C_2 = \angle KBC_2 = \angle B_1A_1K$, i.e., points K and M are isogonally conjugate with respect to triangle $A_1B_1C_1$ and, therefore, K is Lemoin's point of triangle $A_1B_1C_1$.

5.135. Let K be Lemoin's point of triangle ABC; let A_1, B_1 and C_1 be the projections of point K on the sides of triangle ABC; let L be the midpoint of segment B_1C_1 and N the intersection point of line KL and median AM; let O be the midpoint of segment AK (Fig. 61). Points B_1 and C_1 lie on the circle with diameter AK, hence, by Problem 5.132 $OL \perp B_1C_1$. Moreover, $AN \perp B_1C_1$ (Problem 5.133) and O is the midpoint of segment AK, consequently, OL is the midline of triangle AKN and $KL = LN$. Therefore, K is the midpoint of segment A_1N. It remains to notice that the homothety with center M that sends N to A sends segment NA_1 to height AH.



Figure 61 (Sol. 5.135)

Chapter 6. POLYGONS

Background

1) A polygon is called *a convex* one if it lies on one side of any line that connects two of its neighbouring vertices.

2) A convex polygon is called *a circumscribed* one if all its sides are tangent to a circle. A convex quadrilateral is a circumscribed one if and only if $AB + CD = BC + AD$.

A convex polygon is called *an inscribed* one if all its vertices lie on one circle. *A convex quadrilateral is an inscribed one if and only if*

$$\angle ABC + \angle CDA = \angle DAB + \angle BCD.$$

3) A convex polygon is called *a regular* one if all its sides are equal and all its angles are also equal.

A convex n-gon is a regular one if and only if under a rotation by the angle of $\frac{2\pi}{n}$ with center at point O it turns into itself. This point O is called *the center* of the regular polygon.

Introductory problems

1. Prove that a convex quadrilateral $ABCD$ can be inscribed into a circle if and only if $\angle ABC + \angle CDA = 180^\circ$.

2. Prove that a circle can be inscribed in a convex quadrilateral $ABCD$ if and only if $AB + CD = BC + AD$.

3. a) Prove that the axes of symmetry of a regular polygon meet at one point.

b) Prove that a regular $2n$-gon has a center of symmetry.

4. a) Prove that the sum of the angles at the vertices of a convex n-gon is equal to $(n-2) \cdot 180^\circ$.

b) A convex n-gon is divided by nonintersecting diagonals into triangles. Prove that the number of these triangles is equal to $n - 2$.

§1. The inscribed and circumscribed quadrilaterals

6.1. Prove that if the center of the circle inscribed in a quadrilateral coincides with the intersection point of the quadrilateral's diagonals, then this quadrilateral is a rhombus.

6.2. Quadrilateral $ABCD$ is circumscribed about a circle centered at O. Prove that $\angle AOB + \angle COD = 180^\circ$.

6.3. Prove that if there exists a circle tangent to all the sides of a convex quadrilateral $ABCD$ and a circle tangent to the extensions of all its sides then the diagonals of such a quadrilateral are perpendicular.

6.4. A circle singles out equal chords on all the four sides of a quadrilateral. Prove that a circle can be inscribed into this quadrilateral.

6.5. Prove that if a circle can be inscribed into a quadrilateral, then the center of this circle lies on one line with the centers of the diagonals.

6.6. Quadrilateral $ABCD$ is circumscribed about a circle centered at O. In triangle AOB heights AA_1 and BB_1 are drawn. In triangle COD heights CC_1 and DD_1 are drawn. Prove that points A_1, B_1, C_1 and D_1 lie on one line.

6.7. The angles at base AD of trapezoid $ABCD$ are equal to 2α and 2β. Prove that the trapezoid is a circumscribed one if and only if $\frac{BC}{AD} = \tan\alpha\tan\beta$.

6.8. In triangle ABC, segments PQ and RS parallel to side AC and a segment BM are drawn as plotted on Fig. 62. Trapezoids $RPKL$ and $MLSC$ are circumscribed ones. Prove that trapezoid $APQC$ is also a circumscribed one.



Figure 62 (6.8)

6.9. Given convex quadrilateral $ABCD$ such that rays AB and CD intersects at a point P and rays BC and AD intersect at a point Q. Prove that quadrilateral $ABCD$ is a circumscribed one if and only if one of the following conditions hold:

$$AB + CD = BC + AD, \quad AP + CQ = AQ + CP \quad BP + BQ = DP + DQ.$$

6.10. Through the intersection points of the extension of sides of convex quadrilateral $ABCD$ two lines are drawn that divide it into four quadrilaterals. Prove that if the quadrilaterals adjacent to vertices B and D are circumscribed ones, then quadrilateral $ABCD$ is also a circumscribed one.

6.11. Prove that the intersection point of the diagonals of a circumscribed quadrilateral coincides with the intersection point of the diagonals of the quadrilateral whose vertices are the tangent points of the sides of the initial quadrilateral with the inscribed circle.

* * *

6.12. Quadrilateral $ABCD$ is an inscribed one; H_c and H_d are the orthocenters of triangles ABD and ABC respectively. Prove that CDH_cH_d is a parallelogram.

6.13. Quadrilateral $ABCD$ is an inscribed one. Prove that the centers of the inscribed circles of triangles ABC, BCD, CDA and DAB are the vertices of a rectangle.

6.14. The extensions of the sides of quadrilateral $ABCD$ inscribed in a circle centered at O intersect at points P and Q and its diagonals intersect at point S.

a) The distances from points P, Q and S to point O are equal to p, q and s, respectively, and the radius of the circumscribed circle is equal to R. Find the lengths of the sides of triangle PQS.

b) Prove that the heights of triangle PQS intersect at point O.

* * *

6.15. Diagonal AC divides quadrilateral $ABCD$ into two triangles whose inscribed circles are tangent to diagonal AC at one point. Prove that the inscribed circles of triangle ABD and BCD are also tangent to diagonal BD at one point and their tangent points with the sides of the quadrilateral lie on one circle.

6.16. Prove that the projections of the intersection point of the diagonals of the inscribed quadrilateral to its sides are vertices of a circumscribed quadrilateral only if the projections do not lie on the extensions of the sides.

6.17. Prove that if the diagonals of a quadrilateral are perpendicular, then the projections of the intersection points of the diagonals on its sides are vertices of an inscribed quadrilateral.

See also Problem 13.33, 13.34, 16.4.

§2. Quadrilaterals

6.18. The angle between sides AB and CD of quadrilateral $ABCD$ is equal to φ. Prove that

$$AD^2 = AB^2 + BC^2 + CD^2 - 2(AB \cdot BC \cos B + BC \cdot CD \cos C + CD \cdot AB \cos \varphi).$$

6.19. In quadrilateral $ABCD$, sides AB and CD are equal and rays AB and DC intersect at point O. Prove that the line that connects the midpoints of the diagonals is perpendicular to the bisector of angle AOD.

6.20. On sides BC and AD of quadrilateral $ABCD$, points M and N, respectively, are taken so that $BM : MC = AN : ND = AB : CD$. Rays AB and DC intersect at point O. Prove that line MN is parallel to the bisector of angle AOD.

6.21. Prove that the bisectors of the angles of a convex quadrilateral form an inscribed quadrilateral.

6.22. Two distinct parallelograms $ABCD$ and $A_1B_1C_1D_1$ with corresponding parallel sides are inscribed into quadrilateral $PQRS$ (points A and A_1 lie on side PQ, points B and B_1 lie on side QR, etc.). Prove that the diagonals of the quadrilateral are parallel to the corresponding sides of the parallelograms.

6.23. The midpoints M and N of diagonals AC and BD of convex quadrilateral $ABCD$ do not coincide. Line MN intersects sides AB and CD at points M_1 and N_1. Prove that if $MM_1 = NN_1$, then $AD \parallel BC$.

6.24. Prove that two quadrilaterals are similar if and only if four of their corresponding angles are equal and the corresponding angles between the diagonals are also equal.

6.25. Quadrilateral $ABCD$ is a convex one; points A_1, B_1, C_1 and D_1 are such that $AB \parallel C_1D_1$ and $AC \parallel B_1D_1$, etc. for all pairs of vertices. Prove that quadrilateral $A_1B_1C_1D_1$ is also a convex one and $\angle A + \angle C_1 = 180°$.

6.26. From the vertices of a convex quadrilateral perpendiculars are dropped on the diagonals. Prove that the quadrilateral with vertices at the basis of the perpendiculars is similar to the initial quadrilateral.

6.27. A convex quadrilateral is divided by the diagonals into four triangles. Prove that the line that connects the intersection points of the medians of two opposite triangles is perpendicular to the line that connects the intersection points of the heights of the other two triangles.

6.28. The diagonals of the circumscribed trapezoid $ABCD$ with bases AD and BC intersect at point O. The radii of the inscribed circles of triangles AOD, AOB, BOC and COD are equal to r_1, r_2, r_3 and r_4, respectively. Prove that $\frac{1}{r_1} + \frac{1}{r_3} = \frac{1}{r_2} + \frac{1}{r_4}$.

6.29. A circle of radius r_1 is tangent to sides DA, AB and BC of a convex quadrilateral $ABCD$; a circle of radius r_2 is tangent to sides AB, BC and CD; the radii r_3 and r_4 are similarly defined. Prove that $\frac{AB}{r_1} + \frac{CD}{r_3} = \frac{BC}{r_2} + \frac{AD}{r_4}$.

6.30. A quadrilateral $ABCD$ is convex and the radii of the circles inscribed in triangles ABC, BCD, CDA and DAB are equal. Prove that $ABCD$ is a rectangle.

6.31. Given a convex quadrilateral $ABCD$ and the centers A_1, B_1, C_1 and D_1 of the circumscribed circles of triangles BCD, CDA, DAB and ABC, respectively. For quadrilateral $A_1B_1C_1D_1$ points A_2, B_2, C_2 and D_2 are similarly defined. Prove that quadrilaterals $ABCD$ and $A_2B_2C_2D_2$ are similar and their similarity coefficient is equal to

$$\frac{1}{4}\left|(\cot A+\cot C)(\cot B+\cot D)\right|.$$

6.32. Circles whose diameters are sides AB and CD of a convex quadrilateral $ABCD$ are tangent to sides CD and AB, respectively. Prove that $BC \parallel AD$.

6.33. Four lines determine four triangles. Prove that the orthocenters of these triangles lie on one line.

§3. Ptolemy's theorem

6.34. Quadrilateral $ABCD$ is an inscribed one. Prove that

$$AB\cdot CD+AD\cdot BC=AC\cdot BD \quad \text{(Ptolemy's theorem).}$$

6.35. Quadrilateral $ABCD$ is an inscribed one. Prove that

$$\frac{AC}{BD}=\frac{AB\cdot AD+CB\cdot CD}{BA\cdot BC+DA\cdot DC}.$$

6.36. Let $\alpha=\frac{\pi}{7}$. Prove that

$$\frac{1}{\sin\alpha}=\frac{1}{\sin 2\alpha}+\frac{1}{\sin 3\alpha}.$$

6.37. The distances from the center of the circumscribed circle of an acute triangle to its sides are equal to d_a, d_b and d_c. Prove that $d_a+d_b+d_c=R+r$.

6.38. The bisector of angle $\angle A$ of triangle ABC intersects the circumscribed circle at point D. Prove that $AB+AC\leq 2AD$.

6.39. On arc $\smile CD$ of the circumscribed circle of square $ABCD$ point P is taken. Prove that $PA+PC=\sqrt{2}PB$.

6.40. Parallelogram $ABCD$ is given. A circle passing through point A intersects segments AB, AC and AD at points P, Q and R, respectively. Prove that

$$AP\cdot AB+AR\cdot AD=AQ\cdot AC.$$

6.41. On arc $\smile A_1A_{2n+1}$ of the circumscribed circle S of a regular $(2n+1)$-gon $A_1\dots A_{2n+1}$ a point A is taken. Prove that:

a) $d_1+d_3+\dots+d_{2n+1}=d_2+d_4+\dots+d_{2n}$, where $d_i=AA_i$;

b) $l_1+\dots+l_{2n+1}=l_2+\dots+l_{2n}$, where l_i is the length of the tangent drawn from point A to the circle of radius r tangent to S at point A_i (all the tangent points are simultaneously either inner or outer ones).

6.42. Circles of radii x and y are tangent to a circle of radius R and the distance between the tangent points is equal to a. Calculate the length of the following common tangent to the first two circles:

a) the outer one if both tangents are simultaneously either outer or inner ones;

b) the inner one if one tangent is an inner one and the other one is an outer one.

6.43. Circles α, β, γ and δ are tangent to a given circle at vertices A, B, C and D, respectively, of convex quadrilateral $ABCD$. Let $t_{\alpha\beta}$ be the length of the common tangent to circles α and β (the outer one if both tangent are simultaneously either inner or outer ones and the inner one if one tangent is an inner one and the other one is an outer one); $t_{\beta\gamma}$, $t_{\gamma\delta}$, etc. are similarly determined. Prove that

$$t_{\alpha\beta}t_{\gamma\delta} + t_{\beta\gamma}t_{\delta\alpha} = t_{\alpha\gamma}t_{\beta\delta} \qquad \text{(The \textit{generalized Ptolemy's theorem})}$$

See also Problem 9.67.

§4. Pentagons

6.44. In an equilateral (non-regular) pentagon $ABCDE$ we have angle $\angle ABC = 2\angle DBE$. Find the value of angle $\angle ABC$.

6.45. a) Diagonals AC and BE of a regular pentagon $ABCDE$ intersect at point K. Prove that the inscribed circle of triangle CKE is tangent to line BC.

b) Let a be the length of the side of a regular pentagon, d the length of its diagonal. Prove that $d^2 = a^2 + ad$.

6.46. Prove that a square can be inscribed in a regular pentagon so that the vertices of the square would lie on four sides of the pentagon.



Figure 63 (6.46)

6.47. Regular pentagon $ABCDE$ with side a is inscribed in circle S. The lines that pass through the pentagon's vertices perpendicularly to the sides form a regular pentagon with side b (Fig. 63). A side of a regular pentagon circumsribed about circle S is equal to c. Prove that $a^2 + b^2 = c^2$.

See also Problems 2.59, 4.9, 9.23, 9.44, 10.63, 10.67, 13.10, 13.56, 20.11.

§5. Hexagons

6.48. The opposite sides of a convex hexagon $ABCDEF$ are pairwise parallel. Prove that:

a) the area of triangle ACE constitutes not less than a half area of the hexagon.

b) the areas of triangles ACE and BDF are equal.

6.49. All the angles of a convex hexagon $ABCDEF$ are equal. Prove that

$$|BC - EF| = |DE - AB| = |AF - CD|.$$

6.50. The sums of the angles at vertices A, C, E and B, D, F of a convex hexagon $ABCDEF$ with equal sides are equal. Prove that the opposite sides of this hexagon are parallel.

6.51. Prove that if in a convex hexagon each of the three diagonals that connect the opposite vertices divides the area in halves then these diagonals intersect at one point.

6.52. Prove that if in a convex hexagon each of the three segments that connect the midpoints of the opposite sides divides the area in halves then these segments intersect at one point.

See also problems 2.11, 2.20, 2.46, 3.66, 4.6, 4.28, 4.31, 5.80, 9.45 a), 9.76–9.78, 13.3, 14.6, 18.22, 18.23.

§6. Regular polygons

6.53. The number of sides of a polygon $A_1 \dots A_n$ is odd. Prove that:

a) if this polygon is an inscribed one and all its angles are equal, then it is a regular polygon;

b) if this polygon is a circumscribed one and all its sides are equal, then it is a regular polygon.

6.54. All the angles of a convex polygon $A_1 \dots A_n$ are equal; an inner point O of the polygon is the vertex of equal angles that subtend all the polygon's sides. Prove that the polygon is a regular one.

6.55. A paper band of constant width is tied in a simple knot and then tightened in order to make the knot flat, cf. Fig. 64. Prove that the knot is of the form of a regular pentagon.



Figure 64 (6.55)

6.56. On sides AB, BC, CD and DA of square $ABCD$ equilateral triangles ABK, BCL, CDM and DAN are constructed inwards. Prove that the midpoints of sides of these triangles (which are not the sides of a square) and the midpoints of segments KL, LM, MN and NK form a regular 12-gon.

* * *

6.57. Does there exist a regular polygon the length of one of whose diagonal is equal to the sum of lengths of some other two diagonals?

6.58. A regular $(4k+2)$-gon is inscribed in a circle of radius R centered at O. Prove that the sum of the lengths of segments singled out by the legs of angle $\angle A_kOA_{k+1}$ on lines A_1A_{2k}, $A_2A_{2k-1}, \dots, A_kA_{k+1}$ is equal to R.

6.59. In regular 18-gon $A_1 \dots A_{18}$, diagonals A_aA_d, A_bA_e and A_cA_f are drawn. Let $k = a-b$, $p = b-c$, $m = c-d$, $q = d-e$, $n = e-f$ and $r = f-a$. Prove that the indicated diagonals intersect at one point in any of the following cases and only in these cases:

a) $\overrightarrow{k,m,n} = \overrightarrow{p,q,r}$;

b) $\overrightarrow{k,m,n} = \overrightarrow{1,2,7}$ and $\overrightarrow{p,q,r} = \overrightarrow{1,3,4}$;

c) $\overrightarrow{k,m,n} = \overrightarrow{1,2,8}$ and $\overrightarrow{p,q,r} = \overrightarrow{2,2,3}$.

Remark. The equality $\overrightarrow{k,m,n} = \overrightarrow{x,y,z}$ means that the indicated tuples of numbers coincide; the order in which they are written in not taken into account.

6.60. In a regular 30-gon three diagonals are drawn. For them define tuples $\overrightarrow{k,m,n}$ and $\overrightarrow{p,q,r}$ as in the preceding problem. Prove that if $\overrightarrow{k,m,n} = \overrightarrow{1,3,14}$ and $\overrightarrow{p,q,r} = \overrightarrow{2,2,8}$, then the diagonals intersect at one point.

6.61. In a regular n-gon ($n \geq 3$) the midpoints of all its sides and the diagonals are marked. What is the greatest number of marked points that lie on one circle?

6.62. The vertices of a regular n-gon are painted several colours so that the points of one colour are the vertices of a regular polygon. Prove that among these polygons there are two equal ones.

6.63. Prove that for $n \geq 6$ a regular $(n-1)$-gon is impossible to inscribe in a regular n-gon so that on every side of the n-gon except one there lies exactly one vertex of the $(n-1)$-gon.

* * *

6.64. Let O be the center of a regular n-gon $A_1 \dots A_n$ and X an arbitrary point. Prove that

$$\overrightarrow{OA_1} + \dots + \overrightarrow{OA_n} = \overrightarrow{0} \quad \text{and} \quad \overrightarrow{XA_1} + \dots + \overrightarrow{XA_n} = n\overrightarrow{XO}.$$

6.65. Prove that it is possible to place real numbers $x_1, \dots, x_n$ all distinct from zero in the vertices of a regular n-gon so that for any regular k-gon all vertices of which are vertices of the initial n-gon the sum of the numbers at the vertices of the k-gon is equal to zero.

6.66. Point A lies inside regular 10-gon $X_1 \dots X_{10}$ and point B outside it. Let $\mathbf{a} = \overrightarrow{AX_1} + \dots \overrightarrow{AX_{10}}$ and $\mathbf{b} = \overrightarrow{BX_1} + \dots \overrightarrow{BX_{10}}$. Is it possible that $|\mathbf{a}| > |\mathbf{b}|$?

6.67. A regular polygon $A_1 \dots A_n$ is inscribed in the circle of radius R centered at O; let X be an arbitrary point. Prove that

$$A_1X^2 + \dots + A_nX^2 = n(R^2 + d^2), \quad \text{where} \quad d = OX.$$

6.68. Find the sum of squares of the lengths of all the sides and diagonals of a regular n-gon inscribed in a circle of radius R.

6.69. Prove that the sum of distances from an arbitrary X to the vertices of a regular n-gon is the least if X is the center of the n-gon.

6.70. A regular n-gon $A_1 \dots A_n$ is inscribed in the circle of radius R centered at O; let $\mathbf{e}_i = \overrightarrow{OA_i}$ and $\mathbf{x} = \overrightarrow{OX}$ be an arbitrary vector. Prove that

$$\sum (\mathbf{e}_i, \mathbf{x})^2 = \frac{nR^2 \cdot OX^2}{2}.$$

6.71. Find the sum of the squared distances from the vertices of a regular n-gon inscribed in a circle of radius R to an arbitrary line that passes through the center of the n-gon.

6.72. The distance from point X to the center of a regular n-gon is equal to d and r is the radius of the inscribed circle of the n-gon. Prove that the sum of squared distances from point X to the lines that contain the sides of the n-gon is equal to $n\left(r^2 + \frac{d^2}{2}\right)$.

6.73. Prove that the sum of squared lengths of the projections of the sides of a regular n-gon to any line is equal to $\frac{1}{2}na^2$, where a is the length of the side of the n-gon.

6.74. A regular n-gon $A_1 \dots A_n$ is inscribed in a circle of radius R; let X be a point on this circle. Prove that

$$XA_1^4 + \dots + XA_n^4 = 6nR^4.$$

6.75. a) A regular n-gon $A_1 \dots A_n$ is inscribed in the circle of radius 1 centered at 0, let $\mathbf{e}_i = \overrightarrow{OA_i}$ and $\mathbf{u}$ an arbitrary vector. Prove that $\sum (\mathbf{u}, \mathbf{e}_i)\mathbf{e}_i = \frac{1}{2}n\mathbf{u}$.

b) From an arbitrary point X perpendiculars $XA_1, \dots, XA_n$ are dropped to the sides (or their extensions) of a regular n-gon. Prove that $\sum \overrightarrow{XA_i} = \frac{1}{2}n\overrightarrow{XO}$, where O is the center of the n-gon.

6.76. Prove that if the number n is not a power of a prime, then there exists a convex n-gon with sides of length 1, 2, $\dots$, n, all the angles of which are equal.

See also Problems 2.9, 4.59, 4.62, 6.36, 6.41, 6.45–6.47, 9.83, 9.84, 11.46, 11.48, 17.31, 18.30, 19.47, 23.8, 24.2.

§7. The inscribed and circumscribed polygons

6.77. On the sides of a triangle three squares are constructed outwards. What should be the values of the angles of the triangle in order for the six vertices of these squares distinct from the vertices of the triangle belong to one circle?

6.78. A $2n$-gon $A_1 \dots A_{2n}$ is inscribed in a circle. Let $p_1, \dots, p_{2n}$ be the distances from an arbitrary point M on the circle to sides $A_1A_2, A_2A_3, \dots, A_{2n}A_1$. Prove that $p_1p_3 \dots p_{2n-1} = p_2p_4 \dots p_{2n}$.

6.79. An inscribed polygon is divided by nonintersecting diagonals into triangles. Prove that the sum of radii of all the circles inscribed in these triangles does not depend on the partition.

6.80. Two n-gons are inscribed in one circle and the collections of the length of their sides are equal but the corresponding sides are not necessarily equal. Prove that the areas of these polygons are equal.

6.81. Positive numbers $a_1, \dots, a_n$ are such that $2a_i < a_1 + \dots + a_n$ for all $i = 1, \dots, n$. Prove that there exists an inscribed n-gon the lengths of whose sides are equal to $a_1, \dots, a_n$.

* * *

6.82. A point inside a circumscribed n-gon is connected by segments with all the vertices and tangent points. The triangles formed in this way are alternately painted red and blue. Prove that the product of areas of red triangles is equal to the product of areas of blue triangles.

6.83. In a $2n$-gon (n is odd) $A_1 \dots A_{2n}$ circumscribed about a circle centered at O the diagonals $A_1A_{n+1}, A_2A_{n+2}, \dots, A_{n-1}A_{2n-1}$ pass through point O. Prove that the diagonals A_nA_{2n} also passes through point O.

6.84. A circle of radius r is tangent to the sides of a polygon at points $A_1, \dots, A_n$ and the length of the side on which point A_i lies is equal to a_i. The distance from point X to the center of the circle is equal to d. Prove that

$$a_1XA_1^2 + \dots + a_nXA_n^2 = P(r^2 + d^2),$$

where P is the perimeter of the polygon.

6.85. An n-gon $A_1 \dots A_n$ is circumscribed about a circle; l is an arbitrary tangent to the circle that does not pass through any vertex of the n-gon. Let a_i be the distance from vertex A_i to line l and b_i the distance from the tangent point of side A_iA_{i+1} with the circle to line l. Prove that:

a) the value $\frac{b_1 \dots b_n}{a_1 \dots a_n}$ does not depend on the choice of line l;

b) the value $\frac{a_1a_3 \dots a_{2m-1}}{a_2a_4 \dots a_{2m}}$ does not depend on the choice of line l if $n = 2m$.

6.86. Certain sides of a convex polygon are red; the other ones are blue. The sum of the lengths of the red sides is smaller than the semiperimeter and there is no pair of neighbouring blue sides. Prove that it is impossible to inscribe this polygon in a circle.

See also Problems 2.12, 4.39, 19.6.

§8. Arbitrary convex polygons

6.87. What is the greatest number of acute angles that a convex polygon can have?

6.88. How many sides whose length is equal to the length of the longest diagonal can a convex polygon have?

6.89. For which n there exists a convex n-gon one side of which is of length 1 and the lengths of the diagonals are integers?

6.90. Can a convex non-regular pentagon have exactly four sides of equal length and exactly four diagonals of equal lengths? Can the fifth side of such a pentagon have a common point with the fifth diagonal?

6.91. Point O that lies inside a convex polygon forms, together with each two of its vertices, an isosceles triangle. Prove that point O is equidistant from the vertices of this polygon.

See also Problems 4.49, 4.50, 9.82, 9.85, 9.86, 11.35, 13.14, 14.26, 16.8, 17.33, 17.34, 19.9, 23.13, 23.15.

§9. Pascal's theorem

6.92. Prove that the intersection points of the opposite sides (if these sides are not parallel) of an inscribed hexagon lie on one line. (*Pascal's theorem.*)

6.93. Point M lies on the circumscribed cirlce of triangle ABC; let R be an arbitrary point. Lines AR, BR and CR intersect the circumscribed circle at points A_1, B_1 and C_1, respectively. Prove that the intersection points of lines MA_1 and BC, MB_1 and CA, MC_1 and AB lie on one line and this line passes through point R.

6.94. In triangle ABC, heights AA_1 and BB_1 and bisectors AA_2 and BB_2 are drawn; the inscribed circle is tangent to sides BC and AC at points A_3 and B_3, respectively. Prove that lines A_1B_1, A_2B_2 and A_3B_3 either intersect at one point or are parallel.

6.95. Quadrilateral $ABCD$ is inscribed in circle S; let X be an arbitrary point, M and N be the other intersection points of lines XA and XD with circle S. Lines DC and AX, AB and DX intersect at points E and F, respectively. Prove that the intersection point of lines MN and EF lies on line BC.

6.96. Points A and A_1 that lie inside a circle centered at O are symmetric through point O. Rays AP and A_1P_1 are codirected, rays AQ and A_1Q_1 are also codirected. Prove that the intersection point of lines P_1Q and PQ_1 lies on line AA_1. (Points P, P_1, Q and Q_1 lie on the circle.)

6.97. On a circle, five points are given. With the help of a ruler only construct a sixth point on this circle.

6.98. Points $A_1, \dots, A_6$ lie on one circle and points K, L, M and N lie on lines A_1A_2, A_3A_4, A_1A_6 and A_4A_5, respectively, so that $KL \parallel A_2A_3$, $LM \parallel A_3A_6$ and $MN \parallel A_6A_5$. Prove that $NK \parallel A_5A_2$.

Problems for independent study

6.99. Prove that if $ABCD$ is a rectangle and P is an arbitrary point, then $AP^2+CP^2 = DP^2+BP^2$.

6.100. The diagonals of convex quadrilateral $ABCD$ are perpendicular. On the sides of the quadrilateral, squares centered at P, Q, R and S are constructed outwards. Prove that segment PR passes through the intersection point of diagonals AC and BD so that $PR = \frac{1}{2}(AC+BD)$.

6.101. On the longest side AC of triangle ABC, points A_1 and C_1 are taken so that $AC_1 = AB$ and $CA_1 = CB$ and on sides AB and BC points A_2 and C_2 are taken so that $AA_1 = AA_2$ and $CC_1 = CC_2$. Prove that quadrilateral $A_1A_2C_2C_1$ is an inscribed one.

6.102. A convex 7-gon is inscribed in a circle. Prove that if certain three of its angles are equal to 120° each, then some two of its sides are equal.

6.103. In plane, there are given a regular n-gon $A_1 \dots A_n$ and point P. Prove that from segments $A_1P, \dots, A_nP$ a closed broken line can be constructed.

6.104. Quadrilateral $ABCD$ is inscribed in circle S_1 and circumscribed about circle S_2; let K, L, M and N be tangent points of its sides with circle S_2. Prove that $KM \perp LN$.

6.105. Pentagon $ABCDE$ the lengths of whose sides are integers and $AB = CD = 1$ is circumscribed about a circle. Find the length of segment BK, where K is the tangent point of side BC with the circle.

6.106. Prove that in a regular $2n$-gon $A_1 \dots A_{2n}$ the diagonals A_1A_{n+2}, $A_{2n-1}A_3$ and $A_{2n}A_5$ meet at one point.

6.107. Prove that in a regular 24-gon $A_1 \dots A_{24}$ diagonals A_1A_7, A_3A_{11} and A_5A_{21} intersect at a point that lies on diameter A_4A_{16}.

Solutions

6.1. Let O be the center of the inscribed circle and the intersection point of the diagonals of quadrilateral $ABCD$. Then $\angle ACB = \angle ACD$ and $\angle BAC = \angle CAD$. Hence, triangles ABC and ADC are equal, since they have a common side AC. Therefore, $AB = DA$. Similarly, $AB = BC = CD = DA$.

6.2. Clearly,

$$\angle AOB = 180^\circ - \angle BAO - \angle ABO = 180^\circ - \frac{\angle A + \angle B}{2}$$

and $\angle COD = 180^\circ - \frac{\angle C + \angle D}{2}$. Hence,

$$\angle AOB + \angle COD = 360^\circ - \frac{\angle A + \angle B + \angle C + \angle D}{2} = 180^\circ.$$

6.3. Let us consider two circles tangent to the sides of the given quadrilateral and their extensions. The lines that contain the sides of the quadrilateral are the common inner and outer tangents to these circles. The line that connects the midpoints of the circles contains a diagonal of the quadrilateral and besides it is an axis of symmetry of the quadrilateral. Hence, the other diagonal is perpendicular to this line.

6.4. Let O be the center of the given circle, R its radius, a the length of chords singled out by the circle on the sides of the quadrilateral. Then the distances from point O to the sides of the quadrilateral are equal to $\sqrt{R^2 - \frac{a^2}{4}}$, i.e., point O is equidistant from the sides of the quadrilateral and is the center of the inscribed circle.

6.5. For a parallelogram the statement of the problem is obvious therefore, we can assume that lines AB and CD intersect. Let O be the center of the inscribed circle of quadrilateral $ABCD$; let M and N be the midpoints of diagonals AC and BD. Then

$$S_{ANB} + S_{CND} = S_{AMB} + S_{CMD} = S_{AOB} + S_{COD} = \frac{S_{ABCD}}{2}.$$

It remains to make use of the result of Problem 7.2.

6.6. Let the inscribed circle be tangent to sides DA, AB and BC at points M, H and N, respectively. Then OH is a height of triangle AOB and the symmetries through lines AO and BO sends point H into points M and N, respectively. Hence, by Problem 1.57 points A_1 and B_1 lie on line MN. Similarly, points C_1 and D_1 lie on line MN.

6.7. Let r be the distance from the intersection point of bisectors of angles A and D to the base AD, let r' be the distance from the intersection point of bisectors of angles B and

C to base BC. Then $AD = r(\cot\alpha + \cot\beta)$ and $BC = r'(\tan\alpha + \tan\beta)$. Hence, $r = r'$ if and only if

$$\frac{BC}{AD} = \frac{\tan\alpha + \tan\beta}{\cot\alpha\cot\beta} = \tan\alpha \cdot \tan\beta.$$

6.8. Let $\angle A = 2\alpha$, $\angle C = 2\beta$ and $\angle BMA = 2\varphi$. By Problem 6.7, $\frac{PK}{RL} = \frac{\tan\alpha}{\tan\varphi}$ and $\frac{LS}{MC} = \cot\varphi\tan\beta$. Since $\frac{PQ}{RS} = \frac{PK}{RL}$ and $\frac{RS}{AC} = \frac{LS}{MC}$, it follows that

$$\frac{PQ}{AC} = \frac{PK}{RL}\frac{LS}{MC} = \tan\alpha\tan\beta.$$

Hence, trapezoid $APQC$ is a circumscribed one.

6.9. First, let us prove that if quadrilateral $ABCD$ is a circumscribed one, then all the conditions take place. Let K, L, M and N be the tangent points of the inscribed circle with sides AB, BC, CD and DA. Then

$$\begin{gathered} AB + CD = AK + BK + CM + DM = AN + BL + CL + DN = BC + AD, \\ AP + CQ = AK + PK + QL - CL = AN + PM + QN - CM = AQ + CP, \\ BP + BQ = AP - AB + BC + CQ = (AP + CQ) + (BC - AB) = \\ AQ + CP + CD - AD = DP + DQ. \end{gathered}$$

Now, let us prove, for instance, that if $BP + BQ = DP + DQ$, then quadrilateral $ABCD$ is a circumscribed one. For this let us consider the circle tangent to side BC and rays BA and CD. Assume that line AD is not tangent to this circle; let us shift this line in order for it to touch the circle (Fig. 65).



Figure 65 (Sol. 6.9)

Let S be a point on line AQ such that $Q'S \parallel DD'$. Since $BP + BQ = DP + DQ$ and $BP + BQ' = D'P + D'Q'$, it follows that $QS + SQ' = QQ'$. Contradiction.

In the other two cases the proof is similar.

6.10. Let rays AB and DC intersect at point P, let rays BC and AD intersect at point Q; let the given lines passing through points P and Q intersect at point O. By Problem 6.9 we have $BP + BQ = OP + OQ$ and $OP + OQ = DP + DQ$. Hence, $BP + BQ = DP + DQ$ and, therefore, quadrilateral $ABCD$ is a circumscribed one.

6.11. Let sides AB, BC, CD and DA of quadrilateral $ABCD$ be tangent of the inscribed circle at points E, F, G and H, respectively. First, let us show that lines FH, EG and AC intersect at one point. Denote the points at which lines FH and EG intersect line AC by M and M', respectively. Since $\angle AMH = \angle BFM$ as angles between the tangents and chord HF, it follows that $\sin\angle AHM = \sin\angle CFM$. Hence,

$$\frac{AM \cdot MH}{FM \cdot MC} = \frac{S_{AMH}}{S_{FMC}} = \frac{AH \cdot MH}{FC \cdot FM},$$

i.e., $\frac{AM}{MC} = \frac{AH}{FC}$. Similarly,

$$\frac{AM'}{M'C} = \frac{AE}{CG} = \frac{AH}{FC} = \frac{AM}{MC};$$

hence, $M = M'$, i.e., lines FH, EG and AC intersect at one point.

Similar arguments show that lines FH, EG and BD intersect at one point and therefore, lines AC, BD, FH and EG intersect at one point.

6.12. Segments CH_d and DH_c are parallel because they are perpendicular to line BC. Moreover, since $\angle BCA = \angle BDA = \varphi$, the lengths of these segments are equal to $AB|\cot\varphi|$, cf. Problem 5.45 b).

6.13. Let O_a, O_b, O_c and O_d be the centers of the inscribed circles of triangles BCD, ACD, ABD and ABC, respectively. Since $\angle ADB = \angle ACB$, it follows that

$$\angle AO_cB = 90^\circ + \frac{\angle ADB}{2} = 90^\circ + \frac{\angle ACB}{2} = \angle AO_dB,$$

cf. Problem 5.3. Therefore, quadrilateral ABO_dO_c is an inscribed one, i.e.,

$$\angle O_cO_dB = 180^\circ - \angle O_cAB = 180^\circ - \frac{\angle A}{2}.$$

Similarly, $\angle O_aO_dB = 180^\circ - \frac{\angle C}{2}$. Since $\angle A + \angle C = 180^\circ$, it follows that $\angle O_cO_dB + \angle O_aO_bB = 270^\circ$ and, therefore, $\angle O_aO_dO_c = 90^\circ$. We similarly prove that the remaining angles of quadrilateral $O_aO_bO_cO_d$ are equal to 90°.

6.14. a) Let rays AB and DC intersect at point P and rays BC and AD intersect at point Q. Let us prove that point M at which the circumscribed circles of triangles CBP and CDQ intersect lies on segment PQ. Indeed,

$$\angle CMP + \angle CMQ = \angle ABC + \angle ADC = 180^\circ.$$

Hence, $PM + QM = PQ$ and since

$$PM \cdot PQ = PD \cdot PC = p^2 - R^2 \quad \text{and } QM \cdot PQ = QD \cdot QA = q^2 - R^2,$$

it follows that $PQ^2 = PM \cdot PQ + QM \cdot PQ = p^2 + q^2 - 2R^2$. Let N be the intersection point of the circumscribed circles of triangles ACP and ABS. Let us prove that point S lies on segment PN. Indeed,

$$\angle ANP = \angle ACP = 180^\circ - \angle ACD = 180^\circ - \angle ABD = \angle ANS.$$

Hence, $PN - SN = PS$ and since

$$PN \cdot PS = PA \cdot PB = p^2 - R^2 \quad \text{and } SN \cdot PS = SA \cdot SC = R^2 - s^2,$$

it follows that

$$PS^2 = PN \cdot PS - SN \cdot PS = p^2 + s^2 - 2R^2.$$

Similarly, $QS^2 = q^2 + s^2 - 2R^2$.

b) By heading a)

$$PQ^2 - PS^2 = q^2 - s^2 = OQ^2 - OS^2.$$

Hence, $OP \perp QS$, cf. Problem 7.6. We similarly prove that $OQ \perp PS$ and $OS \perp PQ$.

6.15. Let the inscribed circles of triangles ABC and ACD be tangent to diagonal AC at points M and N, respectively. Then

$$AM = \frac{AC + AB - BC}{2} \quad \text{and} quad AN = \frac{AC + AD - CD}{2},$$

cf. Problem 3.2. Points M and N coincide if and only if $AM = AN$, i.e., $AB + CD = BC + AD$. Thus, if points M and N coincide, then quadrilateral $ABCD$ is a circumscribed one and similar arguments show that the tangent points of the inscribed circles of triangles ABD and BCD with the diagonal BD coincide.

Let the inscribed circle of triangle ABC be tangent to sides AB, BC and CA at points P, Q and M, respectively and the inscribed circle of triangle ACD be tangent to sides AC, CD and DA at points M, R and S, respectively. Since $AP = AM = AS$ and $CQ = CM = CR$, it follows that triangles APS, BPQ, CQR and DRS are isosceles ones; let α, β, γ and δ be the angles at the bases of these isosceles triangles. The sum of the angles of these triangles is equal to

$$2(\alpha+\beta+\gamma+\delta)+\angle A+\angle B+\angle C+\angle D;$$

hence, $\alpha+\beta+\gamma+\delta = 180^\circ$. Therefore,

$$\angle SPQ+\angle SRQ = 360^\circ-(\alpha+\beta+\gamma+\delta) = 180^\circ,$$

i.e., quadrilateral $PQRS$ is an inscribed one.

6.16. Let O be the intersection point of diagonals AC and BD; let A_1, B_1, C_1 and D_1 be the projections of O to sides AB, BC, CD and DA, respectively. Points A_1 and D_1 lie on the circle with diameter AO, hence, $\angle OA_1D_1 = \angle OAD_1$. Similarly, $\angle OA_1B_1 = \angle OBB_1$. Since $\angle CAD = \angle CBD$, we have: $\angle OA_1D_1 = \angle OA_1B_1$.

We similarly prove that B_1O, C_1O and D_1O are the bisectors of the angles of quadrilateral $A_1B_1C_1D_1$, i.e., O is the center of its inscribed circle.



Figure 66 (Sol. 6.17)

6.17. Let us make use of the notations on Fig. 66. The condition that quadrilateral $A_1B_1C_1D_1$ is an inscribed one is equivalent to the fact that $(\alpha+\beta)+(\gamma+\delta) = 180^\circ$ and the the fact that AC and BD are perpendicular is equivalent to the fact that $(\alpha_1+\delta_1)+(\beta_1+\gamma_1) = 180^\circ$. It is also clear that $\alpha = \alpha_1$, $\beta = \beta_1, \gamma = \gamma_1$ and $\delta = \delta_1$.

6.18. By the law of cosines

$$AD^2 = AC^2+CD^2-2AC\cdot CD\cos ACD, \quad AC^2 = AB^2+BC^2-2AB\cdot BC\cos B.$$

Since the length of the projection of segment AC to line l perpendicular to CD is equal to the sum of the lengths of projections of segments AB and BC to line l,

$$AC\cos ACD = AB\cos\varphi+BC\cos C.$$

6.19. Let $\angle AOD = 2\alpha$; then the distances from point O to the projections of the midpoints of diagonals AC and BD to the bisector of angle $\angle AOD$ are equal to $\frac{OA+OC}{2}\cos\alpha$ and $\frac{OB+OD}{2}\cos\alpha$, respectively. Since

$$OA+OC = AB+OB+OC = CD+OB+OC = OB+OD,$$

these projections coincide.

6.20. Let us complement triangles ABM and DCM to parallelograms $ABMM_1$ and $DCMM_2$. Since $AM_1 : DM_2 = BM : MC = AN : DN$, it follows that $\triangle ANM_1 \sim \triangle DNM_2$. Hence, point N lies on segment M_1M_2 and

$$MM_1 : MM_2 = AB : CD = AN : ND = M_1N : M_2N,$$

i.e., MN is the bisector of angle M_1MM_2.

6.21. Let a, b, c and d be (the lengths of) the bisectors of the angles at vertices A, B, C and D. We have to verify that $\angle(a,b) + \angle(c,d) = 0^\circ$. Clearly,

$$\angle(a,b) = \angle(a,AB) + \angle(AB,b) \quad \text{and} \quad \angle(c,d) = \angle(c,CD) + \angle(CD,d).$$

Since quadrilateral $ABCD$ is a convex one and

$$\angle(a,AB) = \frac{\angle(AD,AB)}{2}, \ \ \angle(AB,b) = \frac{\angle(AB,BC)}{2},$$
$$\angle(c,CD) = \frac{\angle(CB,CD)}{2}, \ \ \angle(CD,d) = \frac{\angle(CD,DA)}{2},$$

it follows that

$$\angle(a,b) + \angle(c,d) = \frac{\angle(AD,AB) + \angle(AB,BC) + \angle(CB,CD) + \angle(CD,DA)}{2} = \frac{360^\circ}{2} = 0^\circ$$

(see Background to Chapter 2).

6.22. Let, for definiteness, $AB > A_1B_1$. The parallel translation by vector $\overrightarrow{CB}$ sends triangle SD_1C_1 to $S'D_1'C_1'$ and segment CD to BA. Since $QA_1 : QA = A_1B_1 : AB = S'D_1' : S'A$, we see that $QS' \parallel A_1D_1'$. Hence, $QS \parallel AD$. Similarly, $PR \parallel AB$.

6.23. Suppose that lines AD and BC are not parallel. Let M_2, K, N_2 be the midpoints of sides AB, BC, CD, respectively. If $MN \parallel BC$, then $BC \parallel AD$, because $AM = MC$ and $BN = ND$. Therefore, let us assume that lines MN and BC are not parallel, i.e., $M_1 \neq M_2$ and $N_1 \neq N_2$. Clearly, $\overrightarrow{M_2M} = \frac{1}{2}\overrightarrow{BC} = \overrightarrow{NN_2}$ and $\overrightarrow{M_1M} = \overrightarrow{NN_1}$. Hence, $M_1M_2 \parallel N_1N_2$. Therefore, $KM \parallel AB \parallel CD \parallel KN$, i.e., $M = N$. Contradiction.

6.24. By a similarity transformation we can identify one pair of the corresponding sides of quadrilaterals, therefore, it suffices to consider quadrilaterals $ABCD$ and ABC_1D_1 whose points C_1 and D_1 lie on rays BC and AD and such that $CD \parallel C_1D_1$. Denote the intersection points of diagonals of quadrilaterals $ABCD$ and ABC$_1D_1$ by O and O_1, respectively.

Suppose that points C and D lie closer to points B and A, then points C_1 and D_1, respectively. Let us prove then that $\angle AOB > \angle AO_1B$. Indeed, $\angle C_1BA > \angle CAB$ and $\angle D_1BA > \angle DBA$, hence,

$$\angle AO_1B = 180^\circ - \angle C_1AB - \angle D_1BA < 180^\circ - \angle CAB - \angle DBA = \angle AOB.$$

We have obtained a contradiction and, therefore, $C_1 = C$, $D_1 = D$.

6.25. Any quadrilateral is determined up to similarity by the directions of its sides and diagonals. Therefore, it suffices to construct one example of a quadrilateral $A_1B_1C_1D_1$ with the required directions of sides and diagonals. Let O be the intersection point of diagonals AC and BD. On ray OA, take an arbitrary point D_1 and draw $D_1A_1 \parallel BC$, $A_1B_1 \parallel CD$ and $B_1C_1 \parallel DA$ (Fig. 67).